

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE											
CODE NO	ITEM	UNIT		ROADWAY 1000-2A 80% FEDERAL 20% STATE	STRUCTURE X371-15B 80% FEDERAL 20% STATE	ROADWAY 1000-2A 100% COUNTY	SIGNALS Y031-IF 80% FEDERAL 20% STATE	LIGHTING Y030-IE 80% FEDERAL 20% STATE							
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	316	316											
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	32	32											
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	5	5											
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	63	63											
• 80500200	SERVICE INSTALLATION, TYPE B	EACH	1				1								
• 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	1288				731	557							
• 81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	78				78								
• 81012900	CONDUIT IN TRENCH, 3 1/2" DIA., PVC	FOOT	174				174								
• 81021330	CONDUIT PUSHED, 2" DIA., PVC	FOOT	30				30								
• 81021350	CONDUIT PUSHED, 3" DIA., PVC	FOOT	180				180								
• 81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	627					627							
• 81300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 12" X 6"	EACH	4					4							
• 81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	6				6								
• 81400705	HANDHOLE, PORTLAND CEMENT CONCRETE (SPEC IAL)	EACH	1					1							
• 81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRET E	EACH	1				1								
• 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYP E USE) 1/C NO. 6	FOOT	4071				500	3571							
• 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1540				983	557							
• 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUN T, 250 WATT	EACH	2					2							
• 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUN T, 400 WATT	EACH	4					4							
• 83007100	LIGHT POLE, ALUMINUM, 35 FT. M.H., 4 FT. MAST ARM	EACH	2					2							
• 83600100	LIGHT POLE FOUNDATION	EACH	1					1							
• 84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVA GE	EACH	6					6							
• 84200700	LIGHTING FOUNDATION REMOVAL	EACH	4					4							
• 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	1					1							
• 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1				1								
• 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	221				221								
• 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2056.5				2056.5								

• SPECIALTY ITEMS

FILE NAME c:\projects\harmhw\m1sc.dgn	USER NAME = everacl	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 10/20/2000	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6758	(I-R), (I-VC)BR	PEORIA	142	9
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 68092	