



General Notes

After removal the handhole shall be filled to the bottom of the existing pavement, or proposed base course, in accordance with applicable portions of Article 207 of the Standard Specifications.

The remainder of the handhole shall be filled with class PV concrete to bottom of the proposed overlay or as directed by the Engineer.

Materials resulting from the removal of portions of the existing hand holes shall be disposed of in accordance with Article 202.03 of the Standard Specifications.

This work shall be paid for at the contract unit price per each for REMOVE EXISTING HANDHOLE and shall include all labor and materials necessary to complete the work.

FILE NAME =	USER NAME = laynedm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	REMOVE EXISTING HANDHOLE	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
S:\GEN\DRIFT\ST0&PLNS\Squad\68092 Airport Road\Lighting\airportroadlighting.dgn	DRAWN -	REVISED -	389			(1-RIRS (1-VCIBR	Peoria	142	106	
PLOT SCALE = 1/8" = 1'-0"	CHECKED -	REVISED -	CONTRACT NO. 68092							
PLOT DATE = 10/17/2009	DATE -	REVISED -	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							
SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____										