

DETECTOR LOOPS TYPE I

LOCATION	FOOT
IL 17	
Sta. 22+00	35
Sta. 27+40	35
Sta. 30+43	45
Sta. 35+89	<u>45</u>
Total	160

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

LOCATION	EACH
IL 17	
Sta. 6+23 to 65+59	69
IL 26	
Sta. 7+08 to 68+45	<u>440</u>
Total	509

RAISED REFLECTIVE PAVEMENT MARKERS

LOCATION	EACH
IL 17	
Sta. 6+23 to 65+59	69
IL 26	
Sta. 7+08 to 68+45	<u>440</u>
Total	509

WEATHER SENSOR UPGRADE & REPLACE

LOCATION	L SUM
IL 17	
EBL & WBL +/- Sta.7+21	1

SHORT TERM PAVEMENT MARKING

LOCATION	FOOT
IL 17	
Sta. 6+23 to 22+50	325
Sta. 27+15 to 46+44	386
Sta. 46+44 to 65+59	575
IL 26	
Sta. 7+08 to 174+31	5017
Sta. 176+21 to 315+85	4189
Sta. 315+85 to 333+10 bk	345
Sta. 68+45 to 85+20 (S. of IL 17)	335
Sta. 90+00 to 100+75 bk	<u>215</u>
Total	11387

WORK ZONE PAVEMENT MARKING REMOVAL

LOCATION	SQ FT
IL 17	
Sta. 6+23 to 22+50	540.2
Sta. 27+15 to 65+59	128.1
IL 26	
Sta. 7+08 to 174+31	557.4
Sta. 176+21 to 333+10 bk	523.0
Sta. 68+45 to 85+20 (S. of IL 17)	55.8
Sta. 90+00 to 100+75 bk	<u>35.8</u>
Total	1354.0

MOWING

LOCATION	UNIT
JOBSITE	406

HMA SURFACE REMOVAL - BUTT JOINT

LOCATION	SQ YD
IL 17	
Sta. 6+23 to 6+33	26.7
Sta. 22+40 to 22+50	46.7
Sta. 27+15 to 27+25	46.7
Sta. 65+29 to 65+59	86.7
IL 26	
Sta. 7+08 to 7+28	53.3
Sta. 174+01 to 174+31	80.0
Sta. 176+21 to 176+51	80.0
Sta. 90+00 to 90+10	37.8
Sta. 85+10 to 85+20	37.8
Sta. 68+45 to 68+55	<u>28.9</u>
Total	525.0

TEMPORARY RAMP

LOCATION	SQ YD
IL 17	
Sta. 6+23 to 6+30	18.7
Sta. 22+43 to 22+50	18.7
Sta. 27+15 to 27+22	18.7
Sta. 65+54 to 65+59	13.3
IL 26	
Sta. 7+08 to 7+13	13.3
Sta. 174+26 to 174+31	13.3
Sta. 176+21 to 176+26	13.3
Sta. 90+00 to 90+07	20.2
Sta. 85+13 to 85+20	20.2
Sta. 68+45 to 68+52	20.2
Side Roads	<u>560</u>
Total	730.0

FILE NAME =	USER NAME = longar	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	QUANTITIES NOT OTHERWISE SHOWN			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
S:\GEN\DRAF\STD&PLNS\Squad1\68560 IL2	N Leon\plans.dgn	DRAWN - ---	REVISED - ---		SCALE: -----	SHEET NO. -- OF --- SHEETS	STA. ----- TO STA. -----	649	1G,18CSRS-1,13RS-2,RS412,2RS-2	MARSHALL	15	7
PLOT SCALE = 286.8858 / / IN.	CHECKED - ---	REVISED - ---	REVISED - ---					CONTRACT NO. 68560				
PLOT DATE = 7/30/2008	DATE - -----	REVISED - ---	REVISED - ---					FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				