

EARTHWORK SCHEDULE

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	1YRS, 2ZRS-1	CRAWFORD	378	19
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

LOCATION	STATION	RT/LT	EARTH EXCAVATION	EARTH EXCAVATION (WIDENING)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EMBANKMENT REQUIRED	EMBANKMENT REQUIRED FOR ENTRANCES (SEE NOTE)	EARTH EXCAVATION AVAILABLE (ADJUSTED FOR SHRINKAGE - 25%)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION AND PLACEMENT
			M2020010	M2020050	M2021200	CU. M.	CU. M.	CU. M.	CU. M.	M2112500
RURAL										
	STA. 0+915 TO STA. 2+756.900	RT/LT	10207.7	497.3		4069.7	1120.3	8028.8	2838.8	3634.0
	STA. 1+970 (TR 1000)	RT.	173.3			44.0		130.0	86.0	23.8
			10381.0	497.3	0.0	4113.7	1120.3	8158.8	2924.8	3657.8
OBLONG										
	STA. 2+756.900 TO STA. 4+475	RT/LT	1253.7			1416.6		940.3	-476.4	9.7
	STA. 2+767.5 (TR 150)	LT.	74.9			28.2		56.2	28.0	
	STA. 2+892.1 (JOY STREET)	LT.	45.2			8.9		33.9	25.0	
	STA. 2+977.3 (MADISON STREET)	LT.	72.9			4.6		54.7	50.1	
	STA. 3+122.6 (JEFFERSON STREET)	LT.	63.0			2.9		47.3	44.4	
	STA. 3+122.6 (JEFFERSON STREET)	RT.	94.6			4.1		71.0	66.9	
	STA. 3+211.3 (WASHINGTON STREET)	LT.	16.5			5.1		12.4	7.3	
	STA. 3+211.3 (WASHINGTON STREET)	RT.	46.0			2.8		34.5	31.7	
	STA. 3+298.2 (JACKSON STREET)	LT.	45.7			4.3		34.3	30.0	
	STA. 3+298.2 (JACKSON STREET)	RT.	80.8			6.3		60.6	54.3	
	STA. 3+385.0 (WILSON STREET)	LT.	18.6			7.1		14.0	6.9	
	STA. 3+472.4 (ADAMS STREET)	RT.	3.1			9.4		2.3	-7.1	
	STA. 3+572.1 (RANGE STREET)	RT.	23.8			1.8		17.9	16.1	
	STA. 3+572.7 (RANGE STREET)	LT.	37.3			1.3		28.0	26.7	
	STA. 3+659.2 (GARFIELD STREET)	LT.	34.4			0.2		25.8	25.6	
	STA. 3+659.2 (GARFIELD STREET)	RT.	26.2			2.6		19.7	17.1	
	STA. 3+745.8 (GRANT STREET)	LT.	20.3			6.5		15.2	8.7	
	STA. 3+746 GRANT STREET)	RT.	47.2			5.6		35.4	29.8	
	STA. 3+832.3 (HARRISON STREET)	LT.	118.1			4.2		88.6	84.4	
	STA. 3+919 (TAYLOR STREET)	LT.	15.8			28.0		11.9	-16.2	
	STA. 3+919 (TAYLOR STREET)	RT.	16.6			38.5		12.5	-26.1	
	STA. 4+155.8 (ROOSEVELT STREET)	RT.	33.0			3.2		24.8	21.6	
			2187.7	0.0	0.0	1592.2	0.0	1640.8	48.5	9.7
RURAL										
	STA. 4+475 TO STA. 4+655	RT/LT	623.3	48.6		142.6	2066.7	503.9	-1705.4	300.6
	STA. 5+025 TO STA. 9+385	RT/LT	19226.4	1177.2		7737.8	6106.9	15302.7	1458.0	7666.1
	STA. 5+194.097 (TR300)	RT.	127.8			44.0		95.9	51.9	19.0
	STA. 6+444.9 (TR375)	LT.	68.8			72.5		51.6	-20.9	34.3
	STA. 6+446 (TR375)	RT.	57.5			45.8		43.1	-2.7	37.5
	STA. 7+687.148 (TR 450)	LT.	62.8			18.7		47.1	28.4	28.8
	STA. 7+687.148 (TR 450)	RT.	56.0			21.6		42.0	20.4	33.9
	STA. 8+910.897 (TR 525)	LT.	65.6			12.0		49.2	37.2	14.3
	STA. 9+580 TO STA. 15+545	RT/LT	37501.7	1610.6	675.1	12074.9	13226.3	29334.2	4032.9	11454.2
	STA. 10+125.278 (TR 600)	LT.	40.8			7.0		30.6	23.6	24.8
	STA. 10+125.278 (TR 600)	RT.	69.9			60.8		52.4	-8.4	25.3
	STA. 10+736.079 (FIREBAUGH)	RT.	53.7			16.8		40.3	23.5	21.1
	STA. 12+164.026 (TR725)	LT.	103.9			31.0		77.9	46.9	15.6
	STA. 12+164.026 (TR725)	RT.	123.8			14.0		92.9	78.9	8.0
	STA. 13+391.693 (TR800)	LT.	66.4			17.0		49.8	32.8	17.7
	STA. 13+391.693 (TR800)	RT.	155.2			3.0		116.4	113.4	30.8
	STA. 15+062.4 (TR900)	LT.	103.1			23.0		77.3	54.3	19.3
	STA. 15+062.4 (TR900)	RT.	63.6			3.0		47.7	44.7	25.0
			58570.2	2836.4	675.1	20345.5	21400.0	46054.9	4309.5	19776.2
URBAN										
	STA. 15+545 TO 16+016	RT/LT	2306.6	127.2		356.5	675.9	1825.4	792.9	720.9
	STA. 15+661.3 (PASADENA)	RT.	50.3			10.0		37.7	27.7	11.3
	STA. 15+773.3 (GLENDALE)	RT.	56.7			3.0		42.5	39.5	9.5
			2413.6	127.2	0.0	369.5	675.9	1905.6	860.2	741.7
TOTALS			73552.6	3460.8	675.1	26420.9	23196.2	57760.1	8143.0	24185.4
TOTALS ROUNDED FOR SUMMARY SHEET			73555	3465	680					24190

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center">SCHEDULE OF QUANTITIES</p> <p>SCALE NO SCALE DRAWN BY KOJ</p> <p>DATE OCTOBER 28, 2008 CHECKED BY LWJ</p>

PLOT DATE = 11/6/2008
 FILE NAME = H:\4420\Final\Plans\Drawings\0794533\SH1_014_sch_eil_schedules_V8.dgn

H. M. & G. NO. 4420