INDEX OF SHEETS

SHEET TITLE

SHEET NO.

LIST OF ILLINOIS DOT HIGHWAY STANDARDS

STANDARD TITLE

1	COVER SHEET	000001-05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
2	INDEX OF SHEETS, HIGHWAY STANDARDS	001001-02	AREAS OF REINFORCEMENT REBARS
_	AND GENERAL NOTES	001006	DECIMAL OF AN INCH AND OF A FOOT
3	SUMMARY OF QUANTITIES	280001-04	TEMPORARY EROSION CONTROL SYSTEMS
4	EXISTING & PROPOSED TYPICAL SECTIONS	420101-04	24' JOINTED PCC PAVEMENT
5-8	SCHEDULE OF QUANTITIES	420401-07	BRIDGE APPROACH PAVEMENT
9–10	ALIGNMENT, TIES, AND BENCHMARKS	424001-05	CURB RAMPS FOR SIDEWALKS
11-20	PLAN & PROFILE—WEST CORBIN STREET	515001-03	NAME PLATE FOR BRIDGES
21-26	GRADING PLAN-WEST CORBIN STREET		
27	TRAFFIC CONTROL	542301-02	PRECAST REINFORCED CONCRETE FLARED END SECTION
28-33	EROSION AND SEDIMENT CONTROL PLANS-WEST CORBIN STREET	542311 - Ol	GRATING FOR CONCRETE FLARED END SECTION (FOR
34-39	DRAINAGE AND UTILITIES PLAN-WEST CORBIN STREET		600mm (24") THRU 1350mm (54") PIPE)
40-42	RIGHT-OF-WAY PLANS	602301-02	INLET - TYPE A
40-42 - 43-44	PAVEMENT MARKING DETAILS	602306-02	inlet - Type B
 45		602401-02	MANHOLE TYPE A
	WETLAND PLANS	602701-02	MANHOLE STEPS
46-48	STORM SEWER PROFILES	604001-03	FRAME AND LIDS TYPE 1
49	SANITARY SEWER PROFILES	604006-04	FRAME AND GRATE TYPE 3
50-51	MISCELLANEOUS DETAILS	604011-04	FRAME AND GRATE TYPE 3V
52-81	BRIDGE PLANS	604036-02	GRATE TYPE 8
82-83	CULVERT PLAN AND PROFILES	60600104	CONCRETE CURB TYPE B AND COMBINATION CONCRETE
83-87	CULVERT DETAILS		CURB AND GUTTER
88-129	CROSS SECTIONS—WEST CORBIN STREET	606101-04	TYPE A GUTTER (INLET, OUTLET & ENTRANCE)
		609006-04	BRIDGE APPROACH PAVEMENT (DRAIN DETAIL)
		630001-08	STEEL PLATE BEAM GUARDRAIL
		631011-0 <i>5</i>	TRAFFIC BARRIER TERMINAL, TYPE 2
DELETED	SHEETS	631032-04	TRAFFIC BARRIER TERMINAL, TYPE 6A
/ DEACTED	,	665001-02	WOVEN WIRE FENCE
1	}		
		701400-0:3	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
SHEET A	JO, }	701401-05	LANE CLOSURE, FREEWAY/EXPRESSWAY
1 0 0	12 AA A7 A0	701901 -0	TRAFFIC CONTROL DEVISES
م رهی ک	43, 44, 47, 48 <i>}</i>	720001 - Ol	SIGN PANEL MOUNTING DETAILS
Contraction of the second	REVISED 1-6-09	720006-02	SIGN PANEL ERECTION DETAILS
	1)202320 7 0	720011 -01	METAL POST FOR SIGNS, MARKERS & DELINEATORS
		B.L.R. 10-6	PCC PAVEMENT SPECIAL
		B.R.R. 21-3	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES F
		-	CONSTRUCTION ON RURAL LOCAL HIGHWAYS

STANDARD NO.

ABBREVIATIONS AND SYMBOLS

 TBR&R
 TO
 BE
 REMOVED AND RE-ERECTED

 REC
 TO
 BE
 RECONSTRUCTED

 TBADJ
 TO
 BE
 ADJUSTED

 TBA
 TO
 BE
 ABANDONED

LEGEND:

•	EXISTING UTILITY POLE
>	EXISTING GUY WIRE
	EXISTING OVERHEAD UTILITY
	CONSTRUCTION LIMITS
	PROPOSED CURB INLET
•	PROPOSED STORM MANHOLE
•	PROPOSED SANITARY MANHOLE

GENERAL NOTES

- THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- 2. THE CONTRACTOR SHALL PROTECT UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. THE FOLLOWING UTILITIES ARE LOCATED WITHIN THE LIMITS OF THIS PROJECT:

AMEREN IP (GAS) 1050 WEST BLVD. BELLEVILLE, ILLINOIS 62221 (800) 755-5000 AMEREN IP (ELECTRIC) 1050 WEST BLVD. BELLEVILLE, ILLINOIS 62221 (800) 755-5000

VILLAGE OF BETHALTO (SEWER) 101 SOUTH PRAIRIE ST. BETHALTO, IL 62010 (618) 377-8723 AT&T (TELEPHONE) 203 GOETHE ST. COLLINSVILLE, ILLINOIS 62234 (618) 346-6490

VILLAGE OF BETHALTO (WATER) 101 SOUTH PRAIRIE ST. BETHALTO, IL 62010 (618) 377–8723 CHARTER COMMUNICATIONS (CABLE) 210 DIVISION ST. MARYVILLE, IL 62062 (888) 438–2427

J.U.L.I.E. 1-800-892-0123

IT IS UNDERSTOOD AND AGREED THAT THE CONTRACTOR HAS TAKEN THE FOREGOING INTO CONSIDERATION IN SUBMITTING HIS BID, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED FOR ANY DELAYS OR INCONVENIENCES CAUSED BY THE SAME.

THE INFORMATION AND DATA SHOWN OR INDICATED ON THESE IMPROVEMENT PLANS WITH RESPECT TO EXISTING UNDERGROUND FACILITIES AND UTILITIES AT OR CONTIGUOUS TO THE SITE IS BASED ON INFORMATION AND DATA FURNISHED BY THE OWNERS OF SUCH UNDERGROUND FACILITIES AND UTILITIES OR BY OTHERS, FIELD MARKINGS OF FACILITIES IN CRITICAL AREAS MAY BE OBTAINED BY PROVIDING A MINIMUM OF 96 HOURS ADVANCE NOTICE TO THE RESIDENT ENGINEER SO THAT UTILITIES CAN BE GIVEN NOTICE. NO GUARANTEE IS IMPLIED AS TO THE ACCURACY OR COMPLETENESS OF ANY SUCH INFORMATION OR DATA; AND CONTRACTOR SHALL HAVE FULL RESPONSIBILITY FOR I) REVIEWING AND CHECKING ALL SUCH INFORMATION AND DATA, (II) VERIFYING IF ANY CONFLICTS SHOWN OR INDICATED ON THE IMPROVEMENT PLANS; (III) COORDINATION OF THE WORK WITH THE PROPOSED WORKED AND UNDERGROUND FACILITIES AND UTILITIES SHOWN OR INDICATED ON THE IMPROVEMENT PLANS; (III) COORDINATION OF THE WORK WITH THE OWNERS OF SUCH UNDERGROUND FACILITIES AND UTILITIES DURING CONSTRUCTION, AND (IV) THE SAFETY AND PROTECTION OF ALL SUCH UNDERGROUND FACILITIES AND UTILITIES DURING CONSTRUCTION, AND (IV) THE SAFETY AND PROTECTION OF ALL SUCH UNDERGROUND FACILITIES AND UTILITIES DURING CONSTRUCTION, AND (IV) THE SAFETY AND PROTECTION OF ALL SUCH UNDERGROUND FACILITIES AND UTILITIES AND REPAIR ANY DAMAGE THERETO RESULTING FROM THE WORK AT HIS EXPENSE.

- 3. ALL UTILITIES TO BE RELOCATED BY OTHERS.
- 4. THE STANDARDS AND REVISION NUMBERS LISTED SHALL APPLY TO THIS PROJECT.
- 5. ALL AREAS DISTURBED WITHIN OR BEYOND THE CONSTRUCTION LIMITS FOR ANY REASON SHALL BE SEEDED WITH CLASS 2 SEEDING, AS DIRECTED BY THE ENGINEER. NUTRIENTS SHALL CONFORM TO ARTICLE 250.04. FINAL SEEDING SHALL BE PERFORMED AS SOON AS POSSIBLE.
- MULCH, AS APPLIED TO FINAL SEEDING (CLASS 2), SHALL CONFORM TO SECTION 251 OF THE STANDARD SPECIFICATIONS. MULCH UNLESS OTHERWISE PERMITTED BY THE ENGINEER, SHALL CONFORM TO METHOD 2 AS SPECIFIED IN ARTICLE 251.03 (b).
- ALL WORK AS SHOWN ON THESE PLANS SHALL BE PERFORMED IN ACCORDANCE WITH THE SPECIAL PROVISIONS PREPARED BY HOELSCHER ENGINEERING, P.C. ENTITLED "FAU ROUTE 8959 (WEST CORBIN STREET) SECTION 05-00016-03-BR, CONTRACT NO. 97351, VILLAGE OF BETHALTO".
- 8. SEE STANDARD BLR-10 FOR DETAILS OF JOINTS AND REBARS NOT SHOWN ON THE PLANS
- 10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FOLLOWING THE REQUIREMENTS OF AN NPDES STORM WATER PERMIT FOR CONSTRUCTION ACTIVITY FOR THIS PROJECT.
- 11. TOPS OF INLETS WITH TYPE 3 AND TYPE 3V FRAME AND GRATE ARE TO THE EDGE OF PAVEMENT.
- RIPRAP REMOVED ON SITE MAY BE REUSED IN THE PROJECT WITH THE APPROVAL OF THE ENGINEER.
- 13. THE CONTRACTOR SHALL VERIFY EXISTING SANITARY SEWER LOCATION AND ELEVATIONS PRIOR TO ORDERING OR INSTALLING MATERIALS. THE COST FOR THIS WORK SHALL BE INCLUDED IN THE PROPOSED SANITARY SEWER.
- 14. BORROW AREA HAS BEEN PROVIDED ON SITE. SEE WETLANDS PLAN FOR EXACT LOCATION.

ILLINOIS DEPARTMENT OF TRANSPORTATION

INDEX OF SHEETS, HIGHWAY STANDARDS AND GENERAL NOTES FAU ROUTE 8959 SECTION 05-00016-03-BR COUNTY MADISON

RAWN BY: R.A.W.

DATE

NAME