

FAP NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	05-00016-03-BR	MADISON	129	8
STA.	TO STA.			
CONTRACT NO.: 97351				

STORM SEWER SCHEDULE WEST CORBIN

LOCATION			STRUCTURE		TRENCH BACKFILL	CAST IRON		INLETS		MANHOLE TYPE A		FLARED END SECTIONS				STORM SEWERS, TYPE 1		STORM SEWERS, TYPE 2				PIPE CULVERTS, TYPE 1	PIPE CULVERTS, TYPE 2				
STATION	TO	STATION	NO.	DESCRIPTION	CU. YD.	FRAME	GRATE/LID	TYPE A	TYPE B	4' DIA.	5' DIA.	15"	18"	24"	30"	36"	R.C.C.P.		R.C.C.P.				R.C.C.P.	R.C.C.P.			
																	18"	30"	12"	15"	18"	30"	15"	24"	36"		
LT 39+83.00			128	INLET		TYPE 3V		1																			
LT 39+83.00	TO	RT 39+83.00			3.9																						
RT 39+83.00			127	INLET		TYPE 3V			1																		
RT 39+83.00	TO	RT 42+32.00			45.0																						
RT 42+32.00			126	INLET		TYPE 3V			1																		
RT 42+32.00	TO	RT 44+78.00			7.3																						
RT 44+78.00			125	INLET		TYPE 3V			1																		
RT 44+78.00	TO	RT 47+24.00			7.2																						
RT 47+24.00			124	INLET		TYPE 3V			1																		
RT 47+24.00	TO	RT 49+74.00			32.9																						
RT 49+74.00			123	INLET		TYPE 3V			1																		
RT 49+74.00	TO	RT 51+12.37			25.0																						
LT 42+32.00			129	INLET		TYPE 3V		1																			
LT 42+32.00	TO	RT 42+32.00			3.9																						
LT 44+78.00			130	INLET		TYPE 3V		1																			
LT 44+78.00	TO	RT 44+78.00			3.5																						
LT 47+24.00			131	INLET		TYPE 3V		1																			
LT 47+24.00	TO	RT 47+24.00			3.9																						
LT 49+74.00			132	INLET		TYPE 3V		1																			
LT 49+74.00	TO	RT 49+74.00			3.9																						
RT 50+43.77			171	FLARED END SECTION								1															
RT 50+43.77	TO	RT 50+75.61																									
RT 50+75.61			170	FLARED END SECTION								1															
SUB-TOTAL					136.5			5	5			2							1130	138			32				
GRAND TOTAL					612.1			7	13	3	3	2	1	1	1	1			31	0	1,780	138	206	347	32	60	41

SANITARY SEWER SCHEDULE WEST CORBIN

LOCATION			STRUCTURE		TRENCH BACKFILL	MANHOLE TYPE 1 FRAME, CLOSED LID	SANITARY SEWERS, SPECIAL	
STATION	TO	STATION	NO.	DESCRIPTION	CU. YD.	4' DIA.	10"	15"
LT 37+17.97	TO	LT 36+82.93						77
LT 36+82.93			200	MANHOLE		1		
LT 36+82.93	TO	RT 37+15.04			96.0			129
RT 37+15.04			201	MANHOLE		1		
RT 37+15.04	TO	RT 38+70.21						177
RT 38+70.21			202	MANHOLE		1		
GRAND TOTAL					96.0	3		383

NOTE: ALL FLARED END SECTIONS ARE INCLUDED IN THE LENGTHS OF PIPE
SCHEDULE OF QUANTITIES