

100% STATE

CONSTR. CODE

100% STATE

CONSTR. CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	MINOR STRUCTURES	
				0040	URBAN
* X5164000	DRILLED SHAFT IN ROCK (SPECIAL)	CU YD	9.43	9.43	
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	450	450	
* 63302000	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 2	EACH	5	5	
67100100	MOBILIZATION	L SUM	1	1	
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1	
72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	1254.5	1254.5	
73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4' -0" X 4' -6")	FOOT	96	96	
73300300	OVERHEAD SIGN STRUCTURE - SPAN, TYPE III-A (5' -0" X 7' -0")	FOOT	90	90	
73302210	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE III-C-A (36" X 7' -0")	FOOT	105	105	
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	68.03	68.03	
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	2	2	
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	3	3	
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	7	7	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	10	10	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	MINOR STRUCTURES	
				0040	URBAN
X0324181	DISCONNECT SIGN LIGHTING AND REMOVE WIRING TO NEAREST SPLICE	EACH	5	5	
* X6330103	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE I SPECIAL, TANGENT	EACH	3	3	
X6431110	REMOVE ATTENUATOR BASE	EACH	2	2	
X6431120	REMOVE IMPACT ATTENUATOR SAND MODULE	EACH	2	2	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
X7200095	FURNISH AND ERECT SIGN PANEL	SQ FT	1254.5	1254.5	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	

* SPECIALTY ITEM