

Location No.:	1	State I.D. No.:	6S0841072105.9		
County:	SANGAMON	Route:	I-72	M.P.:	105.9
				Direction:	EB
Description of Work	Unit	Quantity			
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00			
OVERHEAD SIGN STRUCTURE-SPAN, TYPE III-A	FOOT	90.00			
REMOVE SIGN PANEL - TYPE 3	SQ FT	532.00			
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	22.50			
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00			
STEEL PLATE BEAM GUARD RAIL, TYPE A 6 FT POSTS	FOOT	25.00			
REMOVE REERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, (TANGENT)	EACH	1.00			
DISCONNECT SIGN LIGHTING AND REMOVE WIRING TO NEARSET SPLICE	EACH	1.00			
CONSTRUCTION LAYOUT	L SUM	0.20			
NIGHTTIME WORK ZONE LIGHTING	L SUM	0.20			
GUARDRAIL MARKERS, TYPE A	EACH	2.00			
FURNISH & ERECT SIGN PANEL	SQ FT	532.00			
DRILLED SHAFT IN ROCK (SPECIAL)	CU YD	9.43			
REMOVE AND REUSE HOSPITAL SIGN - INCIDENTAL	EACH	1.00			
This structure is being completely replaced.					
Elevations: DL 60 CHSLD SQUARE SE CONC. FOUNDATION FOR WB I-72					
IN MEDIAN OF I-72 1.95 MILES E OF STRUCTURE NAVD 88 = 558.578					

Location No.:	2	State I.D. No.:	6S0541055R124.7		
County:	LOGAN	Route:	I-55	M.P.:	124.7
				Direction:	NB
Description of Work	Unit	Quantity			
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00			
OVERHEAD SIGN STRUCTURE-SPAN, TYPE I-A	FOOT	96.00			
REMOVE SIGN PANEL - TYPE 3	SQ FT	441.00			
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	20.94			
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00			
STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FT POSTS	FOOT	350.00			
REMOVE REERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, (TANGENT)	EACH	2.00			
REMOVE REERECT TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2.00			
DISCONNECT SIGN LIGHTING AND REMOVE WIRING TO NEAREST SPLICE	EACH	1.00			
CONSTRUCTION LAYOUT	L SUM	0.20			
NIGHTTIME WORK ZONE LIGHTING	L SUM	0.20			
GUARDRAIL MARKERS, TYPE A	EACH	2.00			
FURNISH & ERECT SIGN PANEL	SQ FT	441.00			
REMOVE ATTENUATOR BASE	EACH	2.00			
REMOVE ATTENUATOR SAND MODULE	EACH	2.00			
This structure is being completely replaced.					
Elevations: BM 054-009 CHSLD "X" NE BOLT OF NORTH LEG OF OVERHEAD SIGN IN CENTER					
OF I-55 MEDIAN 0.27 MILE SOUTH OF STRUCTURE # 054-0045 NAVD88 = 587.276					