

Location No.:	5	State I.D. No.:	6C054I055L132.7		
County:	LOGAN	Route:	I-55	M.P.:	132.7
				Direction:	SB
Description of Work	Unit	Quantity			
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	1.00			
OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE III-C-A	FOOT	35.00			
REMOVE SIGN PANEL - TYPE 3	SQ FT	132.00			
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	8.55			
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00			
STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FT POSTS	FOOT	25.00			
FURNISH AND ERECT SIGN PANEL	SQ FT	132.00			
REMOVE REERECT TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1.00			
DISCONNECT SIGN LIGHTING AND REMOVE WIRING TO NEAREST SPLICE	EACH	1.00			
CONSTRUCTION LAYOUT	L SUM	0.20			
NIGHTTIME WORK ZONE LIGHTING	L SUM	0.20			
GUARDRAIL MARKERS, TYPE A	EACH	2.00			
This structure is being completely replaced.					
Elevations: BM 54 CHSLD "x" E BOLT EXIT 133 BUS LOOP					
55 LINCOLN SIGN +/- 729+23      NAVD 88 = 599.791					