


PAVEMENT TRANSITION DETAIL



- *11' FROM STA. 126+98.81 TP TA/ 129+00.00
- ** 5.5' FROM STA. 126+98.11 TO STA. 129+00.00

PROPOSED TYPICAL SECTION - JOLIET ROAD STA. 120+02.85 TO STA. 129+00.00

LEGEND

- AGGREGATE SUBGRADE IMPROVEMENT
 (AT LOCATIONS DESIGNATE BY THE ENGINEER
 OR AS SHOWN ON THE PLANS)
- GEOTECHNICAL FABRIC FOR GROUND STABILIZATION (AT LOCATIONS DESIGNATE BY THE ENGINEER OR AS SHOWN ON THE PLANS)
- TOPSOIL FURNISH AND PLACE, 4"
- SODDING, SALT TOLERANT (SEE LANDSCAPING PLANS)
- SUB-BASE GRANULAR MATERICAL, TYPE B 2" (COST INCLUDED IN P.C.C. SIDEWALK 5")
- AGGREGATE SUBGRADE IMPROVEMENT 12"
- CONCRETE MEDIAN, TYPE SB-6 (DOWELLED)
- (8) STRIP REFLECTIVE CRACK CONTROL TREATMENT
- 9 CLASS D PATCHES, 12"
 (AT LOCATIONS DESIGNATED BY THE ENGINEER)
- CLASS D PATCHES, 13"
 (AT LOCATIONS DESIGNATED BY THE ENGINEER)
- CLASS D PATCHES, 14"
 (AT LOCATIONS DESIGNATED BY THE ENGINEER)
- (12) CLASS D PATCHES, 17"
 (AT LOCATIONS DESIGNATED BY THE ENGINEER)
- HOT-MIX ASPHALT BASE COURSE, 8 $1\!\!/_2{}''$ (IN 3 LIFTS) (FOR WIDENING GREATER THAN 6 FT)
- POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90, 2"
- POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50 (¾" AND VARIES) SEE DETAIL
- HOT-MIX ASPHALT BASE COURSE WIDENING, 8 $1*2^{\prime\prime}$ (IN 3 LIFTS) (FOR WIDENING 6 FT AND LESS)
- PORTLAND CEMENT CONCRETE SIDEWALK, 5"
- (18) COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24
- HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90, VARIABLE DEPTH (2" MINIMUM THICKNESS) SEE DETAIL

HOT-MIX ASPHALT MIXTURE REQUIREMENTS								
MIXTURE TYPE	AIR VOIDS @Ndes							
PAVEMENT RESURFACING/WIDENING								
POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE. MIX "F", N90, 2" (IL-9.5mm) POLYMERIZED LEVELING BINDER (MACHINE	_4% © 90 Gyr.							
METHOD), IL-4,75, N50 (¾" AND VARIES) HOT-MIX ASPHALT BINDER	3.5%_@_50_Cyr							
COURSE, IL-19.0, N90, VARIABLE DEPTH HOT-MIX ASPHALT BASE COURSE, 81/2":	_ 4% © 90 Gyr.							
HMA BINDER IL-19mm ($8\frac{1}{2}$ ") (3 LIFTS)	4% @ 90 Gyr.							
DRIVEWAYS								
(HMA BINDER IL-19mm) (2 LIFTS)	4% @ 50 Gyr.							
HOT-MIX ASPHALT BASE COURSE, 8" (HMA BINDER IL-19mm) (2 LIFTS) HOT-MIX ASPHALT SURFACE, COURSE, MIX "O", N5O, 2" (IL-9,5mm)	4% @ 50 Gyr. 4% @ 50 Gyr.							
(HMA BINDER IL-19mm) (2 LIFTS) HOT-MIX ASPHALT SURFACE,	_4% @ 50 Gyr. 4% @ 50 Gyr.							

- NOTES:
 1) THE UNIT WEIGHT USED TO CALCULATE ALL HMA SURFACE MIXTURE OUANTITIES IS 112 LBS/SO YD/IN.
- 2) THE "AC TYPE" FOR POLYMERIZED HMA MIXES SHALL BE "SBS/SBR PG 76-22" AND FOR NON-POLYMERIZED HMA THE "AC TYPE" SHALL BE "PG 64-22" UNLESS MODIFIED BY DISTRICT ONE SPECIAL PROVISIONS. FOR USE OF RECYCLED MATERIALS SEE DISTRICT ONE SPECIAL PROVISIONS.
- 3) MILLING SHALL BE DONE PRIOR TO PATCHING

FILE NAME =	USER NAME = \$USER\$	DESIGNED - BDH	REVISED -		PROPOSED TYPICAL SECTIONS	F.A.P.	SECTION	COUNTY TOTAL SHEE	.T
\$FILEL\$		DRAWN - BCD	REVISED -	STATE OF ILLINOIS		330	2010-082-I	COOK 152 11	\dashv
	PLOT SCALE = \$SCALE\$	CHECKED - BDH	REVISED -	DEPARTMENT OF TRANSPORTATION	JOLIET ROAD			CONTRACT NO. 60L73	3
	PLOT DATE = \$DATE\$	DATE - 10-16-13	REVISED -		SCALE: N.T.S. SHEET NO. OF SHEETS STA. TO STA.	1	ILL INOIS FED. AII	PROJECT	-1