

SEQUENCE OF CONSTRUCTION:

- 1. CLOSE EXISTING VALVE.
- 2. REMOVE EXISTING HYDRANT.
- 3. INSTALL HYDRANT EXTENSION AND NEW VALVE.
- 4. RELOCATE EXISTING HYDRANT.
- 5. OPEN EXISTING VALVE, REMOVE BOX.
- 6. BACKFILL.
- 7. FLUSH AND TEST FOR CHLORIDE RESIDUAL AND PROVIDE TEST.

ALL WORK TO BE DONE IN ACCORDANCE WITH ARTICLE 564 OF THE STANDARD SPECIFICATIONS. NEW VALVE AND BOX SHALL BE SAME MAKE AND MODEL AS EXISTING.

FIRE HYDRANT TO BE MOVED

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME =	USER NAME = gaglianobt	DESIGNED -	REVISED - R. SHAH 09-09-94			FIRE HYDRANT TO BE MOVED		RTF.	SECTION	COUNTY SHE	JIAL SHEET
W:\diststd\22x34\bd36.dgn		DRAWN -	REVISED - R. SHAH 10-25-94	STATE OF ILLINOIS	THE HIDHART TO BE MOTED			330	2010-082-I	COOK 15	152 122
	PLOT SCALE = 50.0000 '/ IN.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION					BD-36	CONTRACT NO. 60L73	
	PLOT DATE = 1/4/2008	DATE -	REVISED -	SC	SCALE: NONE	SHEET NO. 1 OF 1 SHEETS STA.	TO STA.	FED. ROAD DIST	. NO. 1 ILLINOIS FED. A		00270