SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: 90% FEDERAL 10% STATE WILL COUNTY 0021	90% FEDERAL 10% STATE COOK COUNTY 0021				
67100100	MOBILIZATION	L SUM	1	0.9	0.1				
70100460	TRAFFIC CONTROL AND PROTECTION,	L SUM	1	0.9	0.1				
	STANDARD 701306								
70100500	TRAFFIC CONTROL AND PROTECTION,	L SUM	1	0.9	0.1				
	STANDARD 701326								
70100600	TRAFFIC CONTROL AND PROTECTION,	L SUM	1	0.9	0.1				
	STANDARD 701336								
70102622	TRAFFIC CONTROL AND PROTECTION,	L SUM	1	0.9	0.1				
	STANDARD 701502								
70102635	TRAFFIC CONTROL AND PROTECTION,	L SUM	1	0.9	0.1				
	STANDARD 701701								
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2839	2745	94				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	14626	14367	259				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	500	487	13				
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	16	12	4				
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	16	12	4				
78300200	RAISED REFLECTIVE PAVEMENT MARKER	EACH	500	487	13				
	REMOVAL								
	* SPECIALTY ITEM								

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: 90% FEDERAL 10% STATE WILL COUNTY 0021	90% FEDERAL 10% STATE COOK COUNTY 0021				
X0326898	CENTER LINE - RUMBLE STRIP - 16"	FOOT	24229	23196	1033				
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	397	397					
□ X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	100	100					
* X7800815	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 4 INCH	FOOT	14626	14367	259				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.9	0.1				
□ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	3	3					
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	100	75	25				
Z0064800	SELECTIVE CLEARING	UNIT	158	158					
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	2900	2900					
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1					
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	15	15					
	□ NP - 100% STATE								
8	* SPECIALTY ITEM								

Rev. 12-30-13

FILE NAME = c:\pw_work\pw_100\cooctrel\d0293497\d722812-sht-schedule.dgn	USER NAME = bocrelar	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	NEW AVE. (COOK COUNTY LINE TO IL 171/ARCHER AVE.) SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -			0361	2011-223-1	COOK & WILL	90	4
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -					CONTRACT NO. 60R86		
	PLOT DATE = 10/31/2013	DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		