

1 C.B., T-C, 2' DIA., W/ T-24 F&G
STA 122+44, 33.5' LT
T.G. 691.15
INV. 686.87 S

2 C.B., T-C, 2' DIA., W/ T-24 F&G
STA 122+24, 33.5' LT
T.G. 691.04
INV. 686.69 N
INV. 686.67 S

3 C.B., T-C, 2' DIA., W/ T-24 F&G
STA 121+88, 33.5' LT
T.G. 691.12
INV. 686.50 N

4 C.B., T-C, 2' DIA., W/ T-24 F&G
STA 122+42, 33.5' RT
T.G. 691.09
INV. 686.36 S

5 C.B., T-C, 2' DIA., W/ T-24 F&G
STA 122+22, 33.5' RT
T.G. 690.97
INV. 686.18 N
INV. 686.16 S

6 C.B., T-C, 2' DIA., W/ T-24 F&G
STA 121+87, 33.5' RT
T.G. 691.18
INV. 686.05 N

7 INLET, T-A, 2' DIA., W/ T-24 F&G
STA 120+92, 35.2' RT
T.G. 691.69
INV. 686.07 E

8 EXIST. C.B. TO BE ADJUSTED W/
NEW F & G, T-1, OL

9 C.B., T-C, 2' DIA., W/ T-24 F&G
STA 118+88 33.0' LT
T.G. 691.50
INV. 687.72 S

10 C.B., T-C, 2' DIA., W/ T-24 F&G
STA 118+28 33.6' LT
T.G. 691.21
INV. 687.73 N

11 C.B., T-A, 4' DIA., W/ T-24 F&G
STA 118+53 33.3' LT
T.G. 691.16
INV. 687.50 N
INV. 687.50 S
INV. 687.59 E
INV. 687.35 W

12 C.B., T-C, 2' DIA., W/ T-24 F&G
STA 118+76 34.6' RT
T.G. 691.42
INV. 688.22 S

13 C.B., T-C, 2' DIA., W/ T-24 F&G
STA 118+26 33.2' RT
T.G. 691.35
INV. 688.22 N

14 C.B., T-A, 4' DIA., W/ T-24 F&G
STA 118+51 33.6' RT
T.G. 691.25
INV. 688.00 N
INV. 688.00 S
INV. 687.94 W

101 EXIST. M.H., 5' DIA., W/T-1 F CL
STA 122+00, 38.0' LT
T.G. 691.41
INV. 686.38 N
INV. 686.38 E
INV. 686.48 NE
INV. 686.48 SE

102 M.H., 6' DIA., W/T-1 F CL
STA 122+03, 40.0' RT
T.G. 691.25
INV. 686.00 N
INV. 685.75 S
INV. 686.05 W
INV. 686.00 NW
INV. 686.00 SW

103 EXIST. M.H., 5' DIA., W/T-1 F CL
STA 120+93 45.3' RT
T.G. 692.12
INV. 685.67 N
INV. 685.52 S
INV. 686.00 W

DRAINAGE PIPES TABLE

PIPE NO.	PIPE LOCATION		STATION - STATION	DESCRIPTION / COMMENTS	DIA. (IN.)	LENGTH (FT)
	FROM STR.	TO STR.				
1	1	2	122+44 - 122+24	SS, CLASS A, TYPE 2	12	20.0
2	2	101	122+44 - 122+24	SS, CLASS A, TYPE 2	12	23.0
3	3	101	121+98 - 122+00	SS, CLASS A, TYPE 2	12	6.0
4	4	5	122+42 - 122+03	SS, CLASS A, TYPE 2	12	20.0
5	5	102	122+22 - 122+03	SS, CLASS A, TYPE 2	12	20.0
6	6	102	121+97 - 122+03	SS, CLASS A, TYPE 2	12	9.0
7	7	103	120+92 - 120+93	SS, CLASS A, TYPE 2	12	10.0
9	9	11	118+78 - 118+53	SS, CLASS A, TYPE 2	12	25.0
10	10	11	118+28 - 118+53	SS, CLASS A, TYPE 2	12	26.0
12	12	14	118+76 - 118+51	SS, CLASS A, TYPE 2	12	25.0
13	13	14	118+26 - 118+51	SS, CLASS A, TYPE 2	12	25.0

FILE NAME =	USER NAME = jimenezjl	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	STRUCTURE AND PIPE SCHEDULE U.S. RTE. 30 (LINCOLN HWY) AT WESTERN AVE	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
Default	Default	DRAWN -	REVISED -			353	23N-2	COOK	75	34	
		CHECKED -	REVISED -			CONTRACT NO. 60T19					
		DATE -	REVISED -			SCALE:	SHEET	OF	SHEETS	STA.	TO