URBAN

	SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
	CODE NO	ITEM	UNIT		FED 90% STATE 10% 0004 ROADWAY	FED 90% STATE 7.5% VILLAGE 2.5% 0021 TRAFFIC SIGNALS	FED 90% STATE 10% 0021 INTER-CONNECT	VILLAGE 100% 0021 EVP	FED 90% STATE 10% 0021 LIGHTING	
•	89502382	REMOVE EXISTING DOUBLE HANDHOLE	EACH	2		2				
•	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	8		8				
•	X0324085	EMERGENCY VEHICLE PRIORITY SYSTEM LINE	FOOT	1109				1109		
		SENSOR CABLE, NO. 20 3/C								
□	X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	200	200					
	X6030310	FRAMES AND LIDS TO BE ADJUSTED	EACH	13	13					
		(SPECIAL)								
*	X8210015	TEMPORARY LUMINAIRE, HIGH PRESSURE	EACH	2					2	
		SODIUM VAPOR, 400 WATT								
*	X8250091	COMBINATION LIGHTING CONTROLLER	EACH	1					1	
*	X8570231	FULL-ACTUATED CONTROLLER AND TYPE V	EACH	1		1				
		CABINET, SPECIAL								
*	X8600105	MASTER CONTROLLER (SPECIAL)	EACH	1			1			
*	X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	1		1				
*	X8710024	FIBER OPTIC CABLE IN CONDUIT, NO.	FOOT	4644			4644			
		62.5/125, MM12F SM24F								
*	X8772115	TEMPORARY MAST ARM, ALUMINUM, 15FT	EACH	2					2	

□ NP- 100% STATE

URBAN

	SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
	CODE NO	ITEM	UNIT		FED 90% STATE 10% 0004 ROADWAY	FED 90% STATE 7.5% VILLAGE 2.5% 0021 TRAFFIC SIGNALS	FED 90% STATE 10% 0021 INTER-CONNECT	VILLAGE 100% 0021 EVP	FED 90% STATE 10% 0021 LIGHTING	
	Z0004562	COMBINATION CONCRETE CURB AND GUTTER	FOOT	228	228					
		REMOVAL AND REPLACEMENT								
□	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	15	15					
	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
*	Z0033024	MAINTAIN EXISTING LIGHTING SYSTEM	L SUM	1					1	
*	Z0033040	ELECTRIC SERVICE DISCONNECT, LIGHTING	EACH	1		1				
		AND TRAFFIC SIGNAL								
*	Z0033044	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL I	EACH	1			1			
*	Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1		1				
*	66A00200	NON-SPECIAL WASTE DISPOSAL	CUYD	60	60					
*	66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1					
*	66900530	SOIL DISPOSAL ANALYSIS	EACH	3	3					
*	67201100	SEALING ABANDONED MONITORING WELLS	EACH	3	3					
•		SPECIALTY ITEM								

1

1 Rev. 12-30-13

FILE NAME = c:\pw_work\pwidot\smith\d0267303\P15451-sht-SQ.dgn	USER NAME = SMITHCJ	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL. RTE. 62 AT MEACHAM RD. SUMMARY OF QUANTITIES	F.A.P. RTE. 339	SECTION 116-RS-5	COUNTY COOK	TOTAL SHEETS 54	SHEET NO. 7
	PLOT SCALE = 100.0000 ' / in.	DRAWN -	REVISED -					CONTRACT NO. 60W05		
	PLOT DATE = 10/18/2013	CHECKED -	REVISED -							
		DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		