



Note:
For Section A-A, see Sheet 4 of 4.
Bars indicated thus 16x3-#5 etc. indicates 16 lines of bars with 3 lengths per line.

BILL OF MATERIAL

Item	Unit	Quantity
Structural Excavation	Cu. Yd.	172
Concrete Structures	Cu. Yd.	56.3
Reinforcement Bars, Epoxy Coated	Pound	8,450
Concrete Sealer	Sq. Ft.	508
Geocomposite Wall Drain	Sq. Yd.	57
Granular Backfill for Structures	Cu. Yd.	76
Pipe Underdrains for Structures 4"	Foot	106

8/10/21 PM 0161708-60W29-5165-RetWall_SED.dgn



USER NAME = BAWitorf	DESIGNED WJC	REVISED
	CHECKED MDS	REVISED
PLOT SCALE = 8:0.0000 ' / in.	DRAWN WJC	REVISED
PLOT DATE = 10/28/2013	CHECKED MDS	REVISED

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**RETAINING WALL 1
PLAN AND ELEVATION**

SHEET NO. 2 OF 4 SHEETS

MUN	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2090	2013-011R	COOK	356	189
ILLINOIS FED. AID PROJECT			CONTRACT NO.	60W29