



Notes:
 For Expansion Joint Detail and Construction Joint Detail see Sheet 2 of 4.
 For Section A-A, see Sheet 4 of 4.

BILL OF MATERIAL

Item	Unit	Quantity
Structural Excavation	Cu. Yd.	163
Concrete Structures	Cu. Yd.	49.0
Reinforcement Bars, Epoxy Coated	Pound	7350
Concrete Sealer	Sq. Ft.	392
Geocomposite Wall Drain	Sq. Yd.	44
Granular Backfill for Structures	Cu. Yd.	58
Pipe Underdrains for Structures 4"	Foot	99

9:10:22 PM 01/17/08-GOW29-5165A-Rev+Wall2.dgn



USER NAME = BAWIort	DESIGNED MDS	REVISED
	CHECKED KAH	REVISED
PLOT SCALE = 8:0.0000 ' / in.	DRAWN KAH	REVISED
PLOT DATE = 10/28/2013	CHECKED MDS	REVISED

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**RETAINING WALL 2
 PLAN AND ELEVATION**

SHEET NO. 3 OF 4 SHEETS

MUN	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2090	2013-011R	COOK	356	190
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60W29	