- INDOOR ELECTRICAL CONTROL CABINETS SHALL HAVE A MINIMUM NEMA-12 RATING OR AS INDICATED, ALL OUTDOOR CABINETS SHALL BE STAINLESS STEEL TYPE 316, AND SHALL BE NEMA 4X RATED UNLESS OTHERWISE NOTED.
- 3. LOCATIONS AND DIMENSIONS OF ELECTRICAL EQUIPMENT AND ASSOCIATED DEVICES AND CONDUIT RUNS ARE APPROXIMATE BASED ON EXISTING CONDITIONS AND BEST AVAILABLE PERTINENT INFORMATION AND PLANS. HOWEVER, THE CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFYING EXACT LOCATIONS AND PROPOSED EQUIPMENT DIMENSIONS AS PART OF THE CONSTRUCTION AND SHOP DRAWING SUBMITTAL PROCESS. AS-BUILT-DRAWINGS SHALL BE BASED ON APPROVED SHOP DRAWINGS AND ON ACTUAL FIELD SURVEYS, MEASUREMENTS, AND APPROVED INSTALLED EQUIPMENT ONLY.
- 4. FURNISH AND INSTALL ALL REQUIRED CONDUIT, WIRE AND CABLE, FITTINGS, BOXES, HARDWARE, ETC. IN ORDER TO MAKE A COMPLETE ELECTRICAL/COMMUNICATION SYSTEM READY FOR OPERATION. DRAWINGS FOR APPROVAL SHOWING LAYOUT DETAILS SHALL BE SUBMITTED PRIOR TO ANY INSTALLATION. TO ANY INSTALLATION WORK.
- ALL CONDUIT AND WIRING FURNISHED AND INSTALLED UNDER THIS CONTRACT SHALL BE NEW AND WEET NEC AND AASHTO CODE CONTRACT SHALL BE NEW AND MEET NEC AND AASHTO CODE
  REQUIREMENTS. EXISTING WIRING NOT USED SHALL BE DISCONNECTED
  AND CLEARLY MARKED AS SUCH. CONDUIT NOT REMOVED AND NOT
  USED SHALL BE CAPPED. ALL CONDUIT AND FITTINGS SHALL BE HOT- DIP
  GALVANIZED RIGID STEEL, ADDITIONALLY, ALL EXTERNAL CONDUITS
  SHALL BE PVC-COATED, MOUNT ALL CONDUIT RUNS ON PVC-COATED
  GALVANIZED STEEL UNISTRUIT (KINDORF) CHANNELS OR APPROVED EQUAL. MOUNTING HARDWARE SHALL BE STAINLESS STEEL, TYPE 316.
- 6. EXACT CONDUITS, JUNCTION AND PULL BOX LOCATIONS, MOUNTING HARDWARE AND SUPPORTS, AND STUB-UP LOCATIONS ARE TO BE DETERMINED BASED ON FIELD CONDITIONS AS SPECIFIED AND SHOWN
- PROVIDE EXPANSION AND DEFLECTION CONDUIT FITTINGS OF THE APPROVED TYPE AT THE LOCATIONS WHERE CONDUIT PASSES THROUGH STRUCTURAL EXPANSION JOINTS OTHER CRITICAL LOC-ATIONS, OR MINIMUM EVERY 300 FEET ON STRAIGHT RUNS.
- 8. PITCH CONDUIT RUNS TOWARD PULL BOXES TO PREVENT MOIS-TURE ACCUMULATION, ON LOWEST POINT OF ALL BOXES AND OTHER ELECTRICAL EQUIPMENT SUBJECT TO WATER ACCUMULATION. PROVIDE NECESSARY DRAIN OPENINGS, FITTINGS, CONDUITS, ETC.
- PERFORM ALL CUTTING, DRILLING AND CORE DRILLING AS NECESSARY TO PROVIDE PENETRATIONS THROUGH WALLS AND FLOORS FOR ELEC-TRICAL INSTALLATION WORK, CORE DRILL DIAMETER SHALL NOT BE MORE THAN 25 PERCENT LARGER THAN THE CONDUIT OUTSIDE DIAM-TER. ALL CONDUITS PENETRATING WALLS AND FLOORS SHALL BE INSTALLED IN A GALVANIZED STEEL SLEEVE WITH FLOOR SUPPORTS , PATCH AND RESTORE SURROUNDING AREA OF PENETRATIONS TO ITS ORIGINAL CONDITION TO THE SATISFACTION OF THE ENGINEER. OPENINGS CONDITION TO THE SATISFACTION OF THE CHOINEST OFERINGS THROUGH SLAB AND WALL FOR CONDUITS SHALL BE FIRE STOPPED IN AN APPROVED MANNER UTILIZING "3M" COMPANY SEALING SYSTEM 7904 SERIES OR APPROVED FOUAL

10.

- 11. CONTRACTOR SHALL NOTIFY IDOT FOR EXISTENCE OF ASBESTOS AFFECTED BY THE INSTALLATION OF ELECTRICAL AND CONTROL
- 12. FURNISH AND INSTALL TAGS FOR CONDUITS AND CABLES TO BE INSTALLED UNDER THIS CONTRACT. TAG IDENTIFICATIONS SHALL BE IN ACCORDANCE WITH THE CONTRACT DRAWINGS, OR AS DIRECTED BY THE ENGINEER.
- 13. PRIOR TO COMMENCEMENT OF WORK, SUBMIT DETAILED STAGING PLANS TO THE ENGINEER FOR APPROVAL. COORDINATE WITH THE ENGINEER ALL CONSTRUCTION ACTIVITIES THAT MAY AFFECT
- 14. COMPLETE ELECTRICAL INSTALLATION SHALL BE PERMANENTLY AND EFFECTIVELY GROUNDED TO GROUND RODS AND/OR STRUCTURAL STEEL IN ACCORDANCE WITH NATIONAL ELECTRICAL CODE AND AASHTO CODE ROUIREMENTS, WHETHER OR NOT SUCH CONNECTIONS ARE SPECIFICALLY IDENTIFIED. MEASURED RESISTANCE TO GROUND TO BE 5 OHMS MAXIMUM.

- ALL GOOV POWER AND CONTROL CABLE SHALL BE TYPES RIH. RHW, XHHW-2 OR USE. THE CABLE SHALL RATED AT A MINIMUM OF 90°C DRY AND 75°C WET AND SHALL BE SUITABLE FOR INSTALLATION IN WET AND DRY LOCATIONS, AND SHALL BE RESISTANT TO OILS AND CHEMICALS, SHALL CONSIST OF STRANDED COPPER CONDUCTORS INSULATED WITH CHEMICALLY CROSS-LINKED POLYETHYLENE, XLPE.
- THE CONTRACTOR SHALL PERFORM FULL CONTINUITY, INSULATION AND GROUNDING INTEGRITY TESTS UPON COMPLETION OF THE ELECTRICAL INSTALLATIONS.
  THE CONTRACTOR SHALL PERFORM FULL ACCEPTANCE TESTS OF ALL INDIVIDUAL NEW CCTV SYSTEM COMPONENTS, THE FULL SYSTEM'S INTEGRATION TO EXISTING IDOT CCTV MONITORING SYSTEM, AND ALL AUXILIARY EQUIPMENT. THE CONTRACTOR SHALL ALSO PERFORM FULL CONTINUITY TEST ON REMAINING SPARE FIBER OPTIC STRANDS IN EACH INSTALLED F.O. CABLE.
- FOR ADDITIONAL INFORMATION REGARDING EXISTING ROADWAY, BRIDGE.
  AND OTHER INFRASTRUCTURE AND SYSTEMS, REFER TO BRIDGE'S ROADWAY
  AND VARIOUS ROOMS CONTRACT WEST CONGRESS STREET BRIDGE
  OVER SOUTH BRANCH CHICAGO RIVER. THE CONTRACTOR SHALL FIELD VERIFY ALL EXISTING INSTALLATIONS, AND SHALL PREPARE CONSTRUCTION DOCUMENTATION BASED ON VERIFIED FIELD MEASURE-MENTS AND INSTALLATIONS.
- ALL POWER EQUIPMENT SHALL BE GROUNDED. COPPER GROUNDING TERMINATION DETAILS, AS INDICATED ON DRAWINGS AND SPECIFICATIONS.
- SUBMIT DETAIL DRAWINGS OF ALL EQUIPMENT PRIOR TO FABRICATION.
- 20. ALL EQUIPMENT SHOULD BE ARRANGED TO PERMIT EASY ACCESS FOR OPERATION AND MAINTENANCE.
- ALL SURFACES DAMAGED IN THE COURSE OF WORK SHALL BE RESTORED TO THE ORIGINAL CONDITION AT NO ADDITIONAL COSTS TO THE OWNER,
- UPON REMOVAL OF ANY EQUIPMENT, REMOVE ALL SUPPORTS AND HANGERS ASSOCIATED WITH THE EQUIPMENT AND RESTORE THE 22. SURFACE TO MATCH THE SURROUNDING AREAS.
- REMOVAL OF HAZARDOUS MATERIALS SHALL FOLLOW PROCEDURES APPROVED BY IDOT AND OTHER LOCAL AUTHORITIES HAVING 23.
- ELECTRICAL EQUIPMENT SHALL NOT BE INSTALLED DIRECTLY OVER HEAT PRODUCING EQUIPMENT SUCH AS WALL/SPACE HEATERS AND TRANSFORMERS.
- ALL SALVACABLE EQUIPMENT SHALL BE RETURNED TO IDOT AT NO

10/21/2013 HINDROFESS/ON THE THE PROFESS/ON THE PROFESS/ON THE PROFESS/ON THE PROFESS/ON THE PROFESSION TO THE PR £062-053407 FOF ILLING MATE OF IL

James William Guinan IL PE 062.053407

## Parsons Brinckerhoff

Applicable to drawing sheets 3 through 10 And 12 through 25

**PARSONS** BRINCKERHOFF

DESIGNED - D. DRAKULICH REVISED DRAWN - E. MALUSEL REVISED PLOT SCALE - NONE CHECKED - S. STERN REVISED PLOT DATE = 10/18/2013 DATE 10/18/2013 REVISED

CCTV SYSTEM, I-90/94 TO CONGRESS PARKWAY GENERAL ELECTRICAL NOTES

1 Rev. 12-30-13

COUNTY TOTAL SHEET NO. SECTION 389 2013-026-1 CONTRACT NO. 60W49

SCALE: AS SHOWN SHEET NO. OF SHEETS STA. 353+46.00 TO STA. 382+50.00