

COOK COUNTY	SIGN PANEL TYPE 2				SIGN PANEL TYPE 1																											
	DO NOT ENTER (R5-1)		KEEP RIGHT (R4-7)		ILLINOIS RTE (M1-1100)		US RTE 2 DIGITS (M1-4)		CARDINAL DIRECTION (M3-1,2,3,4)		DIRECTIONAL ARROW (M6-2A)		WRONG WAY (R5-1A)		ONE WAY (R6-1L)		ONE WAY (R6-1R)		NO RIGHT TURN (R3-1)		NO LEFT TURN (R3-2)		RETROREFLECTIVE SIGN SUPPORT PANEL		TELESCOPING STEEL SIGN SUPPORT		BASE FOR TELESCOPING STEEL SIGN SUPPORT	REMOVE SIGN ASSEMBLY TYPE A	REMOVE SIGN ASSEMBLY TYPE B	REMOVE SIGN PANEL TYPE 1	RELOCATE SIGN PANEL TYPE 1	
	QTY	SQ.FT	QTY	SQ.FT	QTY	SQ.FT	QTY	SQ.FT	QTY	SQ.FT	QTY	SQ.FT	QTY	SQ.FT	QTY	SQ.FT	QTY	SQ.FT	QTY	SQ.FT	QTY	SQ.FT	QTY	SQ.FT	QTY/TOTAL FT	(EA)	(EA)	(EA)	(SQ.FT)	(SQ.FT)		
EB PALATINE RD TO IL RTE 83 (LOC. 1)	0	0	0	0	0	0	0	0	0	0	0	0	0	2	17.5	2	13.5	2	13.5	0	0	0	0	7	5.83	4	53	1	0	0	0	0
WB PALATINE RD TO IL RTE 83 (LOC. 1)	0	0	0	0	0	0	0	0	0	0	0	0	0	2	17.5	2	13.5	2	13.5	0	0	0	0	6	5.00	3	39	1	0	0	0	0
EB PALATINE RD TO WOLF RD (LOC. 2)	0	0	0	0	0	0	0	0	0	0	0	0	0	2	17.5	2	13.5	2	13.5	0	0	0	0	5	4.17	2	30	0	0	0	13.5	0
WB PALATINE RD TO WOLF RD (LOC. 2)	0	0	0	0	0	0	0	0	0	0	0	0	0	2	17.5	2	13.5	2	13.5	0	0	0	0	5	4.17	2	30	0	0	0	13.5	0
EB PALATINE RD TO US RTE 45 (LOC. 3)	0	0	0	0	0	0	0	0	0	0	0	0	0	4	35	2	13.5	2	13.5	0	0	0	0	5	4.17	4	59	0	0	0	17.5	0
WB PALATINE RD TO US RTE 45 (LOC. 3)	0	0	0	0	0	0	0	0	0	0	0	0	0	2	17.5	2	13.5	2	13.5	0	0	0	0	3	2.50	2	30	0	0	0	0	0
EB LAKE-COOK RD TO IL RTE 21 (LOC. 4)	0	0	0	0	0	0	0	0	0	0	0	0	0	4	35	2	13.5	2	13.5	0	0	0	0	4	3.33	4	60	0	1	0	13.5	0
NB IL RTE 53 TO US RTE 12 (LOC. 5)	0	0	0	0	0	0	0	0	0	0	0	0	0	2	17.5	2	13.5	2	13.5	0	0	0	0	6	5.00	2	30	0	0	0	0	0
SEB US RTE 14 TO IL RTE 68 (LOC. 6)	2	32	0	0	0	0	0	0	0	0	0	0	0	1	8.75	2	13.5	2	13.5	0	0	0	0	6	5.00	5	72	2	0	0	18	0
NWB US RTE 14 TO IL RTE 68 (LOC. 6)	2	32	0	0	0	0	0	0	0	0	0	0	0	2	17.5	2	13.5	2	13.5	1	9	1	9	9	7.50	6	97	2	1	0	9	0
IL RTE 68 TO US RTE 14 NWB (LOC. 6)	2	32	0	0	0	0	0	0	0	0	0	0	0	2	17.5	0	0	0	0	0	0	0	3	2.50	3	46	0	0	0	8.75	0	
IL RTE 68 TO US RTE 14 SEB (LOC. 6)	2	32	0	0	0	0	0	0	0	0	0	0	0	2	17.5	0	0	0	0	0	0	0	5	4.17	4	62	0	0	0	9	0	
WB US RTE 14 TO IL-21 (LOC. 7)	0	0	0	0	0	0	0	0	0	0	0	0	0	2	17.5	2	13.5	2	13.5	0	0	0	0	4	3.33	3	39	1	0	0	0	0
EB US RTE 14 TO IL-21 (LOC. 7)	0	0	0	0	0	0	0	0	0	0	0	0	0	2	17.5	2	13.5	2	13.5	0	0	0	0	4	3.33	3	39	1	0	0	0	0
<b>TOTAL</b>	<b>8</b>	<b>128</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>31</b>	<b>271.3</b>	<b>24</b>	<b>162</b>	<b>24</b>	<b>162</b>	<b>1</b>	<b>9</b>	<b>1</b>	<b>9</b>	<b>72</b>	<b>60</b>	<b>47</b>	<b>686</b>	<b>8</b>	<b>2</b>	<b>0</b>	<b>102.75</b>	<b>0</b>

NOTE:  
RETROREFLECTIVE SIGN PANEL SHALL BE USED ON SIGN SUPPORTS  
FOR 'DO NOT ENTER' AND 'WRONG WAY' SIGNS

FILE NAME =	USER NAME = SMITHCJ	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>COOK COUNTY SIGN SCHEDULE OF QUANTITIES</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\pw\work\p\dot\smi\thc\j\d0355785\Design\sh-t-ARS-Will.dgn	DRAWN -	REVISED -	2013-0555G			VARIOUS	46	8		
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -			<b>CONTRACT NO. 60X30</b>				
	PLOT DATE = 10/18/2013	DATE -	REVISED -			ILLINOIS FED. AID PROJECT				
SCALE:						SHEET	OF	SHEETS	STA.	TO STA.