

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	0040		0040		0040		0040		0004		0004	
				80% FED:20% STATE PR SN:043-1097 FAP	80% FED:20% STATE PR SN: 043-1098 FAP	80% FED:20% STATE PR SN: 043-1099 FAS	80% FED:20% STATE EX SN: 043-C001 FAS	80% FED:20% STATE FAP ROADWAY	80% FED:20% STATE ROADWAY FAS						
28100107	STONE RIPRAP, CLASS A4	SQ YD	460	260	60	90	50	0	0						
28200200	FILTER FABRIC	SQ YD	675	475	60	90	50	0	0						
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	1638.2	0	0	0	0	1638.2	0						
35101400	AGGREGATE BASE COURSE, TYPE B	TON	686	0	0	0	0	686	0						
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	319.5	0	0	0	0	221.8	97.7						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	920	0	0	0	0	520.0	400.0						
40600980	TEMPORARY RAMP	SQ YD	139	0	0	0	0	94	45						
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	720	0	0	0	0	573	147						
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	15	0	0	0	0	15	0						
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SQ YD	376	0	0	0	0	80	296						
48100700	AGGREGATE SHOULDERS, TYPE A 8"	SQ YD	520	0	0	0	0	0	520						
48203020	HOT-MIX ASPHALT SHOULDERS, 5 3/4"	SQ YD	1908	0	0	0	0	1908	0						
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	0	1	0	0	0	0						
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	0	0	1	0	0	0						
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1	0	0	0	1	0	0						
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	553	0	553	0	0	0	0						
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	11440	1255	8710	0	1475	0	0						
50800515	BAR SPLICERS	EACH	56	0	56	0	0	0	0						
51500100	NAME PLATES	EACH	3	1	1	1	0	0	0						
54003000	CONCRETE BOX CULVERTS	CU YD	47.6	0	47.6	0	0	0	0						
54213450	END SECTIONS 15"	EACH	6	2	4	0	0	0	0						
54215408	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 8"	EACH	1	0	0	0	0	1	0						

FILE NAME :	USER NAME : GUZZARDOGA	DESIGNED -	REVISED -	STATE OF ILLINOIS	IL 78 /CANYON RD	RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.					
	01310-ht-500.dgn	DRAWN -	REVISED -	DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	X	104T-3	JO DAVJESS	97	7					
	PLOT SCALE = 00.0000' / in.	CHECKED -	REVISED -												
	PLOT DATE = Wed Nov 13 13:33:02 2013	DATE -	REVISED -												
						SCALE:	SHEET	OF	SHEETS	STA.	TO	STA.	CONTRACT NO. 64F74		
											ILLINOIS FED. AID PROJECT				

22