



PLAN

<u>LEGEND</u>

Slopewall, 4"

sf square feet

BILL OF MATERIAL

ITEM	UNIT	TOTAL	
Slope Wall Removal	Sq. Yd.	10	
Slape Wall. 4"	Sq. Yd.	10	
Controlled Low Strength Material	Cu. Ya.	5	

Notes

Slopewall shall be reinforced with welded wire fabric, 6"x 6" - W4,0 x W4,0, weighing 58 lbs, per 100 sq. ft. Existing reinforcement shall be cleaned and incorporated into the new construction. Cost included with Slopewall Repair.

Existing and new weided wire fabric must be lapped at least 6".

Repair of the existing slope walls shall include but may not be limited to the areas shown. The actual areas to be repaired will be determined by the Engineer at the time of construction.

FILE NAME 2 CHIZ aver FAI-72.dgn	USER NAME :	DESIGNED - SAL	REVISEO -		SLOPEWALL REPAIR DETAILS	F.A.I. SECT	ION	COUNTY	TOTAL	IÉE T
		CHECKED - MTH	REVISED -	STATE OF ILLINOIS	MECHANICSBURG ROAD OVER F.A.I72 - S.N. 084-0150	72		SANGAMON	194	137
1	PLOT SCALE :	DRAWN - TJW	REVISED -	DEPARTMENT OF TRANSPORTATION	WICCHAMICSDUNG NUAD UVEN F.A.I72 - 3.W. U84-U13U	- (84-10-1RS-3, 84-1)	0-2RS-R)BR,I	CONTRACT	NO. 72	90
<u> </u>	PLOT DATE z	CHECKED - MTH	REVISED -		SHEET NO. 25 OF 27 SHEETS	FED. ROAD DIST. NO. 6	ILLINOIS FED. AID	PRO.ECY		