INDEX OF SHEETS

- 1. COVER
- 2. INDEX OF SHEETS, GENERAL NOTES, AND HIGHWAY STANDARDS
- 3. SUMMARY OF QUANTITIES
- 4-5. LOCATION MAP
 - 6. TYPICAL SECTIONS

HIGHWAY STANDARDS

701001-02 OFF-RD OPERATIONS, 2L, 2W, MORE THAN 15' AWAY FROM EDGE OF PAVEMENT

701006-05 OFF-RD OPERATIONS, 2L, 2W, 15' TO 24" FROM EDGE OF PAVEMENT

701011-04 OFF-RD MOVING OPERATIONS, 2L, 2W, DAY ONLY

701301-04 LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS

701306-03 LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS DAY ONLY, FOR SPEEDS > 45 MPH

701311-03 LANE CLOSURE, 2L, 2W, MOVING OPERATIONS DAY ONLY

701901-03 TRAFFIC CONTROL DEVICES

780001-04 TYPICAL PAVEMENT MARKINGS

GENERAL NOTES

- 1. ANY REFERENCE TO THE STANDARDS THROUGHOUT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS INCLUDED IN THE PLANS.
- 2.NO EXCAVATION IS ANTICIPATED ON THIS PROJECT. SHOULD ANY EXCAVATION BE REQUIRED, J.U.L.I.E. SHALL BE NOTIFIED A MINIMUM OF 48 HOURS IN ADVANCE (800) 892-0123.
- 3. THE AGGREGATE GRADATION FOR THE A-1 BITUMINOUS SURFACE TREATMENT SHALL BE CA-16 OR CA-20 ON THE WEST SECTION AND CA-13 ON THE EAST SECTION.
- 4. AGGREGATE FOR THE A-1 BITUMINOUS SURFACE TREATMENT SHALL BE CRUSHED LIMESTONE.
- 5. SHORT-TERM PAVEMENT MARKING SHALL BE PAINT TAPE WILL NOT BE ALLOWED.
- 6. PERMANENT PAVEMENT MARKINGS SHALL NOT BE APPLIED UNTIL 10 DAYS AFTER THE AGGREGATE HAS BEEN APPLIED.
- 7. ADDITIONAL BROOMING (UP TO 4 TIMES) SHALL BE REQUIRED AT THE DISCRETION OF THE ENGINEER. INCLUDING THE DAY OF PERMANENT PAVEMENT MARKING.
- 8. THE CONTRACTOR SHALL GIVE IDOT OPERATIONS TWO WEEKS NOTICE PRIOR TO STARTING WORK IN ORDER FOR IDOT TO COMPLETE PATCHING.

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS DISTRICT 6						
EXAMINED	9/11	20 <u>/3</u>				
Billn	4/ - 4 -	ENGINEER OF OPERATIONS				
EXAMINED	August	Mo 20 13				
	PAGINEER OF P	ROJECT IMPLEMENTATION				
EXAMINED_	AUGUST	16 20 13 Maria				

FILE NAME	1	USER NAME + sharptd	DESIGNED -	REVISED -		INDEX OF SHEETS, HIGHWAY STANDARDS	RIF SECTION COUNTY TOTAL SHEET
SINCONTRM	AJNT_CAU\72622 - FAS 1769 - 15	FR E & W - MONT SEAL COATNING-	10-SIGN -	REVISED -	STATE OF ILLINOIS	AND GENERAL NOTES	1769 (68-3 & 4) & (112) Q-1 MONTGOMERY 6 2
		PLOT SCALE * 1,0000 // in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION	AND GENERAL NUICO	CONTRACT NO. 72G22
Cefault		PLOT DATE : 0at-24-2013 @6:49:1@AM	DATE ~	REVISED -		SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.	ILLINOIS FED. AID PROJECT