



DECK PLAN VIEW

**LEGEND**

- Concrete Removal for Joint Replacement (See Sheet 10, 11)
- Deck Slab Repair (Partial Depth)

Patch No.	Patch Depth	Station	Length (ft)	Width (ft)	Quantity (sq. yd.)
1	Partial	1526+61.92	4	18	8.00
2	Partial	1526+74.92	3	3	1.00
3	Partial	1526+74.92	3	3	1.00

**BILL OF MATERIAL**

Item	Unit	Total
Deck Slab Repair (Partial Depth)	Sq. Yd.	10.0
*Deck Slab Repair (Full Depth, Type I)	Sq. Yd.	2.0

\*Additional Deck Slab Repair (Full Depth, Type I) quantity has been included in the event full depth patches are identified during construction. Location not shown.

3/25/2013 3:20:23 PM - G:\S\12\000\Bridges\CAD\Drawings\0220-0220-09-Deck Patching Plan.dgn



USER NAME = ghowley	DESIGNED - SDG	REVISED -
PLOT SCALE = 214' 1" / in.	CHECKED - FAS	REVISED -
PLOT DATE = 3/25/2013	DRAWN - IK	REVISED -
	CHECKED - SDG	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**DECK PATCHING PLAN  
STRUCTURE NO. 060-0220 SB**

SHEET NO. 9 OF 19 SHEETS

F.A.I. RTE. 255	SECTION 60-(8,9) RS-1	COUNTY MADISON	TOTAL SHEETS 206	SHEET NO. 159
			CONTRACT NO. 76F10	
ILLINOIS FED. AID PROJECT				