



**DECK PLAN VIEW**

**LEGEND**

- Concrete Removal for Joint Replacement (See Sheets 6 and 7)
- Deck Slab Repair (Partial Depth)

Patch No.	Patch Depth	Station	Length (ft)	Width (ft)	Quantity (sq. yd.)
1	Partial	718+55	6	4	2.67

**BILL OF MATERIAL**

Item	Unit	Total
Deck Slab Repair (Partial Depth)	Sq. Yd.	2.7
*Deck Slab Repair (Full Depth, Type I)	Sq. Yd.	2.0

\*Additional Deck Slab Repair (Full Depth, Type I) quantity has been included in the event full depth patches are identified during construction. Location not shown.

3/25/2013 3:51:51 PM - G:\S1\2\0001\Bridges\CAD\Drawings\0224\0600224-76F10-05-Deck Patching Plan.dgn

FILE NAME = 0600224-76F10-05-Deck Patching Plan.dgn



USER NAME = gchowley	DESIGNED - SDG	REVISED -
	CHECKED - FAS	REVISED -
PLOT SCALE = 214' = 1" / in.	DRAWN - IK	REVISED -
PLOT DATE = 3/25/2013	CHECKED - SDG	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**DECK PATCHING PLAN  
STRUCTURE NO. 060-0224**

SHEET NO. 5 OF 13 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
255	60-(8,9) RS-1	MADISON	206	188
CONTRACT NO. 76F10				

ILLINOIS FED. AID PROJECT