03

0

0

0

0

#### 01-17-2020 LETTING ITEM 027

#### **INDEX OF SHEETS**

1 COVER SHEET

HIGHWAY STANDARDS AND GENERAL NOTES

-4 SUMMARY OF QUANTITIES

5-6 SCHEDULE OF QUANTITIES
7-9 TRAFFIC CONTROL PLAN STAGE 1

10-12 TRAFFIC CONTROL PLAN STAGE 2

13 GENERAL PLAN AND ELEVATION

14 STAGE CONSTRUCTION DETAILS

15 TEMPORARY CONCRETE BARRIER FOR STAGE CONSTRUCTION

16 BRIDGE DECK REPAIR AND OVERLAY DETAILS

17 EXPANSION JOINT DETAILS

**DESIGN DESIGNATIONS** 

CURRENT ADT: 14,300 (2017)

DESIGN SPEED: 55 MPH

POSTED SPEED: 55 MPH

MU=1.7%, SU=2.3%

1-800-892-0123

OR B11

OTHER PRINCIPAL ARTERIA ICLASS II TURCK ROUTE)

18 EXPANSION JOINT AND REPAIR DETAILS

19 MODIFIED PREFORMED JOINT STRIP SEAL 20 BEAM END REPAIRS

21 BAR SPLICER ASSEMBLY AND MECHANICAL SPLICER DETAILS

## STATE OF ILLINOIS

**DEPARTMENT OF TRANSPORTATION** 

**DIVISION OF HIGHWAYS** 

# PROPOSED HIGHWAY PLANS

FAP ROUTE 316 (IL 26) OVER THE PECATONICA RIVER SECTION (102BR)BDR
PROJECT: NHPP-A06Q(274)

BRIDGE REPAIR STEPHENSON COUNTY

C-92-044-19

#### **EXISTING STRUCTURE**

S.N. 089-0051 A FIVE SPAN P.C.C. I-BEAM (L=429'-4" AND W=93'-2")
SUPERSTRUCTURE WITH OPEN ABDUTMENTS AND SOLID WALL PIERS

# PROJECT ENDS 443 + 00.00 PROJECT BEGINS STA: 373 + 60.00 TOWNSHIP 27 NORTH RANGE 7 & 8 EAST OF 4TH P.M. 20 PROJECT ENDS 21 24 FAP 301 E CURRIER RD 28 FAP 505 FAP 505

062-049202

LICENSED

PRO ESSIONAL

ENG NEFR

/LLINOI

**EXPIRES 11/30/19** 

7-25-2019

MAP NOT TO SCALE

#### LOCATION MAP

GROSS LENGTH = 6.940 FT. = 1.3 Mile Net length = 6.940 FT. = 1.3 Mile

THIS SHEET HAS BEEN SIGNED. SEALED AND DATED ELECTRONICALLY.

NTE. SECTION COUNTY SIGETS NO.
316 (1028R/BDR STEPHENSON 21 | 1
CONTRACT NO. 64M75

D-92-041-19



OUIGG ENGINEERING INC

Kaskaskia

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

Dec to 20 19

ENGINEER OF DESIGN AND ENVIRONMENT

DIRECTOR OF HIGHWAYS PROJECT IMPLEMENTATION

PRINTED BY THE AUTHORITY OF THE STATE OF ILLINOIS

PROJECT MANAGER MAHMOUD ETEMADI, P.E.

CONTRACT NO. 64N75

PROJECT ENGINEER GEOFFREY F. SMITH. P.E.

ENGINEERING SCALES, REDUCED SIZED PLANS WILL NOT

JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION

CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

REV. 11/19/19

#### HIGHWAY STANDARDS

000001.07	CTANDARD COMPOUNC ADDRESSATIONS AND DATTERNS
000001-07	STANDARD SYMBOLYS, ABBREVIATIONS, AND PATTERNS
001001-02	AREA OF REINFORCEMENT BARS
542546-01	FLUSH INLET BOX FOR MEDIAN
610001-08	SHOULDER INLET WITH CURB
701101-05	OFF-RD OPERATIONS, MULTILANE, 15' (4.5m) TO 24" (600mm)
	FROM PAVEMENT EDGE
701426-09	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPER.,
	FOR SPEEDS ≥ 45 MPH
701427-05	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPER.
	FOR SPEEDS < 40 MPH
701431-13	LANE CLOSURE, MULTILANE, UNDIV. WITH CROSSOVER,
, 02 102 20	FOR SPEEDS > 45 MPH TO 55 MPH
701901-08	TRAFFIC CONTROL DEVICES
704001-08	TEMPORARY CONCRETE BARRIER
720006-04	SIGN PANEL ERECTION DETAILS
720011-01	
728001-01	TELESCOPING STEEL SIGN SUPPORT
729001-01	APPLICATIONS OF TYPES A & B METAL POSTS
	(FOR SIGNS & MARKERS
780001-05	TYPICAL PAVEMENT MARKINGS

	1.5"	1.0"
LOCATIONS(S):	IL 26	IL 26
MIXTURE USE(S):	SURFACE	LEVEL BINDER
PG:	SBS PG 70-28	SBS PG 70-28
DESIGN AIR VOIDS:	4.0% @ N70	4.0% @ N50
MIXTURE COMPOSITION:	IL 9.5	IL 4.75
FRICTION AGGREGATE:	D	N/A
MIXTURE WEIGHT:	112 LB/SY/IN	N/A
QUALITY MANAGEMENT PROGRAM:	QC/QA	QC/QA
SUBLOT SIZE:	N/A	N/A
NUMBER OF ROLLER PASSES:	N/A	N/A

#### **GENERAL NOTES**

ALL BORROW/WASTE/USE SITES MUST BE APPROVED BY THE DEPARTMENT PRIOR TO REMOVING ANY MATERIAL FROM THE PROJECT OR INITIATING ANY EARTHMOVING ACTIVITIES, INCLUDING TEMPORARY STOCKPILING OUTSIDE THE LIMITS OF CONSTRUCTION.

THE STRUCTURE WILL RETAIN THE SAME NUMBER: 089-0051

PAVEMENT MARKING SHALL BE DONE ACCORDING TO STANDARD 78001, EXCEPT AS FOLLOW:

- ALL WORDS, SUCH AS ONLY, SHALL BE 8 FEET HIGH.
- ALL NON-FREEWAY ARROWS SHALL BE THE LARGE SIZE.
- THE DISTANCE BETWEEN YELLOW NO-PASSING LINES SHALL BE 8 INCHES, NOT 7 INCHES, AS SHOWN IN THE DETAIL OR TYPICAL LANDE AND EDGE LINES
- CENTERLINE SKIP DASH PAVEMENT MARKING ON MULTI-LANE DIVIDED, MULTI-LANE UNDIVIDED, AND ONE-WAY ROADWAY SHALL BE ACCORDING TO DISTRICT 41.1.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING AND PROTECTING UTILITY PROPERTY DURING CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.39 OF THE STANDARD SPECIFICATIONS. A MINIMUM OF 48 HOURS ADVANCED NOTICE IS REQUIRED FOR NON-EMERGENCY WORK. THE JULIE NUMBER IS 800-892-0123. THE FOLLOWING LISTED UTILITIESLOCATED WITHIN THE PROJECT LIMITS OR IMMEDIATELY ADJACENT TO THE PROJECT CONSTRUCTION LIMITS ARE MEMEBER OF JULIE.

IDOT IS NOT A MEMBER OF JULIE, IF YOU ARE NEAR ANY OVERHEAD LIGHTING, INTERSECTION LIGHTING OR TRAFFIC SIGNALS, CONTACT THE IDOT TRAFFIC OFFICE AND 815-284-5469 AT LEAST 48 HOURS PRIOR TO WORK.

CADD DATA WILL BE AVAILABLE TO CONTRACTORS AND CONSULTANTS WORKING ON THIS PROJECT, ONCE THE PROJECT HAS BEEN AWARDED. THIS INFORMATION WILL BE PROVIDED UPON REQUEST AS MICROSTATION CADD FILES AND GEOPAK COORDINATE GEOMETRY FILES ONLY. IF DATA IS REUIRED IN OTHER FORMATS IT WILL BE YOUR REPONSIBILITY TO MAKE THESE CONVERSIONS. IF ANY DISCREPANCY OR INCONSISTENCY ARISES BETWEEN THE ELECTRONIC DATA AND THE INFORMATION ON THE HARD COPY, THE INFORMATION ON THE HARD COPY SHOULD BE USED. CONTACT THE DISTRICTS PROJECT ENGINEER TO REQUEST THESE FILES.

RELOCATE TEMPORARY IMPACT ATTENUATORS SHALL INCLUDE STORAGE AND TRASNPORTATION TO AND FROM STORAGE, WHEN THE DEVICE IS NOT NEEDED FOR A TIME, AS SHOWN ON THE STAGING PLANS. THIS SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE PER EACH FOR IMPACT ATTENUATORS, RELOCATE OF THE TYPE SPECIFIED.

WHEN RELOCATE TEMPORARY CONCRETE BARRIER IS SPECIFIED, THE WALL SHALL BE REMOVED, STORAGE AND TRANSPORTATION TO AND FROM STORAGE, WHEN THE WALL IS NOT NEEDED FOR A TIME AS SHOWN ON THE STAGING PLANS, RELOCATED AND REINSTATED AT THE NEW LOCATION. THE REINSTALLATION REQUIREMENTS SHALL BE THE SAME AS THOSE FOR A NEW INSTALLATION. THIS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER FOOT FOR RELOCATE TEMPORARY CONCRETE BARRIER.

THE TEMPORARY CONCRETE BARRIER SHALL BE PINNED TO THE PAVEMENT WITH THREE(3) ANCHOR PINS PER SECTION ON THE TRAFFIC SIDE OF THE BARRIER WALL AT THE FOLLWOING LOCATIONS:

STAGE 1 LT 384+55.0 - 384+67.5 LT 396+42.5 - 396+55.0 STAGE 2 RT 384+55.0 - 384+67.5 RT 396+42.5 - 396+55.0

THE BARRIER UNIT AT EACH END SHALL BE ANCHORED AS SPECIFIED IN ARTICLE 704.04. ALL ANCHORING AND PINNING HOLES SHALL BE CORE DRILLED.

ILLINOIS ROUTE 26:ALL CORE HOLES FROM THE TYPE III BARRICADES SHALL BE FILLED IMEADIATELY UPON THE START OF THE PROJECT. ANY AND ALL WATER SHALL BE REMOVED FROM THE CORE HOLES PRIOR TO FILLING. ALL CORE HOLES SHALL BE FILLED WITH A RAPID HARDENING MORTAR OR CONCRETE WHICH SHALL BE MIXED IN A SEPERATE CONTAINAR PRIOR TO PLACEMENT IN THE HOLE. ANY DEPRESSIONS IN THE SURFACE OF THE FILLED CORE HOLES GREATER THAN 1/4 IN. (6mm) AT THE TIME OF FINAL INSPECTION WILL REQUIRE REMOVAL OF THE FILL MATERIAL TO THE DEPTH OF THE PAVEMENT SURFACE.

	VILLETT HOFMANN 1 A S S O C 1 A T E S 1 N C 0016451 AND STREET, DOIDN, IL 61021-0367 1811-264-3381 DESIGN FIRM, #184-000918
--	---

Ĺ	USER NAME = greg	DESIGNED	-	LGN	REVISED -	
,		DRAWN	-	GBG	REVISED -	
,	PLOT SCALE = 2.0000 '/ in.	CHECKED	-	GFS	REVISED -	
_	PLOT DATE = 7/25/2019	DATE	-	7/24/19	REVISED -	

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION** 

							F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
GHW	ΑY	STANI	DAR	DS AND	GENERAL	NOTES	316	(102BR)BDR	STEPHENSON	21	02
									CONTRACT	NO. 6	4N75
SHEET	1	OF	1	SHEETS	STA. N/A	TO STA. N/A		THE INDIS EED A	ID PPO IECT		

# CONSTRUCTION CODE: 0013 20% STATE URBAN

## SUMMARY OF QUANTITIES

CODE NO .	ITEM	UNIT	TOTAL QUANT I TY
40600295	POLYMERIZED BITUMINOUS MATERIALS (TACK COAT)	POUND	2,542
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	435
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	900
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	652
50102400	CONCRETE REMOVAL	CU YD	17.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	21
50300300	PROTECTIVE COAT	SQ YD	65
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2,430
50800515	BAR SPLICERS	EACH	20
52000110	PREFORMED JOINT STRIP SEAL	FOOT	187
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2
67100100	MOBILIZATION	L SUM	1
70107025	CHANGEABLE MESSAGE SIGN (CAL DAY)	CAL DA	56
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	96

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	20,779
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,500
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1,500
70600250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
70600350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	144
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	13,677
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,813
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,920
X0326331	CLEANING AND PAINTING BEARINGS	EACH	28
X0327980	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	6,121
X0931400	INLET BOXES TO BE ADJUSTED (SPECIAL)	EACH	5
X5810100	WATERPROOFING MEMBRANE SYSTEM (SPECIAL)	SQ YD	4,244.5
X7010214	TRAFFIC CONTROL AND PROTECTION, STANDARD 701431 (SPECIAL)	EACH	1

\* SPECIALITY ITEM

SCALE

	Vi for a community frame a construction	١
VVVA	WILLETT HOFMANN	Γ
	messar outside, page a storage	
	T. 8 (S. 2014) THEIR SPHICE PROVIDE RESERVORSE	Г

	USER NAME = luken	DESIGNED ==	LGN	REVISED -	Γ
		DRAWN -	GBG	REVISED -	ı
	PLOT SCALE = 20.0000 '/ in.	CHECKED -	GFS	REVISED -	ĺ
31	PLOT DATE = 8/6/2019	DATE -	7/24/19	REVISED -	

				05 011						F.A.P. RTE.	SECTI	ON	COUNTY	TOTAL SHEETS	SHEET NO.
	S	UMM	ARY	OF QU	ANTIT	IES				316	(102BR)	BDR	STEPHENSON	21	03
									ĺ				CONTRACT	NO. (	54N75
N/A	SHEET 1	OF	2	SHEETS	STA.	N/A	TO	STA.	N/A	i –	II	LLINOIS FED. A	ID PROJECT		

# CONSTRUCTION CODE: 0013 80% FED 20% STATE URBAN

## SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANT I TY
X7030005	TEMPORARY PAVEMENT MARKING REMOVAL	SQ FT	6,983
X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	4,336
X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	390
X7830078	GROOVING FOR RECESSED PAVEMENT MARKING 13"	FOOT	574
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	12
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	30
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	170
Z0024477	TUBULAR MARKER MAINTENANCE	EACH	35
Z0043800	PRECAST PRESTRESSED CONCRETE I-BEAM REPAIR	SQ FT	17

CODE NO.	ITEM	UNIT	TOTAL QUANT I TY

\* SPECIALITY ITEM

SCALE N/A

	USER NAME = greg	DESIGNED -	LGN	REVISED -
ď	USER NAME - greg	DESIGNED	LGN	KEA12ED -
		DRAWN -	GBG	REVISED
	PLOT SCALE = 20.0000 '/ in.	CHECKED -	GFS	REVISED -
3	PLOT DATE = 7/29/2019	DATE -	7/24/19	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

					F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS					
SUMMARY OF QUANTITIES				316	(102BR)BDR	STEPHENSON	21	04					
										S: 12	CONTRACT	NO.	54N75
SHEET	2	OF	2	SHEETS	STA.	N/A	TO STA.	N/A		ILLINOIS FED. A	ID PROJECT		

#### SCHEDULE OF QUANTITIES

# 40600295 POLYMERIZED BITUMINOUS MATERIAL (TACK COAT)

		(	
	STATION	POUND	REMARKS
I-26			
	386+33.3 - 388+08.3	394	EXISTING SURFACE
	386+33.3 - 388+08.3	394	LEVELING BINDER
	388+08.3 - 392+37.7	966	BRIDGE DECK
	392+37.7 - 394+12.7	394	EXISTING SURFACE
	392+37.7 - 394+12.7	394	LEVELING BINDER
	PROJECT TOTAL	2,542	

### 40600625 LEVELING BINDER (MACHINE METHOD)

	STATION	TON	REMARKS
I-26	386+33.3 - 388+08.3 388+08.3 - 392+37.7 392+37.7 - 394+12.7	98 239 98	DEPTH = 1" DEPTH = 1" (BRIDGE DECK) DEPTH = 1"
	PROJECT TOTAL	435	

# 40600982 HOT-MIX ASPHALT SURFACE REMOVAL BUTT JOINT

	STATION	SQ YD	REMARKS
I-26			
	386+33.3 - 388+08.3	450	SOUTH OF BRIDGE (90FT X 45FT
	392+37.7 - 394+12.7	450	NORTH OF BRIDGE (90FT X 45FT
	PROJECT TOTAL	900	

# 40603540 POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D" N70

	STATION	TON	REMARKS
26			
	386+33.3 - 388+08.3	147	DEPTH = 1 1/2"
	388+08.3 - 392+37.7	358	DEPTH = 1 1/2" (BRIDGE DECK
	392+37.7 - 394+12.7	147	DEPTH = 1 1/2"
	PROJECT TOTAL	652	

#### 70107025 CHANGEABLE MESSAGE SIGN (CAL DAY)

	STATION	CAL DAY	REMARKS
I-26			
	IL ROUTE 26	56	2 CHANGEABLE MESSAGE SIGNS
	PROJECT TOTAL	56	

# 70300210\* TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS

			0 2 3
	STATION	SQ FT	REMARKS
I-26			
	LT 382+22	16	LT ARROW
	RT 407+85	16	LT ARROW
	RT 405+64	16	LT ARROW
	RT 406+74	16	LT ARROW
	RT 407+85	16	LT ARROW
	LT 409+12	16	LT ARROW
	PROJECT TOTAL	96	

#### 70300220\* TEMPORARY PAVEMENT MARKING - LINE 4"

STATION	FOOT	REMARKS
I-26		
LT & RT 377+40.0 - 408+19.9	5,708	STAGE 1
LT & RT 381+80.9 - 417+00.0	3,712	STAGE 1
LT 407+41.3 - 408+26.7	102	STAGE 1
LT 408+59.3 - 409+57.3	137	STAGE 1
LT & RT 375+40.0 - 417+00.0	7,186	STAGE 2
LT & RT 375+40.0 - 410+10.0	3,759	STAGE 2
RT 380+49.3 - 381+22.1	81	STAGE 2
RT 381+78.4 - 382+56.5	94	STAGE 2
PROJECT TOTAL	20 779	

## 70400100 TEMPORARY CONCRETE BARRIER REMARKS

I-26				
LT 383+	58.6 - 398+55.0	1,500	_ ;	STAGE
PRO	DJECT TOTAL	1,500		

#### 70400200 RELOCATE TEMPORARY CONCRETE BARRIER

	STATION	FOOT	REMARKS
I-26			
	RT 383+61.7 - 398+59.3	1,500	STAGE 2
	PROJECT TOTAL	1.500	

# 70600250\* IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

	STATION	LACIT	TEMANIS
I-26			
	LT 383+58.6	1	STAGE 1
	LT 398+55.0	1	STAGE 1
	PROJECT TOTAL	2	

# 70600350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 STATION FACH REMARKS

	STATION	EACH	REMARKS
I-26			
	RT 383+61.7	1	STAGE 2
	RT 398+59.3	1	STAGE 2
	PROJECT TOTAL	2	

# 78000100 THERMOPLASTIC PAVEMENT MARKING

	THE CHILD STAFF	JOLJ
STATION	SQ FT	REMARKS
I-26		
LT 382+22	16	LT ARROW
LT 382+93	16	LT ARROW
LT 383+65	16	LT ARROW
RT 405+64	16	LT ARROW
RT 406+74	16	LT ARROW
RT 407+85	16	LT ARROW
LT 409+12	16	LT ARROW
LT 410+33	16	LT ARROW
LT 411+50	16	LT ARROW
PROJECT TOTAL	144	

# 78000200 THERMOPLASTIC PAVEMENT MARKING LINE - LINE 4" STATION FOOT REMARKS

STATION	FOOT	REMAR
I-26		
LT 381+98.6 - 383+89.7	191	SOLIE
LT & RT 375+40.0 - 408+10.6	11,658	DOUBL
RT 405+40.2 - 408+10.6	270	SOLIE
LT & RT 386+33.3 - 394+12.7	1,558	EDGE
PROJECT TOTAL	13,677	

# 78000400 THEMOPLASTIC PAVEMENT MARKING LINE - LINE 6"

	STATION	FOOT	REMARK
I-26	j		
	LT 377+19.3 - 417+00.0	995	SKIP DAS
	RT 375+40.0 - 408+10.6	818	SKIP DAS
	PROJECT TOTAL	1,813	

# 78000600 THERMOPLASTIC PAVEMENT MARKING LINE - LINE 12" STATION FOOT REMARKS

STATION	FOOT	REMARK!
I-26 LT & RT 382+00 - 408+11	1,920	SOLID
PROJECT TOTAL	1,920	

DRAWN - GBG REVISED -	
PLOT SCALE = 20.0000 ' / in. CHECKED - GFS REVISED -	
PLOT DATE = 8/6/2019 DATE - 7/24/19 REVISED -	

# X0327980\* PAVEMENT MARKING REMOVAL - WATER BLASTING

LT 381+98.6 - 383+89.7 63 4" SOLID (STACE AND CONTROL OF A CONTROL OF	STATION	SQ FT	REMARKS
LT 381+98.6 - 383+89.7 63 4" SOLID (STACL AND COLD COLD COLD COLD COLD COLD COLD COL	I-26		
LT & RT 381+98.6 - 408+10.6 RT 405+40.2 - 408+10.6 RT 405+40.2 - 408+10.6 RT 377+40.0 - 408+10.6 253 4" SOLIO (STAC RT 377+19.3 - 383+80.8 38 4" SKIP (STAG LT 377+19.3 - 383+80.8 38 4" SKIP (STAG LT 408+89.7 - 411+74.9 94 4" SOLIO (STAC RT 375+10.0 - 381+30.9 391 4" DOUBLE (STAC RT 375+40.0 - 377+40.0 17 4" SKIP (STAG LT & RT 382+00.0 - 408+11.0 1,286 8" SOLIO (STAC LT 382+93.0 16 LT ARROW (STAC LT 382+93.0 16 LT ARROW (STAC LT 382+93.0 16 LT ARROW (STAC LT 383+65.0 16 LT ARROW (STAC LT 383+65.0 16 LT ARROW (STAC LT 405+64.0 16 LT ARROW (STAC LT 405+64.0 16 LT ARROW (STAC LT 405+85.0 16 LT ARROW (STAC LT 405+85.0 16 LT ARROW (STAC LT 409+12.0 16 LT ARROW (STAC LT 4109+12.0 16 LT ARROW (STAC LT 410+33.0 LT 410+33.0 STAC LT 410+33.0 LT 410+33.0 STAC LT 410+33.0 LT 410+33.	LT 381+80.8 - 417+00.0	290	4" SKIP (STAGE 1)
RT 405+40.2 - 408+10.6 89 4" SOLID (STAC RT 377+40.0 - 408+10.6 253 4" SKIP (STAG RT 377+40.0 - 408+10.6 253 4" SKIP (STAG LT 377+19.3 - 383+80.8 38 4" SKIP (STAG LT 408+89.7 - 411+74.9 94 4" SOLID (STAC RT 375+10.0 - 381+30.9 391 4" DOUBLE (STAC RT 375+40.0 - 377+40.0 17 4" SKIP (STAG LT & RT 382+00.0 - 408+11.0 1,286 8" SOLID (STAC LT 382+22.0 16 LT ARROW (STAC LT 382+93.0 16 LT ARROW (STAC LT 382+93.0 16 LT ARROW (STAC LT 383+65.0 16 LT ARROW (STAC LT 405+64.0 16 LT ARROW (STAC LT 409+12.0 16 LT ARROW (STAC LT 409+12.0 16 LT ARROW (STAC LT 410+33.0 16 LT ARROW (STAC	LT 381+98.6 - 383+89.7	63	4" SOLID (STAGE 1)
RT 377+40.0 - 408+10.6	LT & RT 381+98.6 - 408+10.6	3,456	4" DOUBLE (STAGE 1)
LT 377+19.3 - 383+80.8 38 4" SKIP (STAG LT 408+89.7 - 411+74.9 94 4" SOLID (STAG RT 375+10.0 - 381+30.9 391 4" DOUBLE (STAG RT 375+40.0 - 377+40.0 17 4" SKIP (STAG LT & RT 382+00.0 - 408+11.0 1,286 8" SOLID (STAG LT 382+22.0 16 LT ARROW (STAG LT 382+93.0 16 LT ARROW (STAG LT 383+65.0 16 LT ARROW (STAG LT 406+74.0 16 LT ARROW (STAG LT 406+74.0 16 LT ARROW (STAG LT 409+12.0 16 LT ARROW (STAG LT 409+12.0 16 LT ARROW (STAG LT 409+12.0 16 LT ARROW (STAG LT 410+33.0 STAG LT 410+33.	RT 405+40.2 - 408+10.6	89	4" SOLID (STAGE 1)
LT 408+89.7 - 411+74.9 94 4" SOLID (STAC RT 375+10.0 - 381+30.9 391 4" DOUBLE (STAC RT 375+40.0 - 377+40.0 17 4" SKIP (STAG LT & RT 382+00.0 - 408+11.0 1,286 8" SOLID (STAC LT 382+22.0 16 LT ARROW (STA LT 382+93.0 16 LT ARROW (STA LT 383+65.0 16 LT ARROW (STA RT 405+64.0 16 LT ARROW (STA RT 405+64.0 16 LT ARROW (STA RT 407+85.0 16 LT ARROW (STA LT 409+12.0 16 LT ARROW (STA LT 4709+12.0 16 LT ARROW (STA LT 410+33.0 16 LT ARROW (STA	RT 377+40.0 - 408+10.6	253	4" SKIP (STAGE 1)
RT 375+10.0 - 381+30.9 391 4" DOUBLE (START 375+40.0 - 377+40.0 17 4" SKIP (START 375+40.0 - 377+40.0 17 4" SKIP (START 382+00.0 - 408+11.0 1,286 8" SOLID (START 182+22.0 16 LT 382+93.0 16 LT ARROW (START 182+93.0 16 LT ARROW (START 1405+64.0 16 LT ARROW (START 405+64.0 16 LT ARROW (START 406+74.0 16 LT ARROW (START 407+85.0 16 LT ARROW (START 407+85.0 16 LT ARROW (START 409+12.0 16 LT ARROW (START 409+12.0 16 LT ARROW (START 409+13.0 16 LT ARROW	LT 377+19.3 - 383+80.8	38	4" SKIP (STAGE 2)
RT 375+40.0 - 377+40.0 17 4" SKIP (STAG LT & RT 382+00.0 - 408+11.0 1,286 8" SOLID (STAG LT 382+22.0 16 LT ARROW (STAG LT 382+93.0 16 LT ARROW (STAG LT 383+65.0 16 LT ARROW (STAG LT 383+65.0 16 LT ARROW (STAG LT 383+65.0 16 LT ARROW (STAG LT 406+74.0 16 LT ARROW (STAG LT 406+74.0 16 LT ARROW (STAG LT 407+85.0 16 LT ARROW (STAG LT 409+12.0 16 LT ARROW (STAG LT 410+33.0 16 LT 410+33.0 16 LT ARROW (STAG LT 410+33.0 16 LT 410+	LT 408+89.7 - 411+74.9	94	4" SOLID (STAGE 2)
LT & RT 382+00.0 - 408+11.0	RT 375+10.0 - 381+30.9	391	4" DOUBLE (STAGE 2)
LT 382+22.0 16 LT ARROW (STA LT 382+93.0 16 LT ARROW (STA LT 383+65.0 16 LT ARROW (STA RT 405+64.0 16 LT ARROW (STA RT 406+74.0 16 LT ARROW (STA RT 407+85.0 16 LT ARROW (STA LT 409+12.0 16 LT ARROW (STA LT 410+33.0 16 LT ARROW (STA	RT 375+40.0 - 377+40.0	17	4" SKIP (STAGE 2)
LT 382+93.0 16 LT ARROW (STA LT 383+65.0 16 LT ARROW (STA RT 405+64.0 16 LT ARROW (STA RT 406+74.0 16 LT ARROW (STA RT 407+85.0 16 LT ARROW (STA LT 409+12.0 16 LT ARROW (STA LT 410+33.0 16 LT ARROW (STA	LT & RT 382+00.0 - 408+11.0	1,286	8" SOLID (STAGE 1)
LT 383+65.0 16 LT ARROW (STA RT 405+64.0 16 LT ARROW (STA RT 406+74.0 16 LT ARROW (STA RT 407+85.0 16 LT ARROW (STA LT 409+12.0 16 LT ARROW (STA LT 410+33.0 16 LT ARROW (STA	LT 382+22.0	16	LT ARROW (STAGE 1)
RT 405+64.0 16 LT ARROW (STA RT 406+74.0 16 LT ARROW (STA RT 407+85.0 16 LT ARROW (STA LT 409+12.0 16 LT ARROW (STA LT 410+33.0 16 LT ARROW (STA	LT 382+93.0	16	LT ARROW (STAGE 1)
RT 406+74.0 16 LT ARROW (STA RT 407+85.0 16 LT ARROW (STA LT 409+12.0 16 LT ARROW (STA LT 410+33.0 16 LT ARROW (STA	LT 383+65.0	16	LT ARROW (STAGE 1)
RT 407+85.0 16 LT ARROW (STA LT 409+12.0 16 LT ARROW (STA LT 410+33.0 16 LT ARROW (STA	RT 405+64.0	16	LT ARROW (STAGE 1)
LT 409+12.0 16 LT ARROW (STA LT 410+33.0 16 LT ARROW (STA	RT 406+74.0	16	LT ARROW (STAGE 1)
LT 410+33.0 16 LT ARROW (STA	RT 407+85.0	16	LT ARROW (STAGE 1)
	LT 409+12.0	16	LT ARROW (STAGE 1)
LT 411+50.0 16 LT ARROW (STA	LT 410+33.0	16	LT ARROW (STAGE 1)
	LT 411+50.0	16	LT ARROW (STAGE 1)
PROJECT TOTAL 6,121	PROJECT TOTAL	6,121	

#### X0931400\* INLET BOXES TO BE ADJUSTED (SPECIAL)

	STATION	EACH	REMARKS
I-26			
	387+76.37	1	STD 542546 (DOUBLE)
	LT 387+87.37	1	STD 610001 (TYPE F)
	RT 387+87.37	1	STD 610001 (TYPE F)
	LT 392+58.71	1	STD 610001 (TYPE F)
	RT 392+58.71	1	STD 610001 (TYPE F)
	PROJECT TOTAL	5	

#### X7010214\* TRAFFIC CONTROL AND PROTECTION, STANDARD 701431 (SPECIAL) STATION EACH REMARKS

	STATION	EACH
I-26		
	IL ROUTE 26	1
	PROJECT TOTAL	1

## X7030005\* TEMPORARY PAVEMENT MARKING REMOVAL

STATION	SQ FT	REMARKS
I-26		
LT & RT 377+40.0 - 408+19.9	1,916	4" LINE (STAGE 1)
LT & RT 381+80.9 - 417+00.0	1,225	4" LINE (STAGE 1)
LT 407+41.3 - 408+26.7	34	4" LINE (STAGE 1)
LT 408+59.3 - 409+57.3	45	4" LINE (STAGE 1)
LT & RT 375+40.0 - 417+00.0	2,371	4" LINE (STAGE 2)
LT & RT 375+40.0 - 410+10.0	1,240	4" LINE (STAGE 2)
RT 380+49.3 - 381+22.1	27	4" LINE (STAGE 2)
RT 381+78.4 - 382+56.5	31	4" LINE (STAGE 2)
TEMP LEFT TURN ARROW	94	STAGE 1 & 2
PROJECT TOTAL	6,983	

# X7830070\* GROOVING FOR RECESSED PAVEMENT MARKING 5"

STATION	FOOT	REMARKS
I-26 LT & RT 386+33.3 - 394+12.7 LT & RT 386+33.3 - 394+12.7	2,778 1,558	DOUBLE EDGE
PROJECT TOTAL	4,336	

## X7830074\* GROOVING FOR RECESSED PAVEMENT

	STATION	FOOT	REMARKS
I-26	LT 386+33.3 - 394+12.7 RT 386+33.3 - 394+12.7	195 195	SKIP DASH SKIP DASH
	PROJECT TOTAL	390	

# X7830078\* GROOVING FOR RECESSED PAVEMENT MARKING 13"

STATION	FOOT	REMARK
I-26		
LT & RT 386+33.3 - 394+12.7	574	SOLID
PROJECT TOTAL	574	


#### Z0024477\* TUBULAR MARKER MAINTENANCE


	STATION	EACH	REMARKS
I-26	RT 387+75.0 - 393+50.0	17	STAGE 1
	LT 375+75.0 - 393+30.0	18	STAGE 1 STAGE 2
	PROJECT TOTAL	35	





USER NAME = luken	DESIGNED	-	LGN	REVISED -
	DRAWN	-	GBG	REVISED -
PLOT SCALE = 20.0000 ' / in.	CHECKED	-	GFS	REVISED -
PLOT DATE = 8/6/2019	DATE	-	7/24/19	REVISED -


	SCHEDULE OF QUANTITIES			SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
				(102BR)BDR	STEPHENSON	21	06
					CONTRACT	NO. 6	4N75
	SCALE N/A	SHEET 2 OF 2 SHEETS STA. N/A TO STA. N/A		ILLINOIS FED. A	ID PROJECT		














Existing Structure: S.N. 089-0051, originally built in 1983, as a five-span PPC I-Beam superstructure with open abutments and solid wall piers. The back to back length = 429'-4" and the out to out width = 47'-2". In 1991 the bridge was widened in kind to a new out to out width = 93'-2". Structure is to be repaired as detailed in these plans. Stage construction will be used to maintain one lane of traffic in each direction.


#### DESIGN SPECIFICATIONS

for Highway Bridges - LFD


LOADING HS20-44

Existing and Proposed 2002 AASHTO Standard Specifications

No Salvage



#### ELEVATION



#### DESIGN STRESSES

#### FIELD UNITS (EXIST. CONST.,

f'c = 3,500 psi (Concrete Slab) fy = 60,000 psi (Reinforcement for Slab)

#### PRECAST PRESTRESSED UNITS (EXIST. CONST.)

 $f'c = 6,000 \ psi$ 

f'ci = 4,200 psi (1983 Original Const.)

f'ci = 4,800 psi (1991 Widening Const.)

 $f's = 270,000 \text{ psi } (\frac{1}{2}" \text{ Ø Strands})$ 

 $f'si = 189,000 psi (\frac{1}{2}" \emptyset Strands)$ 

#### FIELD UNITS (NEW CONST.)

f'c = 4,000 psi (Superstructure)fy = 60,000 psi



#### ema 7/31/2019 Michael D. Cima. Illinois S.E. 081-005984

#### SCOPE OF WORK

- 1. Replace the transverse expansion joints located at the ends of the bridge deck using the shallow replacement detail.
- 2. Deck slab partial depth and full depth repairs.
- 3. Add waterproofing membrane system with  $2\frac{1}{2}$ " HMA Overlay.
- 4. Beam repairs at PPC I-Beam ends.
- 5. Clean and paint existing bearings below transverse joints.

#### INDEX OF SHEETS

- 1. General Plan and Elevation
- 2. Stage Construction Details
- 3. Temporary Concrete Barrier for Stage Construction
- 4. Bridge Deck Repair and Overlay Details
- 5. Expansion Joint Details
- 6. Expansion Joint and Repair Details
- 7. Modified Preformed Joint Strip Seal
- 8. Beam End Repairs
- 9. Bar Splicer Assembly and Mechanical Splicer Details

#### TOTAL BILL OF MATERIAL

ITEM	UNIT	SUPER	SUB	TOTAL
Polymerized Hot-Mix Asphalt Surface Course, Mix "D", N70	Ton	596.9		596.9
Concrete Removal	Cu. Yd.	17.2		17.2
Concrete Superstructure	Cu. Yd.	21		21
Protective Coat	Sq. Yd.	65		65
Reinforcement Bars, Epoxy Coated	Pound	2,430		2,430
Bar Splicers		20		20
Preformed Joint Strip Seal	Foot	187		187
Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)		12		12
Deck Slab Repair (Full Depth, Type I)	Sq. Yd.	30		30
Deck Slab Repair (Partial)		170		170
Precast Prestressed Concrete I-Beam Repair		17		17
Cleaning and Painting Bearings	Each	28		28
Waterproofing Membrane System (Special)	Sq. Yd.	4,244.5		4,244.5

#### GENERAL NOTES

No field welding is permitted except as specified in the contract documents.

Reinforcement bars designated (E) shall be epoxy coated.

Plan dimensions and details relative to existing plans are subject to nominal construction variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.

Protective coat shall not be applied to surfaces to which waterproofing membrane system is applied.

Existing reinforcement shall be cleaned and incorporated into the new construction. Cost included with Concrete Removal.

The protective coat shall be applied to the top and inside faces of the new parapets and to the new deck sections on either side of the expansion ioints.


Deck Slab Repair (Full Depth Type I) is only to be used on the Stage II Construction side of the deck.

The Contractor shall use extreme care during concrete removal so as not to damage the PPC I-Beams.

Joint openings shall be adjusted according to Art. 520.04 of the standard specifications when the deck is poured at an ambient temperature other than 50°F.

The deck surface at abutment joints shall have its finish tined according to Art. 420.09(e)(1) of the standard specifications. Cost included with Concrete Superstructure.

4th P.M.



GENERAL PLAN & ELEVATION ILLINOIS ROUTE 26 OVER PECATONICA RIVER SECTION (102BR)BDR STEPHENSON COUNTY STATION 390+23.08 STRUCTURE NO. 089-0051



USER NAME = cstokes	DESIGNED - CFS	REVISED -
0890051-64N75-001-GPE.dgn	CHECKED - KFO	REVISED -
PLOT SCALE = 60.0000 ' / in.	DRAWN - CFS/KFO	REVISED -
PLOT DATE = 7/31/2019	CHECKED - MDC	REVISED -


Expires 11/30/2020


STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION** 

			–	ELEVATION 89-0051
SHEET	1	OF	9	SHEETS

A.P. RTE	SECT	ΓΙΟΝ		COUNTY	TOTAL SHEETS	SHE
26	(102BR)BDR		STEPHENSON	21	13	
			CONTRA	CT NO. 6	34N7	
ILLINOIS FED A			ID PROJECT			

7/31/2019 5:02:43 PM





QUIGG ENGINEERING INC

 USER NAME
 =
 Cslokes
 DESIGNED
 CFS
 REVISED

 0890051-64N75-002-Const. Staging.dgn
 CHECKED
 KFO
 REVISED

 PLOT SCALE
 =
 0:2.0000 :" / in.
 DRAWN
 CFS/KFO
 REVISED

 PLOT DATE
 =
 7/31/2019
 CHECKED
 MDC
 REVISED


STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION STAGE CONSTRUCTION DETAILS
STRUCTURE NO. 089-0051

SHEET 2 OF 9 SHEETS

P. SECTION COUNTY TOTAL SHEETS NO.

(102BR)BDR STEPHENSON 21 14


CONTRACT NO. 64N75



– See Detail I, II or III When "A" is 3'-1" or less, the temporary concrete barrier shall be restrained to the new slab according to Detail I, II or III. No restraint is required when "A" is greater than 3'-1".

#### NEW SLAB OR NEW DECK BEAM

8-11-2017





EXISTING SLAB

EXISTING DECK BEAM

# 1x8 UNC US Std. 11/16" I.D. x 21/2" O.D. x approx. 8 guage thick washer RESTRAINING PIN


#### SECTIONS THRU SLAB OR DECK BEAM





#### STEEL RETAINER P 1" x 8" x "W"

(Detail I and II)



STEEL RETAINER P 1" x "H" x 10" (Detail III)

#### BAR SPLICER FOR #4 BAR - DETAIL III

Cost of retainer assembly is included with Temporary Concrete Barrier. A retainer assembly shall be located at the approximate ( of each temporary

The retainer plate shall not be removed until the concrete on the adjacent stage is ready to be poured. For Detail III applications the retainer plate shall not be removed until just prior to placing the adjacent beam.

When the 'A' dimension is less than  $1\frac{1}{2}$ ", the wood block shall be omitted and the barrier shall be placed in direct contact with the steel retainer plate. For deck beam applications the minimum required 'A' distance is 6" to accommodate the shear key clamping device.

- Detail I Installation for a new bridge deck or bridge slab.
- Detail II Installation for a new deck beam with an initial concrete wearing surface. Additional bar splicers shall be provided at 6'-0" centers and paired with the bar splicers of the concrete wearing surface reinforcement to accommodate the installation of the retainer assemblies. The cost of the additional bar splicers is included with the concrete wearing surface.
- Detail III Installation for a new deck beam with no initial wearing surface or with an initial hot-mix asphalt (HMA) wearing surface present. The deck beam directly beneath the temporary concrete barrier shall be fabricated with bar splicer inserts in the side of the beam, as detailed, to accommodate the installation of the retainer assemblies. A pair of bar splicers, 6" apart, shall be placed at 6'-0" centers along the length of the beam. The cost of the bar splicers is included with the deck beam.

COUNTY

STEPHENSON 21 15

CONTRACT NO. 64N75


R - 27


DESIGNED - CFS REVISED -SER NAME = cstokes 0890051-64N75-003-Temp. Concrete Barrier.dgr CHECKED - KFO REVISED -- CFS/KFO REVISED -PLOT DATE = 7/31/2019 CHECKED - MDC REVISED -

**STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION** 

SECTION TEMPORARY CONCRETE BARRIER FOR STAGE CONSTRUCTION (102BR)BDR **STRUCTURE NO. 089-0051** SHEET 3 OF 9 SHEETS

QUIGG ENGINEERING INC 7/31/2019 5:02:46 PM





#### Notes:

Overlay consist of waterproofing membrane system (special) with  $2\frac{1}{2}$ " HMA surface layer.

Deck Slab Repair (Partial) areas are estimated, and will be field verified by the Engineer prior to patching. The Engineer shall show actual locations of deck repairs on the as-built plans.

The Contractor will take extreme care not to damage the  $2\frac{1}{2}$ " Precast Partial Depth Deck Planks during Stage I Partial Depth Patching operations. If damaged, the precast planks will be replaced at the Contractors expense.

#### CROSS SECTION (Looking North) Edge of Parapet -Existing Drain Pipe – 1" Min. Thickness TOP PLAN of HMA at Drain Overlay Transition at Drain Pipes

#### HMA SURFACE LAYER DESIGN

Mixture Use(s)	Surface	Level Binder
Thickness	1.5"	1"
PG	SBS PG 70-28	SBS PG 70-28
Design Air Voids	4.0% @ 70	4% @ N50
Mixture Composition	IL 9.5	IL 4.75
Friction Aggregate	D	N/A
Mixture Weight	112 lb/sy/in	N/A

#### BILL OF MATERIAL


Unit	Total
Ton	596.9
Sq. Yd.	65
Sq. Yd.	4,244.5
Sq. Yd.	170
Sq Yd.	30
	Ton Sq. Yd. Sq. Yd. Sq. Yd.




USER NAME = cstokes	DESIGNED - CFS	REVISED -
0890051-64N75-004-Deck Overlay.dgn	CHECKED - KFO	REVISED -
PLOT SCALE = 0:2.0000 ':" / in.	DRAWN - CFS/KFO	REVISED -
PLOT DATE = 7/31/2019	CHECKED - MDC	REVISED -

**STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION** 


BRIDGE DECK REPAIR AND OVERLAY DETAILS STRUCTURE NO. 089-0051  SHEET 4 OF 9 SHEETS		SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		(102BR)BDR	STEPHENSON	21	16
			CONTRA	CT NO. 6	34N75
		ILLINOIS FED.	AID PROJECT		



7/31/2019 5:02:48 PM



7/31/2019 5:02:50 P



#### ELEVATION AT PARAPET

(Skews > 30° shown. Skews ≤ 30° similar except as shown in plan view.)

DETAIL A

Concrete flush with back face of ¾" plate Ø. € Concrete flush with back face of ¾" plate

TRIMETRIC VIEW (Showing embedded plates only)

# Locking edge rail-15/8" @ 50°F, N. Abut. 25/8" @ 50°F, S. Abut. Top of concrete Strip seal 2½" @ 50°F, N. Abut. 3½" @ 50°F, S. Abut.

8-11-17


SHOWING ROLLED RAIL JOINT

## Locking edge rail-1⅓" @ 50°F, N. Abut 25/8" @ 50°F, S. Abut. Top of concrete Strip seal \* $\frac{1}{8}$ " Ø x 6" studs @ 6" cts. (alternate angled/bent studs with horizontal studs)

 $\frac{3}{6}$ "  $\phi$  threaded rods in  $\frac{7}{6}$ "  $\phi$  holes at  $\pm 4$ '-0" cts. for holding the proper joint opening based on the temperature during the deck pour. Place to miss studs. All rods shall be burned, or sawed off flush with the plates after concrete is set.


#### SECTION A-A

\* Granular or solid flux filled headed studs conforming to Article 1006.32 of the Std. Specs., automatically end welded.



#### LOCKING EDGE RAILS

\*\* Back gouge not required if complete joint penetration is verified by mock-up.



The strip seal shall be made continuous and shall have a minimum thickness of  $\frac{1}{4}$ ". The configuration of the strip

are not permitted. The gland shall be sized for a maximum

The locking edge rails depicted are configured for typical

applications and are conceptual only. The actual configuration

of the locking edge rails and matching strip seal may vary from

manufacturer to manufacturer provided they fit the application and meet the minimum anchorage shown. Flanged edge rails,

however, will not be allowed. Locking edge rails may exceed the

4½" maximum depth provided the anchorage system is revised

The manufacturer's recommended installation methods

All steel components shall be galvanized after fabrication according to Article 520.03 of the Standard Specifications. The Maximum space between locking edge rail segments

shall be  $\frac{3}{16}$ " and sealed with a suitable sealant; however, any

Cost of parapet sliding plates, embedded plates, and

anchorage studs included with Preformed Joint Strip Seal. 34" F-shape barrier shown, 42" F-shape similar as noted. The concrete opening below the strip seal will vary based

on the locking edge rail chosen by the Contractor. Deck and

parapet lengths shown elsewhere in the plans are dimensioned

to the concrete opening, not the joint opening, and are based

on the rolled locking edge rail. If the Contractor elects to use a different locking edge rail, dimensional adjustments may be required. One exception to this would be the strip seal joint at the end of the precast bridge approach slab. For these cases the pavement connector length shall be adjusted, not the

rail joint within 10' measured perpendicular to the face of the curb or parapet shall be welded as shown in the locking edge

according to the manufacturer's recommendation.

seal shall match the configuration of the locking edge

rated movement of 4 inches.

shall be followed.

rail splice detail.

length of the bridge approach slab.

rails. Open or "webbed" strip seal gland configurations

#### LOCKING EDGE RAIL SPLICE

The inside of the locking edge rail groove shall be free of weld residue. Rolled rail shown, welded rail similar.

#### BILL OF MATERIAL

Item	Unit	Total	1
Preformed Joint Strip Seal	Foot	187	]
			-

EJ-SS

5/8" Ø x 6" Studs



DESIGNED - CFS REVISED -SER NAME = cstokes 890051-64N75-007-PJS Seal.dgr CHECKED - KFO REVISED -OT SCALE = 0:2.0000 ':" / in. CFS/KFO REVISED -PLOT DATE = 7/31/2019 CHECKED - MDC REVISED -


**STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION** 

SHOWING WELDED RAIL JOINT

PREFORMED JOINT STRIP SEAL **STRUCTURE NO. 089-0051** SHEET 7 OF 9 SHEETS

- A.P. RTE	SECT	SECTION		COUNTY	TOTAL SHEETS	SHEE NO.
26	(102BR	)BDR		STEPHENSON	21	19
CONTRACT NO. 64N					34N75	
HI MORE SER AIR PROJECT						

7/31/2019 5:02:51 PM




7/31/2019 5:02:54 PM

#### STANDARD BAR SPLICER ASSEMBLY

Threaded splicer bar length = min. lap length +  $1\frac{1}{2}$ " + thread length


\* Epoxy not required on Bar Splicer Assembly components used in conjunction with black bars.

Location	Bar	No. assemblies	Minimum
Eocation	size	required	lap length
N. End of Deck	#5	3	3'-6"
S. End of Deck	#5	3	3'-6"
N. Abut. Hatchblock	#5	4	3'-6"
S. Abut. Hatchblock	#5	4	3'-6"
N. Appr. Pavement	#5	3	3'-6"
S. Appr. Pavement	#5	3	3'-6"




#### INSTALLATION AND SETTING METHODS

"A": Set bar splicer assembly by means of a template bolt.
"B": Set bar splicer assembly by nailing to wood forms or cementing to steel forms.
(E): Indicates epoxy coating.



#### STANDARD MECHANICAL SPLICER

Location	Bar size	No. assemblies required



Notes:

Splicer bars shall be deformed with threaded ends and have a minimum  $60\ ksi$  yield strength.

All reinforcement shall be lapped and tied to the splicer bars.

Bar splicer assemblies shall be epoxy coated according to the requirements for reinforcement bars. See Section 508 of the Standard Specifications. See approved list of bar splicer assemblies and mechanical splicers for

COUNTY

STEPHENSON 21 21

CONTRACT NO. 64N75

alternatives.

BSD-1

2-17-2017

 USER NAME
 =
 cstokes
 DESIGNED
 CFS
 REVISED

 0890051-64N75-009-Bar Splicer.dgn
 CHECKED
 KFO
 REVISED

 PLOT SCALE
 =
 0:2.0000 ':"/ in.
 DRAWN
 CFS/KFO
 REVISED

 PLOT DATE
 =
 7/31/2019
 CHECKED
 MDC
 REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BAR SPLICER ASSEMBLY AND MECHANICAL SPLICER DETAILS
STRUCTURE NO. 089-0051

SHEET 9 OF 9 SHEETS

FAP. RTE. 26 (102BR)BDR