

MODEL: SQQ [Sheet]
FILE NAME: c:\pw\work\hrt\hrtzeld0310057\0774459-sheets-SQQ.dgn

80% FED 20% STATE				CONSTR. CODE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY
				0005
				RURAL
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	40	40
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	360	360
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	146836	146836
40600370	LONGITUDINAL JOINT SEALANT	FOOT	71960	71960
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	358	358
40600990	TEMPORARY RAMP	SQ YD	405	405
40603219	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-9.5FG, N90	TON	21297	21297
40604164	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N90	TON	24339	24339
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	290	290
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	204145	204145
44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	14136	14136
44000400	GUTTER REMOVAL	FOOT	3964	3964
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SQ YD	3390	3390
44201831	CLASS D PATCHES, TYPE III, 15 INCH	SQ YD	970	970
44201833	CLASS D PATCHES, TYPE IV, 15 INCH	SQ YD	6000	6000
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	3942	3942
48203012	HOT-MIX ASPHALT SHOULDERS, 3 3/4"	SQ YD	220	220
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1321	1321



80% FED 20% STATE				CONSTR. CODE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY
				0005
				RURAL
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	35936	35936
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9
67100100	MOBILIZATION	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	28	28
70300100	SHORT TERM PAVEMENT MARKING	FOOT	29223	29223
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	2435	2435
70300221	TEMPORARY PAVEMENT MARKING - LINE 4" - PAINT	FOOT	182276	182276
70300241	TEMPORARY PAVEMENT MARKING - LINE 6" - PAINT	FOOT	85	85
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	182276	182276
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	85	85
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	634	634
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	634	634
78300202	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	60801	60801
X4400102	SURFACE REMOVAL, VARIABLE DEPTH (SPECIAL)	SQ YD	2961	2961
Z0049799	PROTECTING OR RESETTING SURVEY MARKERS	EACH	38	38

*SPECIALTY ITEM



REVISED 1-6-2025

REV - MS

	USER NAME = kaleb.hirtzel	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					774	(101, 102) RS-2	Shelby	43	3
		CHECKED -	REVISED -					CONTRACT NO. 74A59				
	PLOT DATE = 10/9/2024	DATE -	REVISED -		SCALE:	SHEET 1	OF 1	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	

MODEL: Schedules [Sheet]
FILE NAME: c:\pawork\paw\dot\hrtz\k\ud910057\D774A59-sheets-Schedules.dgn

PAVING SCHEDULE			HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	HOT-MIX ASPHALT SURFACE REMOVAL, 3¾"	GUTTER REMOVAL	EXCAVATING AND GRADING EXISTING SHOULDERS	BITUMINOUS MATERIALS (TACK COAT)	LONGITUDINAL JOINT SEALANT	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-9.5 FG, N90	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N90	HOT-MIX ASPHALT SHOULDERS, 3¾"	HOT-MIX ASPHALT SHOUDERS, 8"	AGGREGATE WEDGE SHOULDERS, TYPE B	SHOULDER RUMBLE STRIPS, 8 INCH
STATIONING		LENGTH														
FROM	TO	FEET	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	UNIT	POUND	FOOT	TON	TON	SQ YD	SQ YD	TON	FOOT
1+85	2+20	35.0	116.7	43.3	-	-	-	-	78.8	35.0	11.4	13.1	-	-	7.3	70.0
2+20	10+36	816.0	-	-	2720.0	-	-	-	1836.0	816.0	266.6	304.6	-	-	170.4	1632.0
10+36	12+30	194.0	-	-	646.7	-	-	-	436.5	194.0	63.4	72.4	-	-	29.5	388.0
12+30	20+52	822.0	-	-	2740.0	-	-	-	1849.5	822.0	268.5	306.9	-	-	78.0	1644.0
20+52	20+87	35.0	116.7	43.3	-	-	-	-	78.8	35.0	11.4	13.1	-	-	3.3	70.0
20+87	22+17	130.0	BRIDGE OMISSION													-
22+17	22+42	25.0	-	43.3	-	83.3	-	-	56.3	25.0	8.2	9.3	-	-	0.0	50.0
22+42	22+77	35.0	-	-	-	116.7	-	-	78.8	35.0	11.4	13.1	-	-	4.0	70.0
22+77	23+63	86.0	-	-	286.7	-	-	-	193.5	86.0	28.1	32.1	-	-	9.8	172.0
23+63	23+83	20.0	-	-	66.7	-	-	-	45.0	20.0	6.5	7.5	-	-	1.7	40.0
23+83	46+18.11	2235.1	-	-	7450.4	-	-	-	5029.0	2235.1	730.1	834.4	-	-	121.0	4230.2
46+18.11	45+89.96	-	STATION EQUATION													-
45+89.96	46+37	47.0	-	-	156.8	-	-	-	105.8	47.0	15.4	17.6	-	-	2.7	94.1
46+37	47+29	92.0	-	-	301.6	-	-	-	203.6	92.0	29.6	33.8	-	-	3.9	184.0
47+29	94+86	4757.0	-	-	13742.4	-	-	-	9276.2	4757.0	1346.8	1539.2	-	-	246.8	-
94+86	98+32	346.0	-	-	1076.4	-	-	-	726.6	346.0	105.5	120.6	-	-	19.7	346.0
98+32	98+95	63.0	-	-	203.0	-	-	-	137.0	63.0	19.9	22.7	-	-	4.8	126.0
98+95	99+30	35.0	-	-	-	118.6	-	-	80.1	35.0	11.6	13.3	-	-	3.3	70.0
99+30	99+52	22.0	-	-	-	90.4	-	-	46.2	22.0	6.7	7.7	-	-	1.0	44.0
99+52	101+14	162.0	-	62.1	-	774.0	-	-	303.8	162.0	44.1	50.4	-	-	0.0	324.0
101+14	104+36	322.0	BRIDGE OMISSION													-
104+36	105+92	156.0	-	62.1	-	745.3	-	-	292.5	156.0	42.5	48.5	-	-	0.0	312.0
105+92	106+22	30.0	-	-	-	123.3	-	-	63.0	30.0	9.1	10.5	-	-	0.9	60.0
106+22	106+57	35.0	-	-	-	120.6	-	-	81.4	35.0	11.8	13.5	-	-	2.0	70.0
106+57	110+45	388.0	-	-	1336.4	-	-	-	902.1	388.0	131.0	149.7	-	-	22.1	776.0
110+45	112+79	234.0	-	-	741.0	-	-	-	500.2	234.0	72.6	83.0	-	-	15.5	468.0
112+79	115+45	266.0	-	-	768.4	-	-	-	518.7	266.0	75.3	86.1	-	-	20.2	-
115+45	135+27	1982.0	-	-	6496.6	-	3964.0	40.0	4385.2	1982.0	636.7	727.6	-	1321.3	112.9	3950.0
135+27	142+00.00	673.0	-	-	1944.2	-	-	-	1312.4	673.0	190.5	217.8	-	-	37.5	-

 REVISED SHEET 1-6-2025

	USER NAME = kaleb.hirtzel	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					774	(101, 102) RS-2	Shelby	43	8
		CHECKED -	REVISED -					CONTRACT NO. 74A59				
	PLOT DATE = 9/4/2024	DATE -	REVISED -		SCALE:	SHEET 1	OF 5 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		

MODEL: Schedules-1 [Sheet]
FILE NAME: c:\pawork\pawdoh\hrtzaki\ud910057\DT74A59-sheets-Schedules.dgn

PAVING SCHEDULE (CONTINUED)			HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	HOT-MIX ASPHALT SURFACE REMOVAL, 3¾"	GUTTER REMOVAL	EXCAVATING AND GRADING EXISTING SHOULDERS	BITUMINOUS MATERIALS (TACK COAT)	LONGITUDINAL JOINT SEALANT	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-9.5 FG, N90	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N90	HOT-MIX ASPHALT SHOULDERS, 3¾"	HOT-MIX ASPHALT SHOULDERS, 8"	AGGREGATE WEDGE SHOULDERS, TYPE B	SHOULDER RUMBLE STRIPS, 8 INCH
STATIONING		LENGTH														
FROM	TO	FEET	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	UNIT	POUND	FOOT	TON	TON	SQ YD	SQ YD	TON	FOOT
142+00.00	142+03.28	-	STATION EQUATION													-
142+03.28	548+00.00	40596.7	-	-	117279.4	-	-	-	79163.6	40596.7	11493.4	13135.3	-	-	2225.0	-
548+00.00	548+03.49	-	STATION EQUATION													-
548+03.49	558+08	1004.5	-	-	2901.9	-	-	-	1958.8	1004.5	284.4	325.0	-	-	50.3	-
558+08	559+06	98.0	-	-	283.1	-	-	-	191.1	98.0	27.7	31.7	-	-	5.2	-
559+06	559+41	35.0	-	-	-	101.1	-	-	68.3	35.0	9.9	11.3	-	-	0.7	-
559+41	584+03	2462.0	-	-	-	6565.3	-	-	4431.6	2462.0	643.4	735.3	-	-	0.0	-
584+03	585+40	137.0	-	-	-	426.2	-	-	287.7	137.0	41.8	47.7	-	-	3.9	137.0
585+40	585+80	40.0	-	-	-	148.9	-	-	100.5	40.0	12.2	13.9	24.4	-	0.6	80.0
585+80	587+40	160.0	-	-	-	693.3	-	-	468.0	160.0	48.8	55.8	195.6	-	0.0	230.0
587+40	593+69.12	629.1	-	-	-	1957.3	-	-	1321.2	629.1	191.8	219.2	-	-	7.6	629.1
593+69.12	594+34.17	-	STATION EQUATION													-
594+34.17	595+87	152.8	-	-	-	475.5	-	-	320.9	152.8	46.6	53.3	-	-	1.7	152.8
595+87	596+22	35.0	-	-	-	97.2	-	-	65.6	35.0	9.5	10.9	-	-	2.0	-
596+22	625+61	2939.0	-	-	8490.4	-	-	-	5731.1	2939.0	832.1	950.9	-	-	158.0	-
625+61	626+05	44.0	-	-	141.8	-	-	-	95.7	44.0	13.9	15.9	-	-	2.5	-
626+05	657+08	3103.0	-	-	11205.3	-	-	-	7563.6	3103.0	1098.1	1255.0	-	-	174.6	6133.0
657+08	657+43	35.0	-	-	-	126.4	-	-	85.3	35.0	12.4	14.2	-	-	2.0	70.0
657+43	658+99	156.0	-	52.0	-	624.0	-	-	280.8	156.0	40.8	46.6	-	-	11.8	312.0
658+99	665+44	645.0	-	-	-	-	-	-	-	-	-	-	-	-	0.0	-
665+44	667+00	156.0	-	52.0	-	624.0	-	-	280.8	156.0	40.8	46.6	-	-	11.8	312.0
667+00	667+35	35.0	-	-	-	124.4	-	-	84.0	35.0	12.2	13.9	-	-	2.0	70.0
667+35	680+14	1279.0	-	-	4547.6	-	-	-	3069.6	1279.0	445.7	509.3	-	-	72.8	2558.0
680+14	724+20.41	4406.4	-	-	15667.2	-	-	-	10575.4	4406.4	1535.4	1754.7	-	-	242.1	8331.8
724+20.41	724+36.12	-	STATION EQUATION													-
724+36.12	732+66	829.9	-	-	2950.7	-	-	-	1991.7	829.9	289.2	330.5	-	-	47.3	1659.8
732+66	733+01	35.0	124.4	46.2	-	-	-	-	84.0	35.0	12.2	13.9	-	-	2.0	70.0
TOTALS:			357.8	404.4	204144.7	14136.0	3964.0	40.0	146835.7	71959.6	21296.8	24339.2	220.0	1321.3	3942.3	35935.8

 REVISED SHEET 1-6-2025

	USER NAME = kaleb.hirtzel	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					774	(101, 102) RS-2	Shelby	43	9
		CHECKED -	REVISED -					CONTRACT NO. 74A59				
	PLOT DATE = 9/4/2024	DATE -	REVISED -		SCALE:	SHEET 2	OF 5	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	