



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

December 30, 2024

SUBJECT: FAI Route 74 (I-74) FAP Route 729 & FAU Route 7029 (Lynch Rd.)
Project NHPP-GFGL(994)
Section 92(12,12-1)RS-2
Vermilion County
Contract No. 70A55
Item No. 132, January 17, 2025 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised page iii of the Table of Contents to the Special Provisions.
3. Added page 151 to the Special Provisions.
4. Revised sheets 9, 10, 12, 38, 52, and 91-94 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

AUTOMATED FLAGGER ASSISTANCE DEVICES (BDE)	66
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE)	67
CEMENT, FINELY DIVIDED MINERALS, ADMIXTURES; CONCRETE, AND MORTAR (BDE)	68
COMPENSABLE DELAY COSTS (BDE)	78
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	81
FUEL COST ADJUSTMENT (BDE)	84
GRADING AND SHAPING DITCHES (BDE).....	86
HOT-MIX ASPHALT (BDE).....	86
HOT-MIX ASPHALT – LONGITUDINAL JOINT SEALANT (BDE).....	88
PERFORMANCE GRADED ASPHALT BINDER (BDE)	89
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)	93
SEEDING (BDE).....	95
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE).....	100
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE)	103
SPEED DISPLAY TRAILER (BDE)	104
STEEL COST ADJUSTMENT (BDE)	105
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	108
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....	108
SUBMISSION OF BIDDERS LIST INFORMATION (BDE)	109
SUBMISSION OF PAYROLL RECORDS (BDE)	109
SURFACE TESTING OF PAVEMENTS – IRI (BDE).....	110
TRAINING SPECIAL PROVISIONS (BDE)	116
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION.	119
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE).....	121
WEEKLY DBE TRUCKING REPORTS (BDE).....	121
WORK ZONE TRAFFIC CONTROL DEVICES (BDE).....	121
WORKING DAYS (BDE)	123
PROJECT LABOR AGREEMENT	124
SWPPP	142
BIAXIAL GEOGRID	151

Revised December 30, 2024

BIAXIAL GEOGRID

Description. This work shall consist of furnishing and installing Biaxial Geogrid at locations as shown in the contract plans and in accordance with the manufacturer's recommendations and Section 210 except as modified herein.

Materials. The Biaxial Geogrid shall be composed of extruded polypropylene that is punched and drawn in two directions and meet the following minimum average roll values (MARV) in accordance with ASTM D4759-02:

- 1) Tensile Strength at 2% Strain determined in accordance with ASTM D6637-10 Method A: MD Value = 410 lb/ft XMD Value = 620 lb/ft
- 2)
- 3) Tensile Strength at 5% Strain determined in accordance with ASTM D6637-10 Method A: MD Value = 810 lb/ft XMD Value = 1,340 lb/ft
- 4)
- 5) Ultimate Tensile Strength determined in accordance with ASTM D6637-10 Method A: MD Value = 1,310 lb/ft XMD Value = 1,970 lb/ft
- 6)

The Biaxial Geogrid aperture shall meet the following nominal dimensions:

MD Value = 1.0 in

XMD Value = 1.3 in

Method of Measurement. Biaxial Geogrid will be measured for payment in place and the area computed in square yards (square meters)

Basis of Payment. Biaxial Geogrid will be paid for at the contract unit price per square yard (square meter) for BIAXIAL GEOGRID.

Added December 30, 2024