

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	112 N-2	DUPAGE	42	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	90% FED. 10% STATE ROADWAY 1000-2A	90% FED. 5% STATE 5% WARRENSVILLE SIGNALS Y031-1F	100% WARRENSVILLE F.P.D. PRE-EMPTION Y031-3D		
20200500	EARTH EXCAVATION (WIDENING)	CU YD	80	80				
20201550	SUB-BASE GRANULAR MATERIAL, TYPE B	CU YD	25	25				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	30	30				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	0.6	0.6				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	0.6	0.6				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	0.6	0.6				
25200110	SODDING, SALT TOLERANT	SQ YD	30	30				
25200200	SUPPLEMENTAL WATERING	UNIT	0.3	0.3				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5	5				
40600300	AGGREGATE (PRIME COAT)	TON	24	24				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	4	4				
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	825	825				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	125	125				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	301	301				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	1170	1170				
42001300	PROTECTIVE COAT	SQ YD	300	300				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	70	70				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	560	560				
42400800	DETECTABLE WARNINGS	SQ FT	48	48				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	11715	11715				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	70	70				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	615	615				
44000600	SIDEWALK REMOVAL	SQ FT	925	925				
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	5815	5815				
44201729	CLASS D PATCHES, TYPE II, 7 INCH	SQ YD	70	70				
44201733	CLASS D PATCHES, TYPE III, 7 INCH	SQ YD	100	100				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	90% FED. 10% STATE ROADWAY 1000-2A	90% FED. 5% STATE 5% WARRENSVILLE SIGNALS Y031-1F	100% WARRENSVILLE F.P.D. PRE-EMPTION Y031-3D		
44201735	CLASS D PATCHES, TYPE IV, 7 INCH	SQ YD	66	66				
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	56	56				
44201839	CLASS D PATCHES, TYPE II, 16 INCH	SQ YD	70	70				
44201843	CLASS D PATCHES, TYPE III, 16 INCH	SQ YD	100	100				
44201845	CLASS D PATCHES, TYPE IV, 16 INCH	SQ YD	60	60				
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2720	2720				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	12	12				
55039700	STORM SEWERS TO BE CLEANED	FOOT	300	300				
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	2	2				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	2	2				
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	501	501				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1230	1230				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	290.4	290.4				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3820	3820				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	660	660				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	200	200				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	175	175				
* 72000100	SIGN PANEL - TYPE 1	SQ FT	31.5		31.5			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	290.4	290.4				

* SPECIALTY ITEMS

NP = NON-PARTICIPATING
* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
IL 59 AT BATAVIA ROAD