

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	112 N-2	DUPAGE	42	4
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		90% FED. 10% STATE ROADWAY 1000-2A	90% FED. 10% STATE 5% WARRENVILLE SIGNALS Y031-1F	100% WARRENVILLE F.P.D. PRE-EMPTION Y031-3D			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3820	3820					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	660	660					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	200	200					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	175	175					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	87	87					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	87	87					
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	730	730					
81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	141	141					
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	50	50					
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	114	114					
81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	35	35					
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	307	307					
81400100	HANDHOLE	EACH	7	7					
81400200	HEAVY-DUTY HANDHOLE	EACH	4	4					
81400300	DOUBLE HANDHOLE	EACH	1	1					
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	884	884					
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1					
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1	1					
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1261	1261					
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1840	1840					
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2563	2563					

* SPECIALTY ITEMS

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		90% FED. 10% STATE ROADWAY 1000-2A	90% FED. 10% STATE 5% WARRENVILLE SIGNALS Y031-1F	100% WARRENVILLE F.P.D. PRE-EMPTION Y031-3D			
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1763	1763					
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2099	2099					
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	55	55					
87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	2	2					
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	2	2					
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2	2					
87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1	1					
87700200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT.	EACH	1	1					
87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	2	2					
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16	16					
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4	4					
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	4	4					
87800300	CONCRETE FOUNDATION, TYPE E 24-INCH DIAMETER	FOOT	20	20					
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	30	30					
87900200	DRILL EXISTING HANDHOLE	EACH	2	2					
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	8	8					
88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2	2					
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	2	2					
88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2	2					
88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2	2					
88100400	PEDESTRIAN SIGNAL HEAD, 2-FACE, BRACKET MOUNTED	EACH	2	2					

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
IL 59 AT BATAVIA ROAD

PLOT DATE: 11/7/2007

11/7/2007 08:00:00 AM C:\projects\1033088\session.ccd