

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	112 N-2	DUPAGE	42	5
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		90% FED. ROADWAY 1000-2A	90% FED. STATE SIGNALS WARRENVILLE Y031-1F	PRE-EMPTION Y031-3D 100% WARRENVILLE F.P.D.			
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	10		10				
88500100	INDUCTIVE LOOP DETECTOR	EACH	8		8				
88600100	DETECTOR LOOP, TYPE I	FOOT	552		552				
88700200	LIGHT DETECTOR	EACH	2			2			
88700300	LIGHT DETECTOR AMPLIFIER	EACH	1			1			
88800100	PEDESTRIAN PUSH-BUTTON	EACH	6		6				
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		1				
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	1557		1557				
X0325737	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1		1				
X3540500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 11-3/4"	SQ YD	140	140					
X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		1				
X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	1		1				
X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	1650		1650				
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	1877		1877				
X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	618			618			
NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	14	14					
* X0325890	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM - LEVEL 1	EACH	1		1				
44002264	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 16"	SQ YD	336	336					
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	11,715	11,715					
87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	1		1				
87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	2		2				
88100200	PEDESTRIAN SIGNAL HEAD, 1-FACE, BRACKET MOUNTED	EACH	4		4				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT							

NP= NON-PARTICIPATING
* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
IL 59 AT BATAVIA ROAD

Rev.

11/7/2007 8:40:38 AM C:\Users\jgibson\Documents\60D51\60D51.dwg