PROP. PAY LIMIT OF HMA SURF. REMOVAL FULL THICKNESS OF MILLING TEMP. RAMP (NOTE "C")
(NOTE "E") PROP. HMA SURFACE REMOVAL EXIST. HMA EXIST. PAVEMENT MILLED TEMPORARY RAMP (FOR BUTT JOINT AND HMA TAPER SEE DETAIL BELOW) OPTION 1 PROP. PAY LIMIT OF HMA SURF. REMOVAL FULL THICKNESS OF MILLING SAW CUT (INCLUDED IN THE COST OF HMA SURFACE (NOTE "C") (NOTE "E") PROP. HMA SURFACE REMOVAL REMOVAL - BUTT JOINT) 13/4 (45) FOR E AND F MIX 4'-6" (1.35 m) PAY LIMIT FOR BUTT JOINT 1/2 (40) FOR C AND D MIX (NOTE "D") EXIST. HMA SURF. EXIST. PAVEMENT TEMP, HMA RAME HMA CONSTRUCTED TEMPORARY RAMP (FOR BUTT JOINT AND HMA TAPER SEE DETAIL BELOW) OPTION 2 TYPICAL TEMPORARY RAMP HMA TAPER LENGTH *** SAW CUT (INCLUDED IN THE COST PROP. HMA SURF. CRSE. PROP. HMA BINDER CRSE. 4'-6" (1.35 m) _VARIES _ 13/4 (45) FOR E AND F MIX PAY LIMIT FOR BUTT JOINT (NOTE "D") 11/2 (40) FOR C AND D MIX EXIST. HMA EXIST. PAVEMENT HMA SURF. REMOVAL - BUTT JOINT BUTT JOINT AND

HMA TAPER

TYPICAL BUTT JOINT AND HMA TAPER
FOR MILLING AND RESURFACING

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT PROP. HMA OR PCC SURFACE REMOVAL - BUTT JOINT 30'-0" (9.0 m) (NOTE "A") EXIST. HMA OR PCC SURFACE SAW CUT (INCLUDED IN THE COST OF HMA OR P.C.C. SURFACE REMOVAL 15'-0" (4.5 m) (NOTE "B") - BUTT JOINT) (NOTE "D") 13/4 (45) FOR E AND F MIX 11/2 (40) FOR C AND D MIX * * EXIST. PAVEMENT BUTT JOINT DETAIL TAPER LENGTH * * VARIES PROP. HMA SURF. CRSE. 13/4 (45) FOR E AND F MIX PROP. HMA BINDER CRSE. -11/2 (40) FOR C AND D MIX * * EXIST, PAVEMEN HMA TAPER DETAIL TYPICAL BUTT JOINT AND HMA TAPER FOR RESURFACING ONLY * * PC CONCRETE, HMA OR HMA RESURFACED PAVEMENT.

NOTES

- A: MAINLINE ROADWAYS AND MAJOR SIDE ROADS.
- B: MINOR SIDE ROADS.
- C: THE TEMP. RAMP SHALL BE CONSTRUCTED IMMEDIATELY UPON REMOVAL OF THE EXISTING HMA SURFACE.
- D: THE BUTT JOINT SHALL BE CONSTRUCTED IMMEDIATELY PRIOR TO PLACING THE PROPOSED HMA COURSES.
- E: TAPER THE TEMP, RAMP AT A RATE OF 3'-0" (900 mm) PER 1 INCH (25 mm) OF MILLING THICKNESS.
- F; INSTALLATION AND REMOVAL OF THE 4'-6" (1.35 m) TEMP. RAMP IS INCLUDED IN COST OF HMA SURFACE REMOVAL BUTT JOINT
- G: SEE ARTICLE 406.08 AND 406.14 OF THE STANDARD SPECIFICATIONS FOR "HMA AND/OR PCC SURFACE REMOVAL, BUTT JOINT".
- * SEE TYPICAL SECTIONS FOR MILLING THICKNESS.

** \times 20'-0" (6.1 m) PER 1 (25) RESURFACING (NOTE "A") 10'-0" (3.0 m) PER 1 (25) RESURFACING (NOTE "B")

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

BASIS OF PAYMENT:

THE BUTT JOINT WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER SQUARE YARD (SQUARE METER) FOR "HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT" OR FOR "PORTLAND CEMENT CONCRETE SURFACE REMOVAL- BUTT JOINT".

INAIVIC.	DAIL
M. DE YONG	6-13-90
M. DE YONG	7-3-90
M. DE YONG	3-27-92
R. SHAH	09/09/94
R. SHAH	10/25/94
A. ABBAS	03/21/97
M. GOMEZ	04/06/01
R. BORO	01/01/07

REVISIONS DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

BUTT JOINT AND HMA TAPER DETAILS

SCALE: VERT. NONE HORIZ. PLOT DATE: 11/7/2007

DRAWN BY

BD400-05 (VI=BD32)

REVISION DATE: 01/01/07

CONTRACT NO. 60D51

TOTAL SHEE

COUNTY

DUPAGE

TO STA.

SECTION

112 N-2

STA.