

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	11T	CARROLL	79	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

# SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	80% FED 20% STATE Y007
50800105	REINFORCEMENT BARS	POUND	22897
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	610
50901760	PIPE HANDRAIL	FOOT	103.2
51205200	TEMPORARY SHEET PILING	SQ FT	4537
51500100	NAME PLATES	EACH	5
54010707	PRECAST CONCRETE BOX CULVERT 7' X 7'	FOOT	176
54010808	PRECAST CONCRETE BOX CULVERT 8' X 8'	FOOT	88
54011008	PRECAST CONCRETE BOX CULVERT 10' X 8'	FOOT	98
542A5491	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36"	FOOT	258
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	46
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	82
54213450	END SECTIONS 15"	EACH	2
54213453	END SECTIONS 18"	EACH	1
54214521	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 36"	EACH	4
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	400
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4
63200310	GUARDRAIL REMOVAL	FOOT	852
63500105	DELINEATORS	EACH	14
66411900	TEMPORARY FENCE	FOOT	299
66502300	WOVEN WIRE FENCE REMOVAL	FOOT	3140
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	40
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	10
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	60

\* Speciality Item

PLOT DATE = Fri Oct 12 13:44:08 2007  
 FILE NAME = c:\prow\jens\y\2006\64082\summary.dgn  
 USER NAME = c:\prow\jens\y\2006\64082\summary.dgn