

# GENERAL NOTES

ROUTE NO.	SEC.	COUNTY	TOTAL SHEETS	SHEET NO.
FAP 642 (IL 78)	11T	Carroll	79	6
FED ROAD DIST. NO.	ILLINOIS	PROJECT		
Contract #64D82				

Right-of-way markers will be erected with the back face of the marker on the right-of-way line unless the new right-of-way line has been surveyed and pinned, in which instance the right-of-way markers will be erected 300 mm (12 inches) inside the new right-of-way line.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123. The following listed utilities located within the project limits or immediately adjacent to the project construction limits are members of JULIE:

Gallatin River Communications  
Jo-Carroll Energy

CADD data will be available to Contractors and Consultants working on this project. This information will be provided upon request as MicroStation CADD files and Geopak coordinate geometry files ONLY. If data is required in other formats it will be your responsibility to make these conversions. If any discrepancy or inconsistency arises between the electronic data and the information on the hard copy, the information on the hard copy should be used. Contact the District's Project Engineer to request these files.

Tree replacement layout to be performed by the District Landscape Architect.

Each tree shall receive five foot diameter of mulch, 4 inches thick, with weed barrier fabric around the base to be included in the cost of the tree.

The boring logs for this structure indicate that groundwater levels may encroach on the construction limits of this culvert. It shall be the responsibility of the contractor to control the ground water and divert the stream flow during construction in order to keep the construction area free of water. The method of controlling the water shall be subject to approval of the Engineer and the cost shall be included in the contract unit price for Class "SI" Concrete.

Bituminous and Aggregate prime coat shall be placed in accordance with Section 406 of the Standard Specifications. The cost of the prime coats shall be included in the contract unit price per metric ton (ton) for SURFACE COURSE of the type specified.

The Contractor shall contact Arlo Paxton at home # 815/541-4835 or cell # 815/947-2593 prior to removal of fence at the following locations:

Sta. 800+00 to Sta. 807+24.69 Lt.  
Sta. 812+00 to Sta. 815+00 Lt.

The Contractor shall use a Narrow Impact Attenuator at the following locations in Stage 3 of construction of culverts

Sta. 801+47 and 805+74.24;  
Sta. 802+12.84 Lt.  
Sta. 806+49.94 Lt.