



F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
786	(109) BR	LASALLE	351	18
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

EXISTING DRAINAGE STRUCTURES AND STORM SEWER SCHEDULE											
STATION	OFFSET	MANHOLES TO BE ADJUSTED (EACH)	REMOVING MANHOLES (EACH)	REMOVING INLETS (EACH)	INLETS TO BE ADJUSTED (EACH)	VALVE VAULTS TO BE ADJUSTED (EACH)	CATCH BASIN REMOVAL (EACH)	STORM SEWER REMOVAL 12" (FOOT)	STORM SEWER REMOVAL 24" (FOOT)	STORM SEWER REMOVAL 30" (FOOT)	PIPE CULVERT REMOVAL (FOOT)
IL-170											
62+62.7	15.4' RT				1						
62+68.2	22.3' RT	1									
67+00	14.0' LT	1							3		
67+03	39' LT				1						
67+27	49.6' RT	1							68		22
67+34.6	42.5' RT					1					
67+36.9	35.5' LT				1						
67+67	32' RT			1				31		82	
67+67	39' RT		1					8			
67+68	1' RT			1							
68+30	37' RT			1							
68+49	8' RT			1				35			
68+49	52' RT		1					23			
69+27	6' RT						1				
70+27.6	10.8' RT						1	35			
70+44	12.2' RT							9			
70+57.8	50' RT			1						25	
70+59.7	23.4' RT			1							
70+60.7	20' RT										
70+62.3	13.8' RT		1								
87+86	36.2' RT										20
87+92.6	44.3' RT										
88+01	55.5' RT			1							
DUPONT ROAD											
94+61.3	21.2' LT										
94+61.4	15.6' LT			1							
RIVER ROAD											
18+80	41' RT										53
TOTALS:		3	3	8	3	1	2	141	71	107	95

STA. TO STA.	IL Route 170 STREET EARTHWORK SUMMARY														
	EARTH EXCAVATION (CU. YD.)					EARTH EXCAVATION ADJUSTED (* 0.75) (CU. YD.)					EMBANKMENT (CU. YD.)				
	STAGE 1 - Phase 1	STAGE 1 - Phase 2	STAGE 2 - Phase 1	STAGE 2 - Phase 2	STAGE 3	STAGE 1 - Phase 1	STAGE 1 - Phase 2	STAGE 2 - Phase 1	STAGE 2 - Phase 2	STAGE 3	STAGE 1 - Phase 1	STAGE 1 - Phase 2	STAGE 2 - Phase 1	STAGE 2 - Phase 2	STAGE 3
IL RTE. 170 (NORTH) STA. 62+41.06 - STA. 76+50.00	0	423	139	2,010	269	0	317	104	1,508	202	8,436	4,273	0	4,176	1,110
IL RTE. 170 (SOUTH) STA. 82+26.91 - STA. 100+00	5,673		646	83	4,228	4,255		485	62	3,171	17,080		4,762	21	1,134
DUPONT ROAD STA. 140+50 - STA. 154+00	2,914	19	835			2,186	14	626			28,008	718	575		
RIVER ROAD STA. 17+50 - STA. 25+45	628		4,580	1,340		471		3,435	1,005		2,061		1,899	623	
TOTAL BY STAGE:	9,215	442	6,200	3,433	4,497	6,911	332	4,650	2,575	3,373	55,585	4,991	7,236	4,820	2,244
TOTAL:					23,787					17,840					74,876

STA. TO STA.	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (FURNISHED EXCAVATION) (CU. YD.)					TOPSOIL REMOVAL (CU. YD.)				
	STAGE 1 - Phase 1	STAGE 1 - Phase 2	STAGE 2 - Phase 1	STAGE 2 - Phase 2	STAGE 3	STAGE 1 - Phase 1	STAGE 1 - Phase 2	STAGE 2 - Phase 1	STAGE 2 - Phase 2	STAGE 3
	IL RTE. 170 (NORTH) STA. 62+41.06 - STA. 76+50.00	-8,436	-3,956	104	-2,669	-908	0	0	0	2,560
IL RTE. 170 (SOUTH) STA. 82+26.91 - STA. 100+00	-12,825	0	-4,278	41	2,037	0		0	0	0
DUPONT ROAD STA. 140+50 - STA. 154+00	-25,823	-704	51	0	0	0	0	0		
RIVER ROAD STA. 17+50 - STA. 25+45	-1,590	0	1,536	382	0	0		0	0	
TOTAL BY STAGE:	-48,674	-4,660	-2,586	-2,245	1,129	0	0	0	2,560	0
TOTAL:					-57,036					2,560

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: 1" = 20'

DATE: OCTOBER, 2007

DRAWN BY: CJO
CHECKED BY: JCL

PLOT DATE = 10/1/2007
FILE NAME = 171118
PLOT SCALE = 1/8" = 1'-0"
USER NAME = Project