



F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
786	(109) BR	LASALLE	351	22
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PROPOSED DRAINAGE STRUCTURES AND STORM SEWER SCHEDULE

STATION	OFFSET	INLET TYPE A TYPE 1 F&L OPEN (EACH)	INLET TYPE A TYPE 3 F&G (EACH)	INLET TYPE A TYPE 8 GRATE (EACH)	INLET TYPE B TYPE 3 F&G (EACH)	GRATES TYPE A (EACH)	MANHOLE TYPE A 4' DIA TYPE 3 F&G (EACH)	MANHOLE TYPE A 5' DIA TYPE 1 FR. CL (EACH)	MANHOLE TYPE A 6' DIA TYPE 1 FR. CL (EACH)	SS WATER MAIN 12" (FEET)	SS WATER MAIN 30" (FEET)	PIPE DRAIN 12" (FEET)	RCP SS TYPE 1 12" (FEET)	RCP SS TYPE 2 12" (FEET)	RCP SS TYPE 2 24" (FEET)	SS, 24" CLASS A W/ STEEL CASING JACKED IN PLACE (FEET)	RCP SS TYPE 2 30" (FEET)	RCP SS TYPE 2 42" (FEET)	PIPE CULVERT CLASS D 12" (FEET)	PIPE CULVERT CLASS D 15" (FEET)	PIPE CULVERT CLASS D 30" (FEET)	TEMPORARY CULVERT, 24" (FEET)	PIPE CULVERT REMOVAL (FEET)	CONCRETE END SECTIONS 12" (EACH)	CONCRETE END SECTIONS 24" (EACH)	CONCRETE END SECTIONS 30" (EACH)	CONCRETE END SECTIONS 42" (EACH)	END SECTIONS 12" (EACH)	END SECTIONS 15" (EACH)	END SECTIONS 30" (EACH)	TRENCH BACKFILL (CU YD)					
DUPONT																																				
141+00	14.75 LT					1																			1											
141+00	99.4 LT																								1											
143+43.9	59.2 RT																								1											
143+48.5	68.7 LT																								1											
PIPES																																	0.1			
141+00	30 LT											81																					63.6			
143+45	0																																			
147+91.7	39 LT																																	1		
148+56.5	39 LT																																	1		
147+89.3	34 RT																																	1		
148+34.7	34 RT																																	1		
PIPES																																				
148+25	39 LT																			66														11.6		
148+11.5	34 RT																				44													2.0		
RIVER																																				
20+00	36 RT					1																														
19+68.9	60.8 RT																																		1	
19+13	50.0 RT																																			
18+63.1	50.0 RT																																			
19+62.7	51.4 LT																																		1	
PIPES																																				
20+00	36 RT																																		5.4	
19+62.7	51.4 LT																				40														117.0	
18+63.1	50 RT																																		19.2	
19+50	180 LT																																		22.2	
20+03	19.5 RT																																			
21+59.3	51.3 RT																																		1	
20+15	32 LT					1																														
22+00	0 RT																																			
25+01.3	48 LT																																			
24+78.8	50 RT																																			
PIPES																																				
20+03	19.5 RT																																			0.0
20+15	32 LT																																			38.7
25+01.3	48 LT																																			46.4
TOTALS:		1	6	6	2	1	1	7	2	4	107	180	81	155	269	168	816	234	106	96	124	149	42	4	5	1	2	5	2	4			1028.2			

PLOT DATE = Nov 01, 2007 - 11:56:03 AM  
 FILE NAME = c:\projects\app5782\consult\phase 2\schedule.dgn  
 PLOT SCALE = 1/8" = 1' IN.  
 USER NAME = schwenkerg

REVISIONS	
NAME	DATE
IDOT	10-30-07

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**

SCALE: 1" = 20'

DATE OCTOBER, 2007

DRAWN BY CJO  
CHECKED BY JCL

**REVISED 10-30-07 MJ**