

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1380	*	PEORIA	16	3
STA. 46+00		TO STA. 49+00		
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

D4 SCOUR MITIGATION 2008

SUMMARY OF QUANTITIES

100% STATE SAFETY-2A PEORIA COUNTY				
CODE NO.	ITEM	UNIT	RURAL	TOTAL
20200100	EARTH EXCAVATION	CU YD	113	113
20300100	CHANNEL EXCAVATION	CU YD	52	52
25000210	SEEDING, CLASS 2	ACRE	1.0	1.0
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90	90
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90	90
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90	90
28100209	STONE RIPRAP, CLASS A5	TON	690	690
28200200	FILTER FABRIC	SQ YD	290	290
28400100	GABIONS	CU YD	191	191
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	34	34
63301000	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL	FOOT	100	100
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	LSUM	1.0	1.0
X0301852	DEWATERING STRUCTURE NO. 1	EACH	1.0	1.0
X0322584	REVTMENT MAT REMOVAL	SQ YD	614	614
X0323655	GABION ANCHOR STAKE	EACH	82	82
67100100	MOBILIZATION	L SUM	1	1

PLOT DATE *
FILE NAME *
PLOT SCALE *
REFERENCE *
SHEET *
SCALE *
DATE *

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT.
DATE: HORIZ.

DRAWN BY MJH
CHECKED BY