

| | | | | |
|---------------------|----------|------------------|--------------|-----------|
| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 685 | (113)B-3 | HANCOCK | 48 | 11 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

PAVEMENT

| LOCATION | AGGREGATE BASE COURSE TYPE A, 8" | HOT-MIX ASPHALT BASE COURSE, 10" | HOT-MIX ASPHALT BASE COURSE WIDENING, 10" | AGGREGATE (PRIME COAT 4*/SQ. YD.) | BITUMINOUS MATERIALS (PRIME COAT 0.00038 TON/SQ. YD) | HOT-MIX ASPHALT BINDER COURSE | HOT-MIX ASPHALT SURFACE COURSE MIX C, N50 | LEVELING BINDER (MACHINE METHOD), N50 |
|------------------------|----------------------------------|----------------------------------|---|-----------------------------------|--|-------------------------------|---|---------------------------------------|
| STATION TO STATION | SQ. YD. | | | TON | | | TON | TON |
| APPLE RIVER ROAD | | | | | | | | |
| 10+80.79 14+97.76 | 1,488.9 | | | | 0.53 | 208.1 | 115.6 | |
| 15+54.67 17+25.00 | 822.2 | | | | 0.27 | 110.9 | 58.8 | |
| 17+25.00 17+42.42 | | 55.0 | | | | | 3.6 | |
| IL RTE 96 | | | | | | | | |
| 118+35.3 119+05.7 | | 190.8 | | | | | | |
| 116+20.0 120+40.0 LT | | 306.0 | | | | | | |
| IL RTE 96 | | | | | | | | |
| 115+00.00 118+63.80 RT | | | 175.3 | | | | | |
| 118+93.59 122+00.00 RT | | | 135.4 | | | | | |
| 115+00.00 116+20.00 LT | | | 50.6 | | | | | |
| 120+40.00 122+00.00 LT | | | 67.5 | | | | | |
| 118+43.30 119+17.72 RT | | | 33.1 | | | | | |
| IL RTE 96 | | | | | | | | |
| 114+00 115+00 | | | | 0.25 | 0.06 | | 20.65 | 9.6 |
| 115+00 122+00 | | | | 5.0 | 0.97 | | 172.0 | 145.5 |
| 122+00 123+00 | | | | 0.25 | 0.06 | | 20.65 | 9.6 |
| TOTAL | 2,132 | 552 | 462 | 5.5 | 1.9 | 319 | 392 | 165 |

AGGREGATE SHOULDER, TYPE B

| LOCATION | TON |
|-------------------------------|-------|
| IL RTE 96 | |
| STA. 114+00 TO STA. 115+00 LT | 11.6 |
| STA. 115+00 TO STA. 116+72 LT | 14.6 |
| STA. 117+95 TO STA. 122+00 LT | 34.3 |
| STA. 122+00 TO STA. 123+00 LT | 5.6 |
| STA. 114+00 TO STA. 115+00 RT | 11.4 |
| STA. 115+00 TO STA. 117+65 RT | 22.5 |
| STA. 119+07 TO STA. 122+00 RT | 24.9 |
| STA. 122+00 TO STA. 123+00 RT | 11.6 |
| APPLE RIVER RD. | |
| STA. 10+81 TO STA. 15+12 LT | 38.4 |
| STA. 10+81 TO STA. 14+63 RT | 35.8 |
| STA. 15+90 TO STA. 16+67 LT | 10.1 |
| STA. 15+39 TO STA. 16+67 RT | 12.0 |
| TOTAL | 232.8 |

HOT-MIX ASPHALT SHOULDERS

| LOCATION | TON |
|-------------------------------|------|
| IL RTE 96 | |
| STA. 115+00 TO STA. 116+73 LT | 11.2 |
| STA. 117+95 TO STA. 122+00 LT | 37.9 |
| STA. 115+00 TO STA. 117+66 RT | 14.9 |
| STA. 119+06 TO STA. 122+00 RT | 16.4 |
| TOTAL | 82.0 |

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE
DATE: 7/07

DRAWN BY: SGL
CHECKED BY: FML