

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
685	(113)B-3	HANCOCK	48	14
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PAINT PAVEMENT MARKING - LINE 5''

LOCATION	WHITE	YELLOW
	FOOT	FOOT
IL RTE 96 STA. 114+00 TO STA. 123+00	1,403.4	225
APPLE RIVER RD. STA. 10+81 TO STA 17+42	1,422.8	1,078
TOTAL	2,827	1,303

TEMPORARY PAVEMENT MARKING - LINE 5''

LOCATION	WHITE	YELLOW
	FOOT	FOOT
IL RTE 96 STA. 114+00 TO STA. 123+00	1,403.4	225
APPLE RIVER RD. STA. 10+81 TO STA 17+42	1,422.8	1,078
TOTAL	2,827	1,303

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B

LOCATION	LINE - 24''	LETTERS & SYMBOLS
	FOOT	SQ. FT.
APPLE RIVER RD. STA. 14+59.70 STA. 15+86.50 STA. 16+40 TO STA. 16+90	29 27.5	109
TOTAL	57	109

SIGN PANEL - TYPE I

LOCATION	SQ. FT.
IL-96 STA. 110+00 W10-3 (30''X30'')	6.25
STA. 125+00 W10-3 (30''X30'')	6.25
APPLE RIVER RD. STA. 7+00 W1-4L (30'' X 30'')	6.25
STA. 14+30 R1-1 (36'' X 36'')	9.0
STA. 14+30 R1-I100 (30'' X 18'')	3.75
STA. 16+00 R1-1 (36'' X 36'')	9.0
STA. 16+00 R1-I100 (30'' X 18'')	3.75
STA. 16+40 W10-1 (36'')	7.1
TOTAL	51.4

TELESCOPING STEEL SIGN SUPPORT

LOCATION	FOOT
IL-96 STA. 110+00 W10-3 (30''X30'')	14.33
STA. 125+00 W10-3 (30''X30'')	14.33
APPLE RIVER RD. STA. 7+00 W1-4L (30'' X 30'')	14.33
STA. 14+30 R1-1 (36'' X 36'')	15.83
STA. 14+30 R1-I100 (30'' X 18'')	15.83
STA. 16+00 R1-1 (36'' X 36'')	15.83
STA. 16+00 R1-I100 (30'' X 18'')	15.83
STA. 16+40 W10-1 (36'')	11.83
TOTAL	86.5

SHORT TERM PAVEMENT MARKING

LOCATION	5'' YELLOW
	FOOT
IL RTE 96 STAGE III 1 APPLICATION ON LEVEL BINDER ☉ SKIP DASH STA. 114+00 TO STA. 123+00	225
STAGE III 1 APPLICATION ON HMA SURFACE ☉ SKIP DASH STA. 114+00 TO STA. 123+00	225
TOTAL	450

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE
DATE: 7/07

DRAWN BY: SGL
CHECKED BY: FML