

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
321	18(N-1,TS)	PIKE	55	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LOCATION OF WORK				ROADWAY IMPROVEMENT	TRAFFIC SIGNALS
				90% FEDERAL 10% STATE	90% FEDERAL 5% STATE 5% CITY
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	I000	Y031-1F
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	132		132
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	12		12
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	3		3
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	26		26
81021540	CONDUIT, AUGERED 1 1/2" DIA., PVC	FOOT	3		3
81021550	CONDUIT, AUGERED 2" DIA., PVC	FOOT	66		66
81021560	CONDUIT, AUGERED 2 1/2" DIA., PVC	FOOT	71		71
81021570	CONDUIT, AUGERED 3" DIA., PVC	FOOT	110		110
81021580	CONDUIT, AUGERED 3 1/2" DIA., PVC	FOOT	54		54
81400100	HANDHOLE	EACH	3		3
81400300	DOUBLE HANDHOLE	EACH	1		1
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	257		257
82104250	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, PHOTO-CELL CONTROL, 250 WATT	EACH	4		4
83057120	LIGHT POLE, WOOD, 25 FOOT, CLASS 4	EACH	1		1
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1
86000100	MASTER CONTROLLER	EACH	1		1
86400100	TRANSCEIVER - FIBER OPTIC	EACH	1		1
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	515		515
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	534		534
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	390		390
87301265	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 9C	FOOT	615		615
87301275	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 12C	FOOT	193		193
87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3 PAIR	FOOT	165		165
87301525	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 6 PAIR	FOOT	202		202
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	16		16
87502680	TRAFFIC SIGNAL POST, ALUMINUM 14 FT.	EACH	2		2
87502700	TRAFFIC SIGNAL POST, ALUMINUM 16 FT.	EACH	2		2
87702830	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 20 FT.	EACH	2		2

PLOT DATE = Dec-10-2007 01:02:27PM
FILE NAME = c:\pwork\sect\485181\sumqty.dgn
PLOT SCALE = 1/8"=1'-0"
USER NAME = laughtinr1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

FAP 321 (US 54/IL 106)
SECTION 18(N-1,TS)
PIKE COUNTY

SCALE: VERT. DRAWN BY
 HORIZ. CHECKED BY
DATE