CONTRACT NO. 72933

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
321	18(N-1,TS)	PIKE	54	33
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SIGN DETAIL
1:50

BORDER
R=2.25"
TH=0.75"

SIGN NUMBER	name
WIDTH x HGHT.	8'-0" x 2'-0"
BORDER WIDTH	0.75"
CORNER RADIUS	2.25"
MOUNTING	Overhead
BACKGROUND	TYPE: Reflective
	COLOR: Green
LEGEND/BORDER	TYPE: Reflective
	COLOR: White /White

SYMBOL	X	Y	WID	HT

Panel Style:Mast Arm.ssi
Dimensions are in inches.tenths

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)

																					LENGTH	SERIES/SIZE
W	A	S	H	I	N	G	T	O	N													E8
9	18	27.6	36.1	44.5	47.9	56.4	64.4	71.9	80.6												77.9	
S	T	R	E	E	T																	E4
36.9	40.9	44.7	48.9	52.7	56.2																22.2	

SIGN DETAIL
1:50



BORDER
R=2.25"
TH=0.75"

SIGN NUMBER	name
WIDTH x HGHT.	6'-6" x 2'-0"
BORDER WIDTH	0.75"
CORNER RADIUS	2.25"
MOUNTING	Overhead
BACKGROUND	TYPE: Reflective
	COLOR: Green
LEGEND/BORDER	TYPE: Reflective
	COLOR: White /White

SYMBOL	X	Y	WID	HT

Panel Style:Mast Arm.ssi
Dimensions are in inches.tenths

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)

																					LENGTH	SERIES/SIZE
F	R	A	N	K	L	I	N															E8
9.4	17	25	34.6	43.1	51.2	58.8	62.2														59.1	
S	T	R	E	E	T																	E4
27.9	31.9	35.7	39.9	43.7	47.2																22.2	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SIGN PANEL

FAP 321 (US 54)
SECTION 18(N-1,TS)
PIKE COUNTY

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = Oct-04-2007 01:06:14PM
FILE NAME = c:\Projects\d655104\trafficsignals.dgn
PLOT SCALE = 42.3529 ' / IN.
USER NAME = laughlin-l