

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1338	05-00083-00-FF	COOK	167	9

SUMMARY OF QUANTITIES				
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT M-8003(512)		

CODED PAY ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	1000-2A			Y030-1E		Y031-1F	Y003
				WISE RD / PLUM GROVE (PARTICIPATING)	WISE ROAD (NON-PARTICIPATING)	CUL-DE-SACS (NON-PARTICIPATING)	LIGHTING		TRAFFIC SIGNALS	LANDSCAPING
				70% FEDERAL 30% LOCAL	100% LOCAL	100% LOCAL	70% FEDERAL 30% LOCAL	100% LOCAL	70% FEDERAL 30% LOCAL	100% LOCAL
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	439	439						
78300100	PAVEMENT MARKING REMOVAL	SQ FT	750	750						
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	50	50						
X • 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1				1			
X • 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L. SUM	1				1			
• 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	926				171		755	
• 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	92						92	
• 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	1573				1544		29	
• 81001100	CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL	FOOT	52						52	
• 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	464				286		178	
• 81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	106						106	
• 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	448				377		71	
• 81019000	CONDUIT PUSHED, 5" DIA., GALVANIZED STEEL	FOOT	225						225	
X • 81400100	HANDHOLE	EACH	6						6	
X • 81400200	HEAVY-DUTY HANDHOLE	EACH	4						4	
X • 81400300	DOUBLE HANDHOLE	EACH	1						1	
• 81603025	UNIT DUCT, 600V, 2-1C NO.4, 1/C NO.4 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	2550				2550			
• 81603085	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.4 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	20250				20250			
• 81702460	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 3/0	FOOT	150				150			
X • 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	12273				11350		923	
• 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	43				43			
• 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	4				4			
X • 82500505	LIGHTING CONTROLLER, SPECIAL	EACH	1				1			
• 83020500	LIGHT POLE, ALUMINUM, TRANSFORMER BASE, 30 FT. M.H., 12 FT. MAST ARM	EACH	39				39			
• 83022500	LIGHT POLE, ALUMINUM, TRANSFORMER BASE, 40 FT. M.H., 12 FT. MAST ARM	EACH	8				8			
X • 83600215	LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	120				120			
X • 83600310	LIGHT POLE FOUNDATION, 30" DIAMETER, SPECIAL	FOOT	12				12			
X • 83600400	POLE FOUNDATION, METAL	EACH	72				72			
• 84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	24				24			
• 84200700	LIGHTING FOUNDATION REMOVAL	EACH	25				25			
• 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	1				1			
• 84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	14				14			
X • 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1						1	

\* INDICATES SPECIALTY ITEMS  
X INDICATES SPECIAL PROVISION

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
DATE 9/28/07  
DRAWN BY DJK  
CHECKED BY JRV