

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1338	05-00083-00-FP	COOK	167	12
SUMMARY OF QUANTITIES				
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT M-80034512		

CODED PAY ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	1000-2A			Y030-1E		Y031-1F	Y003
				WISE RD / PLUM GROVE (PARTICIPATING)	WISE ROAD (NON-PARTICIPATING)	CUL-DE-SACS (NON-PARTICIPATING)	LIGHTING		TRAFFIC SIGNALS	LANDSCAPING
				70% FEDERAL 30% LOCAL	100% LOCAL	100% LOCAL	70% FEDERAL 30% LOCAL	100% LOCAL	70% FEDERAL 30% LOCAL	100% LOCAL
X *	X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	18	12	6				
X •	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	133	133					
X •	X0322859	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	27						27
X	X0323381	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 1, 12"	FOOT	575	575					
X	X0323382	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 1, 15"	FOOT	103	103					
X	X0323383	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 1, 18"	FOOT	133	133					
X	X0323430	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 1, 24"	FOOT	51	51					
X *	X0323449	REMOVE EXISTING WATER VALVE	EACH	2		2				
X	X0323863	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 2, 12"	FOOT	20	20					
X	X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	1072	1072					
X	X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	550	550					
X •	X0325105	IRRIGATION SYSTEM	SQ YD	1305						1305
X *	X0487700	SANITARY SEWER REMOVAL 10"	FOOT	50		50				
X	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	21	21					
X	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	2	2					
X	X4023000	TEMPORARY ACCESS (ROAD)	EACH	16	16					
X •	X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1					1	
X •	X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	1					1	
X •	X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	697					697	
X •	X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	356					356	
X	XX007172	HMA DRIVEWAY PAVEMENT 4 1/4" (HOT-MIX ASPHALT)	SQ YD	113	113					
X	XX007173	HMA DRIVEWAY PAVEMENT 7" (HOT-MIX ASPHALT)	SQ YD	207	207					
X	XX007174	CONCRETE HEADER BAND, 6"	FOOT	1536						1536
X	XX007175	CONCRETE HEADER BAND, 12"	FOOT	400						400
X	XX007176	AGGREGATE SUBGRADE 10"	SQ YD	36227	36227					
X	XX007177	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID, SPECIAL	EACH	1		1				
X	XX007178	INLETS, TYPE A, TYPE 1 FRAME, CLOSED LID, SPECIAL	EACH	5		5				
X	XX007179	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID, SPECIAL	EACH	1		1				
X	60262510	INLETS TO BE ADJUSTED WITH NEW FRAME AND GRATE (SPECIAL)	EACH	1	1					
X *	XX007218	SANITARY MANHOLES TO BE RECONSTRUCTED (SPECIAL)	EACH	2	2					
X *	XX007180	SANITARY MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID, (SPECIAL)	EACH	1	1					
X •	XX007181	VERTICAL IDENTIFIER	EACH	15						15
X •	XX007182	WELDED ALUMINUM TRELLIS	EACH	4						4

* INDICATES SPECIALTY ITEMS
 X INDICATES SPECIAL PROVISION

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DATE 9/28/07
 DRAWN BY DJK
 CHECKED BY JRV