

**SUMMARY OF QUANTITIES**

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2993	05-00094-00-WR	DUPAGE	67	4
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		
PROJECT NO.: M-8003 (707)				

SP	CODED PAY ITEM NUMBER	DESCRIPTION	UNIT OF MEASURE	TOTAL QUANTITY	ROADWAY 1000-2A		HIGHWAY LIGHTING Y030-1E	
					PARTICIPATING	NON-PARTICIPATING	PARTICIPATING	NON-PARTICIPATING
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	158	158	-	-	-
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	18	18	-	-	-
	20101000	TEMPORARY FENCE	FOOT	1,000	1,000	-	-	-
*	20101100	TREE TRUNK PROTECTION	EACH	30	30	-	-	-
*	20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	14	14	-	-	-
	20200100	EARTH EXCAVATION	CU YD	727	727	-	-	-
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1,597	1,597	-	-	-
△	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	496	496	-	-	-
	20800150	TRENCH BACKFILL	CU YD	679	679	-	-	-
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	4,202	4,202	-	-	-
*	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3,487	3,487	-	-	-
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	44	44	-	-	-
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	44	44	-	-	-
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	44	44	-	-	-
*	25100630	EROSION CONTROL BLANKET	SQ YD	3,487	3,487	-	-	-
*	25200110	SODDING, SALT TOLERANT	SQ YD	3,487	3,487	-	-	-
*	25200200	SUPPLEMENTAL WATERING	UNIT	32	32	-	-	-
*	28000400	PERIMETER EROSION BARRIER	FOOT	1,404	1,404	-	-	-
*	28000510	INLET FILTERS	EACH	10	10	-	-	-
	35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	52	52	-	-	-
	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	61	61	-	-	-
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	819	819	-	-	-
	40600300	AGGREGATE (PRIME COAT)	TON	9	9	-	-	-
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	197	197	-	-	-
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	4	4	-	-	-
	40701801	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 6"	SQ YD	3,988	3,988	-	-	-
	42001300	PROTECTIVE COAT	SQ YD	2,486	2,486	-	-	-
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	19,107	19,107	-	-	-
	42400800	DETECTABLE WARNINGS	SQ FT	240	240	-	-	-
	44000100	PAVEMENT REMOVAL	SQ YD	2,384	2,384	-	-	-
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	101	101	-	-	-
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,190	1,190	-	-	-
	44000600	SIDEWALK REMOVAL	SQ FT	4,124	4,124	-	-	-
	44004250	PAVED SHOULDER REMOVAL	SQ YD	1,010	1,010	-	-	-
	44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	45	45	-	-	-
△	550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	311	311	-	-	-
△	550A2340	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 18"	FOOT	10	10	-	-	-
△	550A2360	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 24"	FOOT	371	371	-	-	-
	55019900	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	FOOT	62	62	-	-	-
	55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	142	142	-	-	-
	55021700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 15"	FOOT	48	48	-	-	-
	55021800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 18"	FOOT	48	48	-	-	-
△	55039700	STORM SEWERS TO BE CLEANED	FOOT	26	26	-	-	-
	55100500	STORM SEWER REMOVAL, 12"	FOOT	63	63	-	-	-
*	56300300	ADJUSTING WATER SERVICE LINES	FOOT	190	190	-	-	-
* △	56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	5	5	-	-	-
	60200305	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	8	8	-	-	-
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2	-	-	-
	60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3	-	-	-
△	60224090	MANHOLES, TYPE A, 6'-DIAMETER, WITH SPECIAL FRAME AND GRATE	EACH	1	1	-	-	-

PLAN	DATE
BY	
CHECKED	
DATE	
NO.	

PROFILE	DATE
BY	
CHECKED	
DATE	
NO.	

PLOT DATE = #DATE#  
 FILE NAME = #FILE#  
 PLOT SCALE = #SCALE#  
 USER NAME = #USER#

\* INDICATES SPECIALTY ITEM  
 △ DENOTES SPECIAL PROVISION

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		VILLAGE OF WESTMONT WILLIAMS STREET RECONSTRUCTION  SUMMARY OF QUANTITIES SHEET 1 OF 2  SCALE: N.T.S. DATE: 09/21/07
DRAWN BY: JMT		CHECKED BY: AJB
DATE: 09/21/07		