CONTRACT NO. 83986

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2993	05-00094-00-WR	DUPAGE	67	5
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

PROJECT NO.: M-8003 (707)

SUMMARY OF QUANTITIES

SP	CODED PAY ITEM NUMBER	DESCRIPTION	UNIT OF MEASURE	TOTAL QUANTITY	ROADWAY I000-2A PARTICIPATING	HIGHWAY LIGHTING Y030-1E NON-PARTICIPATING
	60255500	MANHOLES TO BE ADJUSTED	EACH	4	4	-
	60260100	INLETS TO BE ADJUSTED	EACH	4	4	-
	60265700	VALVE VAULTS TO BE ADJUSTED	EACH	2	2	-
	60500040	REMOVING MANHOLES	EACH	1	1	-
	60500060	REMOVING INLETS	EACH	2	2	-
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1,919	1,919	-
	67100100	MOBILIZATION	L SUM	1	1	-
△	70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1	-
△	70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1	-
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1,200	1,200	-
	72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	24	24	-
	72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	12	12	-
	72900100	METAL POST - TYPE A	FOOT	48	48	-
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	146	146	-
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2,177	2,177	-
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,967	1,967	-
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	274	274	-
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	136	136	-
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	465	465	-
*	81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	1177	-	1,177
*	81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	302	-	302
*	81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	1258	-	1,258
*	81702410	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 4	FOOT	1258	-	1,258
*	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1173	-	1,173
*	82103150	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 150 WATT	EACH	14	-	14
*	83007300	LIGHT POLE, ALUMINUM, 35 FT. M.H., 8 FT. MAST ARM	EACH	14	-	14
*	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	162	-	162
*	84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	5	-	5
*	B2001124	TREE, CERCIS CANADENSIS (EASTERN REDBUD) 3" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	5	5	-
*	B2004120	TREE, MALUS PRAIRIFIRE (PRAIRIFIRE CRABAPPLE), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	5	5	-
*	B2006220	TREE, SYRINGA RETICULATA (JAPANESE TREE LILAC), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	4	4	-
*	B2010016	TREE, AMELANCHIER CANADENSIS (SHADBLOW SERVICEBERRY), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	4	4	-
△	X0301245	SHOULDER REMOVAL	SQ YD	398	398	-
*△	X0321478	MAINTENANCE OF EXISTING LIGHTING SYSTEM COMPLETE	L SUM	1	-	1
△	X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	185	185	-
*△	X0324637	BASE COVER, LIGHT POLE	EACH	12	-	12
*△	X8380090	BREAKAWAY DEVICE, COUPLING	EACH	56	-	56
*△	X8950130	MODIFY EXISTING LIGHTING CONTROLLER	EACH	1	-	1
△	XX004904	BITUMINOUS DRIVEWAY PAVEMENT, 10"	SQ YD	72	72	-
△	Z0001050	AGGREGATE SUBGRADE, 12"	SQ YD	4,202	4,202	-
△	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	1	1	-
△	Z0076600	TRAINEES	HOURS	500	500	-
*△	X0389863	INTERCEPT EXISTING CONDUIT FOR LIGHT POLE	EACH	5	-	5
*△	X0907144	CLEAN AND RELAMP EXISTING LUMINAIRE	EACH	2	-	2

* INDICATES SPECIALTY ITEM
△ DENOTES SPECIAL PROVISION

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

VILLAGE OF WESTMONT
WILLIAMS STREET RECONSTRUCTION

SUMMARY OF QUANTITIES
SHEET 2 OF 2

SCALE: N.T.S. DRAWN BY: JMT
DATE: 09/21/07 CHECKED BY: AJB

PLAN | SURVEYED | PLOTTED | ALIGNMENT CHECKED | GRADES CHECKED | PLAN PLOT CHECKED | CADD FILE NAME: | NOTE BOOK NO. | BY | DATE

PROFILE | SURVEYED | PLOTTED | GRADES CHECKED | PLAN PLOT CHECKED | STRUCTURE NOTATNS CHKDD | NOTE BOOK NO. | BY | DATE

PLOT DATE = $DATE$
FILE NAME = $FILEN$
PLOT SCALE = $SCALE$
PLOT DATE = $DATE$
USER NAME = $USER$