CONTRACT NO. 83986

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2993	05-00094-00-WR	DUPAGE	67	34
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

PROJECT NO.: M-8003 (707)

DRAINAGE STRUCTURE TABLE

STR NO.	STA	O/S	MH	CB	INL	DIA (FEET)	FRAME	TOP OF GRATE	N. Inv.	E. Inv.	S. Inv.	W. Inv.	SHEET NO.
1	105+50.58	26.02	A *	--	--	6	1	736.39	732.61	--	--	732.51	1
2	107+44.17	26.16	A *	--	--	6	1	737.53	733.69	--	733.38	733.40	2
3	109+15.40	26.16	A *	--	--	4	1	738.41	734.56	--	734.03	734.10	2
4	112+20.73	26.78	A *	--	--	4	1	739.60	--	--	735.79	735.80	3
5	112+24.00	22.94	--	A *	--	4	3	739.12	--	735.81	--	735.90	3
6	112+24.00	-25.27	--	A *	--	4	3	739.12	--	736.00	--	--	3
7	109+24.00	22.72	--	A *	--	4	3	738.00	--	734.12	--	734.30	2
8	109+24.00	-25.40	--	A *	--	4	3	738.00	--	734.49	--	--	2
9	107+48.00	22.58	--	A *	--	4	3	737.10	--	733.42	--	733.50	2
10	107+48.00	-25.48	--	A *	--	4	3	737.10	--	733.64	--	--	2
11	105+47.81	22.43	--	A *	--	4	3	735.91	--	732.50	--	732.50	1
12	105+47.00	-25.57	A *	--	--	6	two 3, special	735.91	--	732.40	--	732.33	1
13	105+46.33	-39.55	A *	--	--	6	1	736.10	732.70	732.30	732.30	--	1
21 (ex)	119+59.20	21.30	existing	--	--	existing	existing	735.33	--	existing	730.83	existing	4
22	118+65.00	25.79	--	A *	--	4	3	735.25	731.25	--	--	--	4

* FLAT TOP SLAB

STORM SEWER TABLE

NO.	U/S STA.	CLASS AND TYPE	D/S STA.	DIA (inches)	LENGTH (feet)	SHEET NO.	UPSTREAM ELEV	DOWN STREAM ELEV	SLOPE (FT/FT)	TRENCH BACKFILL (CY)
1	107+44.17	C A, T-1	105+50.58	24	194	2	733.38	732.61	0.40	139.11
2	109+15.40	C A, T-1	107+44.17	24	172	2	734.03	733.69	0.20	123.33
3	112+20.73	C A, T-1	109+15.40	12	306	2	735.79	734.56	0.40	195.05
4	112+24.00	C A, T-1	112+20.73	12	5	3	735.81	735.79	0.40	2.82
5	112+24.00	C III, T-2	112+24.00	12	48	3	736.00	735.90	0.21	27.04
6	109+24.00	C A, T-1	109+15.40	18	5	2	734.12	734.10	0.40	3.42
7	109+24.00	C III, T-2	109+24.00	15	48	2	734.49	734.30	0.40	31.76
8	107+48.00	C A, T-1	107+44.17	18	5	2	733.42	733.38	0.80	3.42
9	107+48.00	C III, T-2	107+48.00	18	48	2	733.64	733.50	0.29	28.85
10	105+50.58	C A, T-1	105+47.00	24	5	1	732.51	732.50	0.20	3.12
11	105+47.81	C IV, T-1	105+47.00	24	48	1	732.50	732.40	0.21	29.97
12	105+47.00	C IV, T-1	105+47.00	24	14	1	732.33	732.30	0.21	10.04
21	118+65.00	C III, T-2	119+59.20	12	94	4	731.25	730.83	0.45	66.88

PLAN | SURVEYED | PLOTTED | ALIGNMENT CHECKED | STAKED BY | CADD FILE NAME | NOTE BOOK | NO. | BY | DATE

PROFILE | SURVEYED | PLOTTED | GRADES CHECKED | STAKED BY | STRUCTURE NOTATNS CHKD | NOTE BOOK | NO. | BY | DATE

PLOT DATE = $DATE$
FILE NAME = $$FILEN$
PLOT SCALE = $$SCALE$
USER NAME = $$USERN$

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

VILLAGE OF WESTMONT
WILLIAMS STREET RECONSTRUCTION

DRAINAGE SCHEDULES

SCALE: N.T.S. | DRAWN BY: JAL
DATE: 09/21/07 | CHECKED BY: AJB