Location No.	5-09		
Structure No.	5 S 010 1074 L180.76		
County / Route	CHAMPAIGN CO I-74 WB - just East of Prospect Ave.		
Scope of Work	This overhead sign structure is being replaced on existing foundations.	_	
CODE NUMBER	PAY [TEM	UNIT	QUANTITY
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2.00
72000300	SIGN PANEL - TYPE 3	SQFT	507.75
72400330	REMOVE SIGN PANEL - TYPE 3	SOFT	470.50
73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" X 4'-6")	FOOT	83.00
73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	50.00
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00
X7330070	OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	4.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00

Note: new end supports are included in the cost of the OVERHEAD SIGN STRUCTURE - SPAN per Section 733 of the Std. Specs. Pay Item for CMS is for the advanced interstate notice only. CMS shown on Standards are included in the cost of the Standard.

. D-5 OVD SIN STR REPL 2013-09

FILE NAME 2	USER NAME * booklasjj	DESIGNED ~	REVISED ~		SCHEDULE OF QUANTITIES						F.A.I.	SECTION	COUNTY	TOTAL SHEET
cs\pw,work\pwidot\bucklesjj\d@388231\054	5222-Sht-Schedule,dgn	DRAWN -	REVISED ~	STATE OF ILLINOIS	INDIVIDUAL TRUSS LOCATIONS					74	•	Champalan	50 11	
	PLOT SCALE * 48.8208 '/ in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION						<u> </u>	·	CONTRAC	T NO. 46222	
MODEL NAME	PLOT GATE * 8/22/2012	DATE -	REVISED -		SCALE	SHEET	0F	SHEETS	STA.	TO STA.		ILLINOIS FEO.	AID PROJECT	PROJECT