

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FED. / 20% STATE				80% FED. 10% STATE 10% VILLAGE	80% FED. 15% STATE 5% VILLAGE	100% CHICAGO
				CONSTRUCTION CODE						
				ROADWAY 0003 URBAN	BALMORAL 0003 URBAN	BRIDGE 0008 URBAN	LIGHTING 0021 URBAN	TS-MONTROSE 0021 URBAN	TS-LAWRENCE 0021 URBAN	
44000100	PAVEMENT REMOVAL	SQ YD	103,253	103,253						
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	5,567	5,567						
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3,673	3,673						
44004000	PAVED DITCH REMOVAL	FOOT	582	582						
44004250	PAVED SHOULDER REMOVAL	SQ YD	31,567	31,567						
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	390	250	140					
44300200	STRIP RELFECTIVE CRACK CONTROL TREATMENT	FOOT	500	500						
48101620	AGGREGATE SHOULDERS, TYPE B, 10"	SQ YD	1,722	1,222	500					
48203040	HOT-MIX ASPHALT SHOULDERS, 10 3/4"	SQ YD	1,093	1,093						
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	2,730		2,730					
48300515	PORTLAND CEMENT CONCRETE SHOULDERS 10 3/4"	SQ YD	25,872	25,872						
50200100	STRUCTURE EXCAVATION	CU YD	9,505			9,505				
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	885			885				
50300225	CONCRETE STRUCTURES	CU YD	2,260.1			2,242.1				

* SPECIALITY ITEM

HNTB	USER NAME * lsupancheck	DESIGNED	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT
	PLOT SCALE * 1/1	DRAWN	REVISED -									
	DATE * 22-OCT-2012	CHECKED	REVISED -									
	DATE 10/19/12	REVISED -										
Rev. 1-3-13												
SECTION 0105 WRS&HB												
COUNTY COOK												
TOTAL SHEETS 005												
SHEET NO. 9												
CONTRACT NO. 60037												