

SUMMARY OF QUANTITIES

80% FED. / 20% STATE

80% FED. 10% STATE 10% VILLAGE
80% FED. 15% STATE 5% VILLAGE
100% CHICAGO

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0003 URBAN	BALMORAL 0003 URBAN	BRIDGE 0008 URBAN	LIGHTING 0021 URBAN	TS-MONTROSE 0021 URBAN	TS-LAWRENCE 0021 URBAN
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1,240.7			1,240.7			
50300260	BRIDGE DECK GROOVING	SQ YD	2,688			2,688			
50300285	FORM LINER TEXTURED SURFACE	SQ FT	7,774			7,774			
50300300	PROTECTIVE COAT	SQ YD	10,224		7,135	3,089			
50500305	ERECTING STRUCTURAL STEEL	L SUM	1			1			
50500505	STUD SHEAR CONNECTORS	EACH	10,465			10,465			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	500,880			497,680			
50800515	BAR SPLICERS	EACH	719			719			
50901760	PIPE HANDRAIL	FOOT	45						
51100100	SLOPE WALL 4 INCH	SQ YD	1,670			1,670			
51500100	NAME PLATES	EACH	2			2			
52000030	PREFORMED JOINT SEAL 2 1/2"	FOOT	126			126			
52000110	PREFORMED JOINT STRIP SEAL	FOOT	368			368			
52100210	ERECTING ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	20			20			
52100520	ANCHOR BOLTS, 1"	EACH	40			40			

* SPECIALITY ITEM

Rev. 1-3-13

S00-5

HNTB

USER NAME: isupencheck

DESIGNED

REVISED

PLOT SCALE: 1/4"

DRAWN

REVISED

PLOT DATE: 22-OCT-2012

CHECKED

REVISED

DATE 10/19/12

REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE:

SHEET NO.

OF

SHEETS

STA.

TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	0105 WRS&HB	COOK	605	10
CONTRACT NO. 60637				

ILLINOIS FED. AID PROJECT