

SUMMARY OF QUANTITIES

80% FED / 20% STATE

80% FED. 10% STATE 10% VILLAGE
80% FED. 15% STATE 5% VILLAGE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BALMORAL	BRIDGE	LIGHTING	TS-MONTROSE	TS-LAWRENCE
				0003 URBAN	0003 URBAN	0008 URBAN	0021 URBAN	0021 URBAN	0021 URBAN
52100530	ANCHOR BOLTS, 1 1/4"	EACH	40			40			
542A0217	PIPE CULVERTS, CLASS A, TYPE 1, 12"	FOOT	61		61				
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	61		61				
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	3	1	2				
54261430	CONCRETE END SECTION, STANDARD 542001, 30", 1:4	EACH	1		1				
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2		2				
54261615	CONCRETE END SECTION, STANDARD 542001, 15", 1:6	EACH	3	1	2				
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2		2				
54261624	CONCRETE END SECTION, STANDARD 542001, 24", 1:6	EACH	2		2				
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1	1					
54261630	CONCRETE END SECTION, STANDARD 542001, 30", 1:6	EACH	1		1				
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	2		2				
54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	2		2				
550A0050	STORM SEWERS, CLASS A, TYPE 1, 12"	FOOT	407	234	173				
550A0090	STORM SEWERS, CLASS A, TYPE 1, 18"	FOOT	187		187				
550A0140	STORM SEWERS, CLASS A, TYPE 1, 30"	FOOT	64		64				
550A0340	STORM SEWERS, CLASS A, TYPE 2, 12"	FOOT	4,587	4,169	418				
550A0360	STORM SEWERS, CLASS A, TYPE 2, 15"	FOOT	26		26				
550A0380	STORM SEWERS, CLASS A, TYPE 2, 18"	FOOT	1,721	1,721					

* SPECIALITY ITEM

Rev. 1-3-13

S00-6

HNTB

USER NAME: lsupancheck

DESIGNED

REVISED

PLOT SCALE: 1:1

DRAWN

REVISED

PLOT DATE: 22-OCT-2012

CHECKED

REVISED

DATE: 10/19/12

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	0105 WRS&HB	COOK	605	11
CONTRACT NO. 60637				
ILLINOIS FED. AID PROJECT				