

SUMMARY OF QUANTITIES

80% FED. / 20% VILLAGE

80% FED. 10% STATE 10% VILLAGE
80% FED. 15% STATE 5% VILLAGE
100% CHICAGO

CONSTRUCTION CODE

XXXXX

ALSF-2
0043

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0003 URBAN	BALMORAL 0003 URBAN	BRIDGE 0008 URBAN	LIGHTING 0021 URBAN	TS-MONTROSE 0021 URBAN	TS-LAWRENCE 0021 URBAN
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1, (SPECIAL) FLARED	EACH	3	3					
63200310	GUARDRAIL REMOVAL	FOOT	9,229	9,229					
63301210	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	442	442					
63700155	CONCRETE BARRIER, SINGLE FACE, 32 INCH HEIGHT	FOOT	700	700					
63700255	CONCRETE BARRIER, DOUBLE FACE, 32 INCH HEIGHT	FOOT	3,760	3,760					
63700900	CONCRETE BARRIER BASE	FOOT	4,600	4,600					
64300260	IMPACT ATTENUATOR (FULLY REDIRECTIVE, NARROW) TEST LEVEL 3	EACH	3	3					
64407400	CHAIN LINK GATES, 6' X 8' DOUBLE	EACH	1						
64300530	IMPACT ATTENUATORS (PARTIALLY REDIRECTIVE), TEST LEVEL 3	EACH	1		1				
* 66900200	NON-SPECIAL WASTE DISPOSAL	CY YD	132,000	132,000					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	20	20					
* 66900400	SPECIAL WASTE GROUNDWATER DISPOSAL	GALLON	3,424,000	3,424,000					
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	20	20					
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1					
67100100	MOBILIZATION	L SUM	1	1					
* 66901000	BACKFILL PLUGS	CUYD	210	210					
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	464	464					
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	10	10					
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	151	151					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	169	169					

* SPECIALITY ITEM

Rev. 1-3-13

SQ-11

HNTB

USER NAME * lsupencheck	DESIGNED	REVISED -
	DRAWN	REVISED -
PLOT SCALE * 1:1	CHECKED	REVISED -
PLOT DATE * 22-OCT-2012	DATE 10/19/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	0105 WRS&HB	COOK	605	16
CONTRACT NO. 60637				
ILLINOIS FED. AID PROJECT				