

SUMMARY OF QUANTITIES

80% FED. / 20% STATE

80% FED. 80% FED.
10% STATE 15% STATE
10% VILLAGE 5% VILLAGE100%
CHICAGO

CONSTRUCTION CODE

ROADWAY BALMORAL BRIDGE LIGHTING TS-MONTROSE TS-LAWRENCE
0003 0003 0008 0021 0021 0021
URBAN URBAN URBAN URBAN URBAN URBANALSF-2
0043

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0003 URBAN	BALMORAL 0003 URBAN	BRIDGE 0008 URBAN	LIGHTING 0021 URBAN	TS-MONTROSE 0021 URBAN	TS-LAWRENCE 0021 URBAN	ALSF-2 0043
② Z0076600	TRAINEES	Hour	2000	2000						
* X0327519	INNERDUCT, 1" SOLID WALL, SDR-11	Foot	37,600	37,600						
② Z0076604	TRAINING PROGRAM GRADUATE L TRAINEES	Hour	2000	2000						
* XX608162	MAINTAIN LIGHTING SYSTEM	L SUM	1		1					
* X0327516	2-WAY 2-5" PVC DUCT BANK - 1 HIGH BY 2 WIDE	Foot	480		480					
* X0327520	FAA ELECTRICAL HANDHOLE	EACH	14	9						5
* X0327517	15-WAY 15-5" PVC DUCT BANK - 5 HIGH BY 3 WIDE	Foot	1120		1120					
* X0327521	NEW COVER ON EXISTING FAA MANHOLE/HANDHOLE	EACH	10	10						
* X0327522	AGGREGATE SURFACE COURSE, CA -4, 6 INCH	SQ YD	130							130
* X0327523	INSTALL NEW MALSR MG-30 LIGHT TOWER - COMPLETE	EACH	1							1
* X0327524	12 STRAND, TYPE B, MULTI-MODE FIBER OPTIC CABLE, OUTDOOR	Foot	8500	8500						
* X0327525	MULTI-MODE FIBER OPTIC PATCH PANEL, 72 PORT	EACH	2	2						
* X0327526	INSTALL TEMPORARY ALSF-2 MG-20 LIGHT TOWER - COMPLETE	EACH	1							1
* X0327527	RELOCATE ALSF-2 MG-20 LIGHT TOWER - COMPLETE	EACH	1							1
* X0327528	ADJUST WINCH BRACKET ON ALSF-2 TOWER - COMPLETE	EACH	1							1
* X0327529	ALSF-2 FLASHER CONTROL CABLE, 12 PAIR #19, SHIELDED	Foot	350							350
* X0327530	POWER CABLE - L - B24, TYPE C 5 KV, 1/C #6 AWG	Foot	8200							8200
* X0327531	GROUND WIRE - 1/C, #6 AWG, 600V, THWN GREEN	Foot	1000							1000
* X0327532	GUARD WIRE - 1/C, 1/0 AWG, 600V, BARE COPPER	Foot	2440	2200						240
* X0327533	TRACER WIRE - 1/C, #14 AWG, SOLID, INSTALLED, ORANGE	Foot	8500	8500						
* X0327534	CONDUCTOR - ALSF-2 FLASHER POWER CABLE	Foot	350							350
* X0327535	DUCT BANK, 2-WAY, 2" PVC CONDUIT, CONCRETE ENCASED	Foot	8							8
* X0327536	DUCT BANK, 2-WAY, 3" PVC CONDUIT, CONCRETE ENCASED	Foot	15							15
* X0327537	DUCT BANK, 2-WAY, 4" PVC CONDUIT, CONCRETE ENCASED	Foot	2150	2150						
* X0327538	DUCT BANK, 5-WAY (3-WAY 2", 2-WAY 3") PVC CONDUIT WITH 6" SEPERATION, CONDUIT ENCASED	Foot	100							100
* X0327539	DUCT BANK, 6-WAY 2" PVC CONDUIT WITH 6" SEPERATION, CONCRETE ENCASED	Foot	120							120
* X0327540	DUCT BANK, 7-WAY, 2" PVC COATED GALVANIZED RIGID STEEL (GRS) CONDUIT, DIRECTIONALLY BORED	Foot	190							190
* X0327541	DUCT BANK, 2-WAY, 4" PVC COATED GALVANIZED RIGID STEEL (GRS) CONDUIT, DIRECTIONALLY BORED	Foot	726	726						

HNTB

USER NAME: jlp@hntb.com

DESIGNED

REVISED

PLOT SCALE: 1"=100'

DRAWN: MMK

REVISED

PLOT DATE: 22-OCT-2012

CHECKED: LLS

REVISED

DATE: 10/19/12

REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

Rev. 1-3-13

F.A.P.
RTE.
330SECTION
0105 WRS&HBCOUNTY
COOKTOTAL
SHEETS
605SHEET
NO.
34

CONTRACT NO. 60637

ILLINOIS FED. AID PROJECT

SCALE:

SHEET NO. 28 OF 28 SHEETS

STA.

TO STA.